
# ENERGY MANAGEMENT SYSTEM (EMS) STUDY

# FORT BELVOIR, VIRGINIA

Department of the Army Baltimore District, Corps of Engineers



COE Project No:

DACA31-92-D-0061

EYP Project No:

60692.00

DTIC QUALITY INSPECTED 2

1 NOVEMBER 1995 FINAL SUBMITTAL VOLUME 2 OF 2

19971017 100

## DUPLICATE PAGE NUMBERS HAVE DIFFERENT NAMES

AND DATES - THEY WERE RENUMBERED

PER: DAVE OPLER

(202) 471-5000

EINHORN YAFFEE PRESCOTT

ARCHITECTURE AND ENGINEERING

WASHINGTON, D.C.

## DEPARTMENT OF THE ARMY

CONSTRUCTION ENGINEERING RESEARCH LABORATORIES, CORPS OF ENGINEERS P.O. BOX 9005 CHAMPAIGN, ILLINOIS 61826-9005

ATTENTION OF:

TR-I Library

17 Sep 1997

Based on SOW, these Energy Studies are unclassified/unlimited. Distribution A. Approved for public release.

Marie Wakeffeld, Librarian Engineering

1 NOVEMBER 1995 FINAL SUBMITTAL VOLUME 2 OF 2

# Energy Management System (EMS) STUDY

Fort Belvoir, Virginia

Prepared by:

EINHORN YAFFEE PRESCOTT ARCHITECTURE AND ENGINEERING, P.C. The Flour Mill 1000 Potomac Street, N.W., Ste. L-1 Washington, DC 20007-3238 (202) 471-5000

PROJECT NUMBER: DACA31-92-D-0061 Delivery Order # 0004

# TABLE OF CONTENTS

## Volume 1 of 2

I.	EXEC	UTIVE SUMMARY	page	I-1
	A.	INTRODUCTION	page 1	I-1
	B.	PURPOSE	page 1	I-1
	C.	BUILDING INFORMATION	page 1	I-1
	, <b>D</b> .	PRESENT ENERGY CONSUMPTION	page 1	I-2
	E.	ENERGY CONSERVATION ANALYSIS	page 1	I-3
	F.	EXTRAPOLATION OF RESULTS	page 1	I-7
	G.	TABULATION OF RESULTS	page ]	I-10
II.	INTRO	DDUCTION	page 1	II-1
	A.	PURPOSE	page 1	II-1
	B.	METHODOLOGY	page ]	II-1
	C.	EMS SYSTEM DESCRIPTIONS	page l page l page l	II-5 II-7
III.	EVAL	UATION OF EMS SYSTEMS		
	A.	BUILDING 200 - ENLISTED MEN'S SERVICE CLUB  1. Existing systems descriptions and comments  2. Analysis of EMS options	page :	III-1 III-1
	В.	BUILDING 219 - FINANCE	page page page	III-16 III-17

FORT BE	LVOIR, V	IRGINIA		1 NOVE	MBER 1995
	C.	BUILI 1. 2. 3.	DING 247 - HUMPHREY'S HALL  Existing systems descriptions and comments  Analysis of EMS options  Recommendations	page III-32 page III-33	
	D.	BUILI 1. 2. 3.	Existing systems descriptions and comments Analysis of EMS options	page III-47 page III-47	
	E.	BUILI 1. 2. 3.	DING 3136 - DAAF OPERATIONS BUILDING Existing systems descriptions and comments Analysis of EMS options Recommendations	page III-61 page III-62	
IV.	APPEN	NDICES	5		
	APPE	NDIX B	A - FIELD SURVEY DATA SHEETS	AWINGS PUT DATA	B-1
Volui	ne 2 o	f 2			
	APPEN APPEN APPEN APPEN APPEN APPEN	NDIX E NDIX F NDIX C NDIX F NDIX I NDIX J	C - CARRIER E20-II BUILDING SIMULATION IN (Building 247, Building 1425 & Building 3136) D - CARRIER E20-II BUILDING SIMULATION RI C - BLCC 4.2 LIFE CYCLE COST ANALYSIS INP D - BLCC 4.2 LIFE CYCLE COST ANALYSIS RES D - COST DATA	ESULTS UT DATA SULTS	E-1 F-1 G-1 H-1

**BUILDING 247** 

\_\_\_\_\_\_

#### TABLE 1. SIMULATION WEATHER DATA DESIGN PARAMETERS

\* = User-defined design parameters. All other values are fixed.

TABLE 2. DRY-BULB TEMPERATURE STATISTICS (F)

Month	Absolute Maximum	Average Maximum	Average	Average Minimum	Absolute Minimum	
January	60.4	39.3	30.7	21.0	-1.9	
February	62.1	42.8	33.1	22.9	7.5	
March	75.5	53.9	43.3	32.4	17.1	
April	85.5	65.7	55.0	44.3	31.2	
May	91.9	73.3	63.5	53.8	40.5	
June	93.5	80.8	70.0	58.8	48.8	
July	91.0	84.9	75.9	66.5	55.8	
August	96.8	85.1	74.3	64.5	49.6	
September	91.6	79.3	69.3	60.0	46.5	
October	84.7	67.5	56.8	46.7	23.4	
November	75. <b>7</b>	56.4	46.6	35.7	17.3	
December	59.0	42.7	36.9	30.9	20.5	

TABLE 3. DAILY TOTAL SOLAR RADIATION STATISTICS

[---- Daily Total Solar ---] [-- Daily Clearness Number --] (BTU/sqft) (Dimensionless)

Month Maximum Average Minimum Maximum Average Minimum

January 1043.4 609.1 137.7 0.648 0.430 0.107

February 1448.6 815.5 79.9 0.685 0.433 0.048

March 1861.2 1183.4 211.6 0.680 0.473 0.094

April 2371.0 1484.8 247.6 0.717 0.479 0.079

May 2579.4 1712.0 355.4 0.711 0.487 0.104

June 2551.8 1890.8 515.8 0.697 0.514 0.140

July 2398.3 1714.6 629.5 0.657 0.478 0.171

August 2378.9 1696.2 708.2 0.694 0.522 0.227

September 1943.6 1307.6 258.0 0.674 0.482 0.094

October 1546.1 977.2 92.6 0.656 0.469 0.045

November 143.4 672.4 129.4 0.647 0.437 0.094

December 803.2 488.0 73.1 0.618 0.382 0.057

Notes: \* All solar data is daily total flux on a horizontal surface.

<sup>\*</sup> Clearness number is (Daily Total Solar)/(Extraterrestrial Solar) Values between 0.70 and 0.80 represent clear conditions.

#### CALENDAR DATA

Prepared By: EINHORN YAFFEE PRESCOTT	12-30-94
HAP v3.04	Page 1 of 1
***********	*********
1	
Calendar Name: Baseline	Day Type Assignments
	Monday = Weekday
January first is on: Saturday	Tuesday = Weekday
	Wednesday = Weekday
Day Type Names	Thursday = Weekday
Day Type 1 = Weekday	Friday = Weekday
Day Type 2 = Saturday	Saturday = Saturday
Day Type 3 = Sunday	Sunday = Sunday
	Holiday = Saturday
Holidays	
January 1 January 17 February 21	May 30 July 4
	December 26

#### SCHEDULE DATA

_				CHEDU.		ľA						
Prepared By: 1	EINHO	RN YA	FFEE .	PRESC	OTT					_	12-3	
HAP v3.04										Page	1 0	
******			****	****	****	****					****	****
Schedule Name	Schedule Name: People Hourly Percentages											
Houx	00	01	02	03	04	05	06	07	08	09	10	11
Hour>	00	01										
DESIGN DAY	1 0	0	0	0	1 0	0	0	0	50	100	100	100
Weekday	0	0	0	j o	0	0	0	0	10	25	40	50
Saturday	i o	0	j o	j o	0	0	0	0	0	0	0	0
Sunday	0	0	j o	0	0	0	0	0	0	0	10	25
	<del></del>		·									
Hour>	12	13	14	15	16	17	18	19	20	21	22	23
DESIGN DAY	100	100	100	100	100	100	100	100	100	75	50	1 0
Weekday	60	60	50 l	40	40	40	50	50	50	50	50	0
Saturday	10	50	50	50	50	50	50	50	50	50	50	0
Sunday	40	50	50	50	50	50	25	0	0	0	0	0
********	<del>-</del>	30 *****	****	****	****	****	1	1	-	****	1 -	***
Schedule Name	: Lia	hts					Hou	rly Pe	ercen	tages		
		<del></del> -			<b></b>							
Hour>	00	01	02	03	04	05	06	07	08	09	10	11
		<del>-</del> -	1 25		25	25	25	<del>-</del> -	75	1100	1100	100
DESIGN DAY	25	25	25	25	25	25	25	50   50	75	100	1100	100
Weekday	25	25	25	1		25	25	30   25	25	25	25	25
Saturday	25	25	25 25	25 25	25   25	25	25	25	25	25	25	25
Sunday	25	25 	25	23 			2J					
Hour>	12	13	14	15	16	17	18	19	20	21	22	23
			<u>-</u>		<u>-</u>			<del>-</del>		- <del>-</del>		
DESIGN DAY	100	100	100	100	100	50	25	25	25	25	25	25
Weekday	100	100	100	100	100	50	25	25	25	25	25	25
Saturday	25	25	25	25	25	25	25	25	25	25	25	25
Sunday	25	25	25	25	25	25	25	25	25	25	25	25
*****	****	****	****	****	****	****	****	****	****		****	****
Schedule Name	: Peo	ple A	udito	rium			Hou:	rly P	ercen	tages		
Hour>	00	01	02	03	l 04	1 05	1 06	07	l 08	09	10	11
HOUL										<del>-</del>		
DESIGN DAY	0	0	0	0	0	0	0	0		100	100	100
Weekday	0	0	0	0	0	0	0	0	10	25	25	25
Saturday	0	0	0	0	0	0	0	0	0	0	0	0
Sunday	0	0	0	0	0	0	0	0	0	0	10	25
									1 20		1 22	1 22
Hour>	12	13	14	15	16 <b></b>	17 	18	19	20 	21	22	23
DESIGN DAY	100	100	100	100	100	100	100	100	100	75	50	0
Weekday	25	25	25	25	25	25	25	25	25	50	50	50
Saturday	10	50	50	50	50	50	50	50	50	50	50	0
Sunday	40	50	50	50	50	50	25	j o	0	0	0	0
******	****	****	****	****	****	****	****	****	****	****	****	****

#### SCHEDULE DATA

Prepared By: EINHORN YAFFEE PRESCOTT       12-30-94         HAP v3.04       Page 2 of 2         ************************************												
Hour>	00	01	02	03	04	05	   06 	07	08	09	10	11 
DESIGN DAY Weekday Saturday Sunday	15   15   15   15	50   10   15   15	100  100   15   15	100  100   15   15	100  100   15  100							
Hour>	12	13 	14	15	16	17	18	19 	20	21	22	23
DESIGN DAY Weekday Saturday Sunday	100  100   15  100	100  100  100   25	100  100  100   15	100  100  100   15	75   50  100   15	50   50  100   15	15   50   15   15					

#### WALL CONSTRUCTION TYPES

Prepared by: EINHORN YAFFEE PRES	SCOTT				2-30-94 Page 1
HAP v3.04 ************************************	*****	*****	*****		_
WALL TYPE 1: (CUSTOM WALL)					
Description: Custom W Absorptivity: 0.900	all				
Layer Description	Thickness	Density	Spec.Ht	R-Val	Weight
Inside surface resistance	-	-	-	0.69	-
1/2-in (13 mm) gypsum board	0.50	50.0	0.26	0.45	2.1
8-in (203 mm) LW concrete block	8.00	38.0	0.20	2.02	25.3
Airspace	1.00	0.0	0.00	0.91	0.0
4-in (102 mm) face brick	4.00	125.0	0.22	0.43	41.7
Outside surface resistance		-			-
Totals	13.50			4.83	69.1
Thickness: in Den		.ft	Weigh		sqft

#### ROOF CONSTRUCTION TYPES

Prepared by: EINHORN YAFFEE PRESCOTT HAP v3.04 ************************************	*****	]	2-30-94 Page 1 *****		
ROOF TYPE 1: (CUSTOM ROOF)	<b></b>				
Description: Rubber Membra Absorptivity: 0.900	ne Roo	f			
Layer Description Thic	kness	Density	Spec.Ht	R-Val	Weight
Inside surface resistance 3/4-in Acoustical Ceiling Tile R-19 (RSI-3.3) batt insulation 22 gage steel deck R-14 (RSI-2.5) board insulation Membrane Roof Outside surface resistance	0.03 2.00 0.00	18.0 0.5 489.0 2.0 0.0	0.12 0.22	19.23 0.00 13.89 0.00 0.33	1.1 0.3 1.4 0.3 0.0
Totals	8.78 		<b></b>	36.03	3.1
Thickness: in Density: R-value : (hr-sqft-F)/BTU Specific				nt: lb/	sqft

#### WINDOW TYPE CONSTRUCTIONS

Prepared by: EINHORN YAFFEE PRESCOTT	12-30-94
HAP v3.04	Page 1
***************	******
WINDOW TYPE 1: (SIMPLE WINDOW)	
Window Description: Double Pane Double Hung Windows	(By sqft)
Height 1.00 ft	
Width 1.00 ft	
Overall U-value: 0.580 BTU/hr/sqft/F	
Overall Shade Coeff: 0.880	

#### ELECTRIC RATE DATA

Prepared by: EI	NHORN YAFFEE PRESCOTT	12-30-94
HAP v3.04		Page 1
**********	***************	*****
BASIC ELECTRIC	RATE INFORMATION	
ELECTRIC RATE	Rate schedule name: Virginia Power - Kwh Currency symbol: \$	Only
INFORMATION:	Type of rate schedule Simple	
THE ORDER TON.	Flat rate 0.0196	8 \$/kWh

#### FUEL RATE DATA

HAP v3.04	NHORN YAFFEE PRESCOTT ***********************************	12-30-94 Page 1
*****	****	******
BASIC FUEL RATE	INFORMATION	
FUEL RATE INFORMATION:	Rate schedule name: Ft. Belvoir Distriction of Structure Symbol: \$ Units of measurement: 1000 lb Fuel conversion factor: 1000.00000 kl Type of rate schedule: Simple Flat rate: 7.98000 \$	BTU/1000 lb

#### FUEL RATE DATA

Prepared by: EI	NHORN YAFFEE PRESCOTT	12-30-94 Page 1
	***************	******
BASIC FUEL RATE	INFORMATION	
FUEL RATE INFORMATION:	Rate schedule name: Washington Gas Rate Currency symbol \$ Units of measurement: Therm Fuel conversion factor: 100.00000 kE Type of rate schedule: Simple Flat rate	3TU/Therm

Prepared by: EINHORN	YAFFEE :	PRESCO'	${ m TT}$					12-30-94
HAP v3.04								Page 1
******	****	*****	***	*****	*****	*****	****	*****
GENERAL			:	SCHEDULES	3			
Name: Basement	Classr	ooms		Lighting	a:	Lights		
Floor Area:	8330.0			Task Lig	-	-		
Building Weight.:								
Windows Shaded?	N	_		Equipmen		_		
Partitions Used.?	N			Misc. Se				
LIGHTING				Misc. La		_		
Overhead Fixture: Re	cessed			INFILTRA:		-		
Lamp Wattage:		W/sqf	t	Cooling	:	0	.00 CFI	M/sqft
Ballast Mult:	1.00	, - 1-		Heating			.00 CFI	
Task Lighting:	0.00	W/sqf	t	Typical			.00 CFI	
PEOPLE		, 4		When Far			N	, <u>-</u>
Occupancy:	200.0	sqft/	per 1	FLOOR				
Activity Level: Of				Туре	:S	lab Be	low Gra	ade
Sensible:		BTU/h	r	Perimete				400.0 ft
Latent		BTU/h		Slab Flo	or Are	a	:	8330.0 sqft
OTHER LOADS		,	_	Floor R	-Value.		:	2.40
Equipment:	0.50	W/saf	t.	Insulat	ion R-v	alue	:	0.00
Misc. Sensible:	0.0	BTU/h	r	Depth of				0.0 ft
Misc. Latent:		BTU/h		Depth Be				6.0 ft
======================================		•		-				========
WALL Gross Area	WALL		INDO		l W	INDOW		Any
Exp (sqft)	Туре	Type	Otv	Shade	Type	Qty	Shade	Doors?
Exp (Sqrc)	-120	-76-						' 
N 1831.0	1	1	522	_	1	0	-	N
s 2134.0	ı	1	421	_	1	0	-	N
E 1040.0	1	1	0	_	1	0	_	N
	:=======	=====	====	=======	======	=====	======	=========
No roof or door data	for thi	s spac	e.					
=======================================				======		=====	=====	========
No partition data for								
<b>F</b>	•	_						

Prepared by: EINHORN YAFFEE PRESCOTT	12-30-94					
HAP v3.04 Page 1						
*********	**********					
GENERAL	SCHEDULES					
Name: Basement Offices	Lighting: Lights					
Floor Area: 1372.0 sqft	Task Lights.: Lights					
Building Weight.: 70.0 lb/sqft	People: People					
Windows Shaded? N	Equipment: People					
Partitions Used.? N	Misc. Sens: People					
LIGHTING	Misc. Latent: People					
Overhead Fixture: Recessed	INFILTRATION					
Lamp Wattage: 3.00 W/sqft	Cooling: 0.00 CFM/sqft					
Ballast Mult: 1.00	Heating: 0.00 CFM/sqft					
Task Lighting: 0.00 W/sqft	Typical: 0.00 CFM/sqft					
PEOPLE	When Fan On.? N					
Occupancy: 345.0 sqft/per	FLOOR					
Activity Level: Office Work	Type:Slab Below Grade					
Sensible: 245.0 BTU/hr	Perimeter 400.0 ft					
Latent 205.0 BTU/hr	Slab Floor Area: 1372.0 sqft					
OTHER LOADS	Floor R-Value: 2.40					
Equipment: 1.00 W/sqft						
Misc. Sensible: 0.0 BTU/hr	Depth of Insulation: 0.0 ft					
Misc. Latent: 0.0 BTU/hr	Depth Below Grade: 6.0 ft					
=======================================	=======================================					
WALL Gross Area   WALL   WINDO						
Exp (sqft) Type Type Qty	y Shade   Type Qty Shade   Doors?					
E 1275.0   1   1 28	0 -   1 0 -   N					
No roof or door data for this space.						
No powerition data for this space						
No partition data for this space.						

Prepared by: EINHOR	N YAFFEE	PRESCOTT				12-30-94 Page 1	
*************	*****	*****	****	*****	******		
GENERAL			SCHEDULES				
	m 1&6 (ፒኒፖ	n 1 & 2)		_	ights		
Name: Classrm 1&6 (Typ 1 & 2) Lighting: Lights Floor Area: 2600.0 sqft Task Lights.: Lights							
Building Weight: 70.0 lb/sqft People: People Windows Shaded? N Equipment: People							
Partitions Used.?	N		Misc. Se				
LIGHTING	-		Misc. La		~		
Overhead Fixture:	Recessed		INFILTRA				
Lamp Wattage:		W/saft	Cooling	:	0.00	CFM/sqft	
Ballast Mult:			Heating			CFM/sqft	
Task Lighting:		W/sqft				CFM/sqft	
PEOPLE		, 4	When Far		N	, <u>-</u>	
Occupancy:	65.0	saft/per	FLOOR				
Activity Level:			Туре	:Ab	ove Condi	tioned Space	
Sensible:				,			
Latent:							
OTHER LOADS							
Equipment:	0.00	W/sqft					
Misc. Sensible:	0.0	BTU/hr					
Misc. Latent:		BTU/hr					
	=======	_=======	=======		=======	==========	
WALL Gross Area	WALL	WINDO	W	WI	NDOW	Any	
Exp (sqft)	Type	Type Qty	y Shade	Type (	Qty Shad	le   Doors?	
			. <b>-</b>				
N 858.0	1	1 240		1	0 -	N	
s 858.0	1	1 240	) -	1	0 -	N	
E 520.0	1	1 (	) –	1	0 -	N	
No roof or door data for this space.							
	=======	=======	=======		=======	=======================================	

\_\_\_\_\_\_

No partition data for this space.

Prepared by: EINHORN YAFFEE	PRESCOTT				12-30-94			
HAP v3.04					Page 1			
*******	*****	*****	*****	*****	*****			
GENERAL		SCHEDULES	3					
Name: Classrm 2&3 (Ty	p 1 & 2)	Lighting	д: L	ights				
Floor Area: 2600.0 sqft Task Lights.: Lights								
	Building Weight:: 70.0 lb/sqft People: People							
Windows Shaded?		Equipmer						
Partitions Used.?		Misc. Se	ens: P	eople				
LIGHTING		Misc. La	atent: P	eople				
Overhead Fixture: Recessed		INFILTRAT	rion	_				
Lamp Wattage: 3.00	W/sqft	Cooling	:	0.00	CFM/sqft			
Ballast Mult: 1.00	_	Heating.	:	0.00	CFM/sqft			
	W/sqft	Typical.	:	0.00	CFM/sqft			
PEOPLE	_	When Far	n On.?	N	•			
Occupancy: 65.0 sqft/per FLOOR								
Activity Level: Office Work Type:Above Conditioned Space								
Sensible 245.0								
Latent 205.0	BTU/hr							
OTHER LOADS								
Equipment: 0.00	W/sqft							
	BTU/hr							
Misc. Latent: 0.0	BTU/hr							
=======================================	=======	=======	======		==========			
WALL Gross Area   WALL	WINDO		l	NDOW	Any			
Exp (sqft) Type	Type Qty	y Shade	Туре	Qty Sha	de   Doors?			
	1 240		   1	0	-   N			
N 858.0   1	1 240		1 1	0	- N			
S 858.0   1   520.0   1		) -	<del> </del>   1	0	-   N			
W 520.0   1		, - 	<del>'</del> 					
No roof or door data for this space.								
NO TOOL OF GOOF data for this space.								
No partition data for this s								
no pareteron adea for entre					==========			

Prepared by: EINHO	RN YAFFEE	PRESCO	TT					12-30-94 Page 1	<b>4</b> 1
	*****	*****	****	*****	*****	****	*****	_	_
**************************************	rm 4 (Typ 2600.0 70.0 N N Recessed 3.00 1.00 0.00 65.0 Office Wo	1 & 2) ) sqft ) lb/sq  1 ) W/sqf ) W/sqf ) sqft/	aft ft ft per I	Lighting Task Lig People. Equipmen Misc. So Misc. Lo INFILTRA Cooling Heating Typical When Fan	ghts.: nt: nts.: ens.: atent: TION: n On.?	Light Light Peopl Peopl Peopl	s s e e e 0.00 CF 0.00 CF 0.00 CF	**************************************	_
OTHER LOADS Equipment: Misc. Sensible: Misc. Latent: ==================================	0.0	BTU/h BTU/h ====== W	nr nr :====: /INDOV	W	1	===== INDOW		======================================	=
Exp (sqft)	i TAbe i		Qcy						_
W 650.0 E 845.0 N 520.0	1   1   1		200 605 0	- - -	1   1   1	_	- - -	N   N   N	=
No roof or door data for this space.									
=======================================		-			=====	====	======	=========	=

No partition data for this space.

Prepared by: EINHO HAP v3.04							12-30-94 Page 1
******	*****	*****	*****	*****	****	****	********
GENERAL			SCHEDULE	S			
Name: Class	rm 5 (Tvp	1 & 2)	Lightin	a:	Light	s	
Floor Area:			_	-	-		
Building Weight.:				_	-		
Windows Shaded?			Equipme:				
Partitions Used.?		•	Misc. S		_		
LIGHTING	-	•	Misc. L		_		
Overhead Fixture:	Recessed		INFILTRA			-	
Lamp Wattage:		W/sqft				0.00 CF	M/saft
Ballast Mult:		_	Heating			0.00 CFI	-
Task Lighting:		) W/sqft	_			0.00 CF	
PEOPLE	0.00	, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	When Fa			N	-,
Occupancy:	65 (	arft/ne					
Activity Level:			Type	٠. ٢	bove (	Conditio	oned Space
Sensible:			1750		20.0	00114101	onou opass
Latent:							
	203.0	, DIO/III					
OTHER LOADS	0 00	W/caft					
Equipment: Misc. Sensible:	0.00	N/Sqrc					
		BTU/hr					
Misc. Latent:		•		<b></b>			
WALL Gross Area			ADOM	 I w	INDOW		Any
	,	mame (	ty Shade	ı			-
Exp (sqft)	Туре	TAbe d	ery Shade				, 20015.
E 650.0	1 1	1 2	200 -	1	0	_	N
W 845.0	1		505 -	!		_	N
N 520.0	1	1	0 -	1	0	_	l N
		- :=======	· :=========	, =======	=====	======	, ============
No roof or door data for this space.							
=======================================				======	=====	======	

No partition data for this space.

Prepared by: EINHOR	N YAFFEE I	PRESCOTT				12-30-94
HAP v3.04						Page 1
******	*****	******	*****	*****	*****	*****
GENERAL			SCHEDULES	}		
Name: North	Offices (T	Typ 1 & 2	Lighting	r: Ligh	nts	
Floor Area:		sqft		hts.: Ligh	nts	•
Building Weight.:	70.0	lb/sqft	People	: Peop	ole	
Windows Shaded?	N			ıt: Peop	ole	
Partitions Used.?	N		Misc. Se	ns: Peop	ole	
LIGHTING			Misc. La	tent: Peop	ole	
Overhead Fixture:	Recessed		INFILTRAT	ION		
Lamp Wattage:	3.00	W/sqft	Cooling.	:	0.00 CF	M/sqft
Ballast Mult:	1.00		Heating.	:	0.00 CF	M/sqft
Task Lighting:	0.00	W/sqft	Typical.	:	0.00 CF	M/sqft
PEOPLE			When Fan	On.?	N	
Occupancy:	147.0	sqft/per				
Activity Level:	Office Wor	ck	Туре	:Above	e Conditi	oned Space
Sensible:		BTU/hr				
Latent:	205.0	BTU/hr				
OTHER LOADS						
Equipment:	2.00	W/sqft				
Misc. Sensible:	0.0	BTU/hr				
Misc. Latent:	0.0	BTU/hr				
			========			
WALL Gross Area		WINDO		WINDO		Any
Exp (sqft)	Туре	Type Qty	Shade	Type Qty	Snade	Doors?
N 520.0	1	1 160	-	1 (	) -	N
	=======	=======	=======	=======	=======	=======================================
No roof or door data for this space.						
=======================================			=======			
No partition data f	or this sp	pace.				

Prepared by: EINHORN YAFFEE PRESCOTT	12-30-94					
HAP v3.04	Page 1					
	**********					
GENERAL	SCHEDULES					
Name: East Offices (Typ 1 & 2	) Lighting: Lights					
Floor Area: 1372.0 sqft						
Building Weight.: 70.0 lb/sqft People: People						
Windows Shaded?	Equipment: People					
Partitions Used.?	Misc. Sens: People					
LIGHTING	Misc. Latent: People					
Overhead Fixture: Recessed	INFILTRATION					
Lamp Wattage: 3.00 W/sqft	Cooling: 0.00 CFM/sqft					
Ballast Mult: 1.00	· · · · · · · · · · · · · · · · · ·					
Task Lighting: 0.00 W/sqft	Typical: 0.00 CFM/sqft					
PEOPLE	When Fan On.?					
Occupancy: 275.0 sqft/pe	r FLOOR					
Activity Level: Office Work	TypeAbove Conditioned Space					
Sensible 245.0 BTU/hr						
Latent 205.0 BTU/hr						
OTHER LOADS						
Equipment: 2.00 W/sqft						
Misc. Sensible: 0.0 BTU/hr						
Misc. Latent: 0.0 BTU/hr						
WALL Gross Area   WALL   WIN	DOW WINDOW Any					
Exp (sqft)   Type   Type Q	ty Shade   Type Qty Shade   Doors?					
E 1274.0   1   1 3	76 -   1 0 -   N					
	=======================================					
No roof or door data for this space.						
No partition data for this space.	=======================================					
	=======================================					

Prepared by: EINHORN YAFFEE PRESCOTT 12-30-9						12-30-94	
HAP v3.04	· · · · · · · · · · · · · · · · · · ·						
*******************							
GENERAL			SCHEDULES				
Name: South C	ffices (	Typ 1 & 2	Lighting	J: Li	ghts		
Floor Area:	2294.0	-	-	Jhts.: Li	_		
Building Weight.:	70.0	lb/sqft		: Pe			
Windows Shaded?	N		Equipmer	nt: Pe	ople		
Partitions Used.?	N			ens: Pe	-		
LIGHTING			Misc. La	atent: Pe	ople		
Overhead Fixture: R	ecessed		INFILTRA	CION			
Lamp Wattage:	3.00	W/sqft		:		• •	
Ballast Mult:	1.00		Heating.	:	0.00 CFN		
Task Lighting:	0.00	W/sqft	Typical.		0.00 CFN	M/sqft	
PEOPLE			When Far	on.?	N		
Occupancy:		sqft/per		_			
Activity Level: C			Type	:Abo	ve Condition	oned Space	
Sensible:		BTU/hr					
Latent:	205.0	BTU/hr					
OTHER LOADS							
Equipment:	2.00	W/sqft					
Misc. Sensible:		BTU/hr					
Misc. Latent:		BTU/hr					
=======================================		WINDC	:=====================================	======= WTN	:======= DOW	Any	
WALL Gross Area	WALL					Doors?	
Exp (sqft)	Туре	Type Qty	snaue		cy Shade	DOOLS:	
E 182.0	1	1 0		1	0 -	N	
s 1586.0	1	1 210	-	1	0 -	N	
No roof or door data for this space.							
=======================================							
No partition data for this space.							
	=======	=======	=======	======	========		

Prepared by: EINHORN YAFFEE PRESCOTT	12-30-94					
HAP v3.04	Page 1					
**********	**********					
GENERAL	SCHEDULES					
Name: West Offices (Typ 1 & 2)	Lighting: Lights					
Floor Area: 1372.0 sqft	Task Lights.: Lights					
Building Weight.: 70.0 lb/sqft						
Windows Shaded? N	Equipment: People					
Partitions Used.?	Misc. Sens: People					
LIGHTING	Misc. Latent: People					
Overhead Fixture: Recessed	INFILTRATION					
Lamp Wattage: 3.00 W/sqft	Cooling: 0.00 CFM/sqft					
Ballast Mult: 1.00	Heating: 0.00 CFM/sqft					
Task Lighting: 0.00 W/sqft	Typical: 0.00 CFM/sqft					
PEOPLE	When Fan On.? N					
Occupancy: 275.0 sqft/per	FLOOR					
Activity Level: Office Work Type:Above Conditioned Space						
Sensible: 245.0 BTU/hr						
Latent 205.0 BTU/hr						
OTHER LOADS						
Equipment: 1.00 W/sqft						
Misc. Sensible: 0.0 BTU/hr						
Misc. Latent: 0.0 BTU/hr						
=======================================						
WALL Gross Area   WALL   WIND	OW WINDOW Any					
Exp (sqft) Type Type Qt	y Shade   Type Qty Shade   Doors?					
	0 -   1 0 -   N					
W 1274.0   1   1 30						
No roof or door data for this space.						
No partition data for this space.						
=======================================						

Prepared by: EINHORN YAFFEE PRESCOTT	12-30-94						
HAP v3.04	Page 1						
**********	***********						
GENERAL	SCHEDULES						
Name: Cloak Rm (Typ 4/Flr)	Lighting: Lights						
Floor Area: 1040.0 sqft							
	People: People						
Windows Shaded?	Equipment: People						
Partitions Used.?	Misc. Sens: People						
LIGHTING	Misc. Latent: People						
Overhead Fixture: Recessed	INFILTRATION						
Lamp Wattage: 3.00 W/sqft							
Ballast Mult: 1.00	Heating: 0.00 CFM/sqft						
Task Lighting: 0.00 W/sqft	Typical: 0.00 CFM/sqft						
PEOPLE	When Fan On.?						
Occupancy: 200.0 sqft/per							
Activity Level: Office Work	Type:Above Conditioned Space						
Sensible 245.0 BTU/hr							
Latent 205.0 BTU/hr							
OTHER LOADS							
Equipment: 0.00 W/sqft							
Misc. Sensible: 0.0 BTU/hr							
Misc. Latent: 0.0 BTU/hr							
=======================================							
No external wall or window data for this space.							
No roof or door data for this space.							
No partition data for this space.							
	=======================================						

Prepared by: EINHORN YAFFEE I	PRESCOTT		12-30-94				
HAP v3.04			Page 1				
********	******	*****	******				
GENERAL		SCHEDULES					
Name: Auditorium		Lighting: Ligh	hts				
Floor Area: 9272.0	saft						
	lb/sqft	_					
Windows Shaded?		Equipment: Peop					
		Misc. Sens: Peop					
1410101010 000411		Misc. Latent: Peop	<del>-</del>				
LIGHTING		INFILTRATION	Die				
Overhead Fixture: Recessed	T.7 / E L		0 00 CEM/acft				
Lamp Wattage: 2.50	w/sqrt						
Ballast Mult: 1.00	/ <b>-</b> -	Heating:					
5 5	W/sqft		<del>-</del>				
PEOPLE	_ ,	When Fan On.?	N				
<u> </u>	sqft/per						
Activity Level: Seated at	Rest	TypeAbove	e Conditioned Space				
DOMESTICATION	BTU/hr						
Latent 120.0	BTU/hr						
OTHER LOADS							
Equipment: 0.00	W/sqft						
Misc. Sensible: 0.0	BTU/hr						
Misc. Latent: 0.0							
=======================================	=		=======================================				
No external wall or window data for this space.							
=======================================							
No roof or door data for this space.							
No partition data for this space.							

Prepared by: EINHORN YAFFEE PRESCOTT	12-30-94
HAP v3.04	Page 1
	**********
GENERAL	SCHEDULES
Name: Classrm 1&6 (3rd Flr)	Lighting: Lights
Floor Area: 2600.0 sqft	Task Lights.: Lights
Building Weight: 70.0 lb/sqft	
Windows Shaded?	Equipment: People
Partitions Used.?	Misc. Sens: People
LIGHTING	Misc. Latent: People
Overhead Fixture: Recessed	INFILTRATION
Lamp Wattage: 3.00 W/sqft	Cooling: 0.00 CFM/sqft
Ballast Mult: 1.00	Heating: 0.00 CFM/sqft
Task Lighting: 0.00 W/sqft	Typical: 0.00 CFM/sqft
PEOPLE	When Fan On.? N
Occupancy: 65.0 sqft/per	FLOOR
Activity Level: Office Work	Type:Above Conditioned Space
Sensible: 245.0 BTU/hr	
Latent 205.0 BTU/hr	
OTHER LOADS	
Equipment: 0.00 W/sqft	
Misc. Sensible: 0.0 BTU/hr	
Misc. Latent: 0.0 BTU/hr	
=======================================	=======================================
WALL Gross Area   WALL   WINI	·
Exp (sqft)   Type   Type Qt	y Shade   Type Qty Shade   Doors?
N 858.0   1   1 21	0 - 1 0 - N
S 858.0 1 1 21	0 - 1 0 - N
E 520.0 1 1	0 -   1 0 -   N
	.======================================
	KYLIGHT
Exp (deg) (sqft) Type Ty	pe Qty
HOR - 2600.0   1	1 0
=======================================	
No partition data for this space.	

Prepared by: EINHO	RN YAFFEE	PRESCO	TT					12-30-94
HAP v3.04								Page 1
*****	*****	****	****	*****	*****	****	*****	******
GENERAL			S	CHEDULES	3			
Name: Class:	rm 2&3 (3r	d Flr)		Lighting	j:	Light	s	
Floor Area:	2600.0	sqft		Task Lig	hts.:	Light	s	
Building Weight.:	70.0	lb/sq	ſft	People.	:	Peopl	e	
Windows Shaded?	N			Equipmen	ıt:	Peopl	e	
Partitions Used.?	N	Ī		Misc. Se	ens:	Peopl	е	
LIGHTING				Misc. La				
Overhead Fixture:	Recessed		I	NFILTRA	MOIT	_		
Lamp Wattage:	3.00	W/sqf	t	Cooling	<b>:</b>		0.00 CF	M/sqft
Ballast Mult:	1.00	1		Heating	<b>:</b>		0.00 CF	M/sqft
Task Lighting:	0.00	W/sqf	t	Typical	:		0.00 CF	M/sqft
PEOPLE				When Far	on.?		N	
Occupancy:	65.0	sqft/	per F	LOOR				
Activity Level:				Type	:A	bove	Conditi	oned Space
Sensible:		BTU/h	ır					
Latent:	205.0	BTU/h	ır					
OTHER LOADS								
Equipment:	0.00	W/sqf	t					
Misc. Sensible:		BTU/h						
Misc. Latent:		BTU/h						
=======================================					======	=====	======	=======================================
	WALL		INDOW			INDOW		Any
Exp (sqft)	Туре	Туре	Qty	Shade	Туре	Qty	Shade	Doors?
			210		 I 1			N
N 858.0	1		210 210	-	1   1	0 0	<u>-</u>	l N
s 858.0	1	_		-		0	_	l N
W 520.0	1	1	0					N
ROOF Slope Gross Area   ROOF   SKYLIGHT								
		Туре						
Exp (deg)	(sqft)   				! 			
HOR -	2600.0	1	1	. 0	 			
nor - ====================================					' ======	=====	======	
No partition data								
=======================================					======	=====		=========

12-30-94
SCHEDULES  Name: Classrm 4 (3rd Flr) Floor Area: 2600.0 sqft Floor Area: 2600.0 sqft Building Weight: 70.0 lb/sqft Building Weight: People Windows Shaded.? N Building Weight: People Building W
Name: Classrm 4 (3rd Flr)  Floor Area: 2600.0 sqft  Floor Area: 2600.0 sqft  Building Weight: 70.0 lb/sqft  Feople: People  Bequipment: People  Misc. Sens.: People  Misc. Latent: People  Misc. Latent: People  Misc. Latent: People  Misc. Latent: People  Coverhead Fixture: Recessed  INFILTRATION  Lamp Wattage: 3.00 W/sqft  Cooling: 0.00 CFM/sqft  Ballast Mult: 1.00  Heating: 0.00 CFM/sqft  Typical: 0.00 CFM/sqft  When Fan On.? N  Cocupancy: 65.0 sqft/per  Activity Level.: Office Work  Sensible: 245.0 BTU/hr  Latent: 205.0 BTU/hr  DTHER LOADS  Equipment: 0.00 W/sqft  Misc. Sensible.: 0.00 BTU/hr  Misc. Latent: 0.00 BTU/hr
Floor Area: 2600.0 sqft   Task Lights: Lights   Building Weight: 70.0 lb/sqft   People: People   Equipment: People   Equipment: People   Equipment: People   Equipment: People   Equipment: People   Equipment: People   Misc. Sens: People   Misc. Latent: People   Misc. Latent: People   INFILTRATION   Infil
Floor Area: 2600.0 sqft   Task Lights: Lights   Building Weight: 70.0 lb/sqft   People: People   Equipment: People   Equipment: People   Equipment: People   Equipment: People   Equipment: People   Equipment: People   Misc. Sens: People   Misc. Latent: People   Misc. Latent: People   INFILTRATION   Infil
Windows Shaded.? N Equipment: People Partitions Used.? N Misc. Sens: People LIGHTING Misc. Latent: People Overhead Fixture: Recessed INFILTRATION Lamp Wattage: 3.00 W/sqft Cooling: 0.00 CFM/sqft Ballast Mult: 1.00 Heating: 0.00 CFM/sqft Task Lighting: 0.00 W/sqft Typical: 0.00 CFM/sqft When Fan On.? N  Occupancy: 65.0 sqft/per FLOOR Activity Level: Office Work Type:Above Conditioned Space Sensible: 245.0 BTU/hr Latent: 205.0 BTU/hr DTHER LOADS Equipment: 0.00 W/sqft Misc. Sensible.: 0.0 BTU/hr Misc. Latent: 0.0 BTU/hr MISC. MINDOW WINDOW Any
Windows Shaded.? N Equipment: People Partitions Used.? N Misc. Sens: People LIGHTING Misc. Latent: People Overhead Fixture: Recessed INFILTRATION Lamp Wattage: 3.00 W/sqft Cooling: 0.00 CFM/sqft Ballast Mult: 1.00 Heating: 0.00 CFM/sqft Task Lighting: 0.00 W/sqft Typical: 0.00 CFM/sqft When Fan On.? N  Occupancy: 65.0 sqft/per FLOOR Activity Level: Office Work Type:Above Conditioned Space Sensible: 245.0 BTU/hr Latent: 205.0 BTU/hr DTHER LOADS Equipment: 0.00 W/sqft Misc. Sensible.: 0.0 BTU/hr Misc. Latent: 0.0 BTU/hr MISC. MINDOW WINDOW Any
DIGHTING  Overhead Fixture: Recessed  Lamp Wattage: 3.00 W/sqft  Ballast Mult: 1.00  Task Lighting: 0.00 W/sqft  PEOPLE  Occupancy: 65.0 sqft/per  Activity Level.: Office Work  Sensible: 245.0 BTU/hr  Latent: 205.0 BTU/hr  DTHER LOADS  Equipment: 0.00 W/sqft  Misc. Latent: People  INFILTRATION  Heating: 0.00 CFM/sqft  Typical: 0.00 CFM/sqft  When Fan On.? N  Type:Above Conditioned Space  Type:Above Conditioned Space  O.00 W/sqft  O.00 W/sqft  Misc. Sensible.: 0.0 BTU/hr  Misc. Latent: 0.0 BTU/hr  MALL Gross Area WALL WINDOW WINDOW Any
Overhead Fixture: Recessed INFILTRATION  Lamp Wattage: 3.00 W/sqft Cooling: 0.00 CFM/sqft  Ballast Mult: 1.00 Heating: 0.00 CFM/sqft  Task Lighting: 0.00 W/sqft Typical: 0.00 CFM/sqft  PEOPLE When Fan On.? N  Occupancy: 65.0 sqft/per FLOOR  Activity Level: Office Work Type:Above Conditioned Space  Sensible: 245.0 BTU/hr  Latent: 205.0 BTU/hr  OTHER LOADS  Equipment: 0.00 W/sqft  Misc. Sensible: 0.0 BTU/hr  Misc. Latent: 0.0 BTU/hr  Misc. Latent: 0.0 BTU/hr  WALL Gross Area WALL WINDOW WINDOW Any
Lamp Wattage: 3.00 W/sqft Cooling: 0.00 CFM/sqft Ballast Mult: 1.00 Heating: 0.00 CFM/sqft Task Lighting: 0.00 W/sqft Typical: 0.00 CFM/sqft PEOPLE When Fan On.? N  Occupancy: 65.0 sqft/per FLOOR Activity Level.: Office Work Type:Above Conditioned Space Sensible: 245.0 BTU/hr Latent: 205.0 BTU/hr DTHER LOADS Equipment: 0.00 W/sqft Misc. Sensible.: 0.0 BTU/hr Misc. Latent: 0.0 BTU/hr Misc. Latent: 0.0 BTU/hr Misc. Latent: 0.0 BTU/hr  MALL Gross Area WALL WINDOW WINDOW Any
Ballast Mult: 1.00 Heating: 0.00 CFM/sqft Task Lighting: 0.00 W/sqft Typical: 0.00 CFM/sqft PEOPLE When Fan On.? N  Occupancy: 65.0 sqft/per FLOOR Activity Level: Office Work Type:Above Conditioned Space Sensible: 245.0 BTU/hr Latent: 205.0 BTU/hr DTHER LOADS Equipment: 0.00 W/sqft Misc. Sensible: 0.0 BTU/hr Misc. Latent: 0.0 BTU/hr  MALL Gross Area WALL WINDOW WINDOW Any
Task Lighting: 0.00 W/sqft Typical: 0.00 CFM/sqft PEOPLE When Fan On.? N  Occupancy: 65.0 sqft/per FLOOR Activity Level: Office Work Type:Above Conditioned Space Sensible: 245.0 BTU/hr Latent: 205.0 BTU/hr  OTHER LOADS Equipment: 0.00 W/sqft Misc. Sensible: 0.0 BTU/hr Misc. Latent: 0.0 BTU/hr  MALL Gross Area   WALL   WINDOW   WINDOW   Any
PEOPLE When Fan On.? N  Occupancy: 65.0 sqft/per FLOOR  Activity Level.: Office Work Type:Above Conditioned Space Sensible: 245.0 BTU/hr Latent: 205.0 BTU/hr  OTHER LOADS Equipment: 0.00 W/sqft Misc. Sensible.: 0.0 BTU/hr Misc. Latent: 0.0 BTU/hr  MALL Gross Area   WALL   WINDOW   WINDOW   Any
When Fan On.? N  Occupancy: 65.0 sqft/per FLOOR  Activity Level.: Office Work Type:Above Conditioned Space  Sensible: 245.0 BTU/hr  Latent: 205.0 BTU/hr  OTHER LOADS  Equipment: 0.00 W/sqft  Misc. Sensible.: 0.0 BTU/hr  Misc. Latent: 0.0 BTU/hr  Misc. Latent: 0.0 BTU/hr  WALL Gross Area   WALL   WINDOW   WINDOW   Any
Activity Level.: Office Work Type:Above Conditioned Space Sensible: 245.0 BTU/hr Latent: 205.0 BTU/hr DTHER LOADS Equipment: 0.00 W/sqft Misc. Sensible.: 0.0 BTU/hr Misc. Latent: 0.0 BTU/hr  WALL Gross Area   WALL   WINDOW   WINDOW   Any
Activity Level.: Office Work Type:Above Conditioned Space Sensible: 245.0 BTU/hr Latent: 205.0 BTU/hr DTHER LOADS Equipment: 0.00 W/sqft Misc. Sensible.: 0.0 BTU/hr Misc. Latent: 0.0 BTU/hr  WALL Gross Area   WALL   WINDOW   WINDOW   Any
Sensible:       245.0 BTU/hr         Latent:       205.0 BTU/hr         DTHER LOADS       0.00 W/sqft         Equipment:       0.00 BTU/hr         Misc. Sensible:       0.0 BTU/hr         Misc. Latent:       0.0 BTU/hr         WALL Gross Area   WALL   WINDOW   WINDOW   Any
DTHER LOADS  Equipment: 0.00 W/sqft  Misc. Sensible: 0.0 BTU/hr  Misc. Latent: 0.0 BTU/hr  ===================================
Equipment: 0.00 W/sqft  Misc. Sensible: 0.0 BTU/hr  Misc. Latent: 0.0 BTU/hr  ===================================
Misc. Sensible: 0.0 BTU/hr Misc. Latent: 0.0 BTU/hr
Misc. Latent: 0.0 BTU/hr
WALL Gross Area   WALL   WINDOW   WINDOW   Any
WALL Gross Area   WALL   WINDOW   WINDOW   Any
The Clobb in the
Exp (sqft)   Type   Type Qty Shade   Type Qty Shade   Doors?
W 650.0   1   1 131 -   1 0 -   N
E 858.0   1   1 158 -   1 0 -   N
N 520.0   1   1 0 -   N
=======================================
ROOF Slope Gross Area   ROOF   SKYLIGHT
Exp (deg) (sqft) Type Type Qty
3XD (UCG) (BULC)   19PC   19PC   201
HOR - 2600.0   1   1 0

				RIPIION				
Prepared by: EINHO	RN YAFFEE	PRESCOT	'T					12-30-94
HAP v3.04								Page 1
*****	*****	*****	****	*****	*****	****	*****	*****
GENERAL			S	CHEDULES	5			
Name: Class	rm 5 (3rd	Flr)	]	Lighting	J:	Light	S	
Floor Area:				Task Lig	hts.:	Light	s	
Building Weight.:		lb/sqf	t :	People.	:	People	e	
Windows Shaded?		_		Equipmer	ıt:	People	e	
Partitions Used.?		Ī	1	Misc. Se	ens:	People	<b>e</b>	
LIGHTING			1	Misc. La	atent:	People	е	
Overhead Fixture:	Recessed		I	NFILTRA	CION	_		
Lamp Wattage:	3.00	W/sqft	. (	Cooling	:		0.00 CF	M/sqft
Ballast Mult:				Heating	:		0.00 CF	M/sqft
Task Lighting:	0.00	W/sqft		Typical.			0.00 CF	M/sqft
PEOPLE		•		When Far			N	
Occupancy:	65.0	sqft/p	er F	LOOR				•
Activity Level:					: A	bove (	Condition	oned Space
Sensible:		BTU/hr						
Latent:		BTU/hr						
OTHER LOADS		,						
Equipment:	0.00	W/sqft	:					
Misc. Sensible:		BTU/hr						
Misc. Latent:		BTU/hr						
=======================================			====	======		=====	======	=========
WALL Gross Area	WALL	WI	NDOW		W	INDOW		Any
Exp (sqft)	Туре	Туре	Qty	Shade	Туре	Qty	Shade	Doors?
				<b></b> -	<del></del> -			
E 650.0	1 1	1	131		1	0	-	N
W 858.0	1 1	1	158	-	1	0	-	j n
N 520.0	1	1	0	_	1	0	-	N
=======================================	========	======		======	======	=====	======	========
ROOF Slope Gross Area   ROOF   SKYLIGHT								
Exp (deg)	(sqft)	Туре	Туре	Qty				
			- <b></b> -					
HOR -	2600.0	1	1	0				
=======================================		======	====	======	======	=====	======	
No partition data	for this s	pace.						

Prepared by: EINHO	RN YAFFEE	PRESCOTT				12-30-94
HAP v3.04						Page 1
*****	*****	*****	*****	*****	*****	******
GENERAL			SCHEDULES	3		
Name: North	Offices (	3rd Flr)	Lighting	j: Li	.ghts	
Floor Area:	588.0	sqft	Task Lig	hts.: Li	ghts	
Building Weight.:	70.0	lb/sqft	People.	: Pe	eople	
Windows Shaded ?				nt: Pe	eople	
Partitions Used.	N		Misc. Se	ens: Pe	eople	
LIGHTING			Misc. La	atent: Pe	eople	
Overhead Fixture:	Recessed		INFILTRA	rion		
Lamp Wattage:	3.00	W/sqft	Cooling	:	0.00	CFM/sqft
Ballast Mult:	1.00		Heating	:	0.00	CFM/sqft
Task Lighting:	0.00	W/sqft	Typical	:	0.00	CFM/sqft
PEOPLE			When Far	on.?	N	
Occupancy:	147.0	sqft/per	FLOOR			
Activity Level:	Office Wo	rk	Type	: Abc	ove Condi	ltioned Space
Sensible:		•				
Latent:	205.0	BTU/hr				
OTHER LOADS						
Equipment:						
Misc. Sensible:						
Misc. Latent:	0.0	BTU/hr				
=======================================				=======	.=======	:======================================
WALL Gross Area		WINDO			IDOW	Any
Exp (sqft)	Туре	Type Qty	Shade	Type C	ty Snac	de   Doors?
N 520.0	1 1	1 105	,	1	0 -	-   N
			:=====: 'XI TOUM	======= 	:======	=======================================
ROOF Slope Gro		ROOF SK				
Exp (deg)	(sqft)	Type Live	e Qty			
HOR -	588.0	- 1	1 0			
No partition data			======	======	=======	:======================================

Prepared by: EINHORN YAFFEE	PRESCOTT	12-30-94
HAP v3.04		Page 1
******	*****	********
GENERAL	SCHEDULES	S
Name: East Offices (3	rd Flr) Lighting	g: Lights
Floor Area: 1372.0		ghts.: Lights
Building Weight.: 70.0	lb/sqft People.	: People
Windows Shaded?	Equipmen	nt: People
Partitions Used.?	Misc. Se	ens: People
LIGHTING	Misc. La	atent: People
Overhead Fixture: Recessed	INFILTRA	TION
Lamp Wattage: 3.00	W/sqft Cooling	: 0.00 CFM/sqft
Ballast Mult: 1.00		: 0.00 CFM/sqft
Task Lighting: 0.00	W/sqft Typical	: 0.00 CFM/sqft
PEOPLE	When Far	n On.? N
Occupancy: 275.0	sqft/per FLOOR	
Activity Level: Office Wo	ork Type	:Above Conditioned Space
	BTU/hr	
Latent 205.0	BTU/hr	
OTHER LOADS		
Equipment: 2.00	W/sqft	
Misc. Sensible: 0.0	BTU/hr	
	BTU/hr	
=======================================	=======================================	=======================================
	WINDOW	WINDOW   Any
Exp (sqft)   Type	Type Qty Shade	Type Qty Shade   Doors?
E 1274.0   1	1 235 -	1 0 -   N
=======================================		
	ROOF SKYLIGHT	
Exp (deg) (sqft)	Type  Type Qty	
11011	1   1 0	I
No partition data for this s	space.	

Prepared by: EINHORN YAFFEE	PRESCOTT	12-30-94
HAP v3.04		Page 1
*******	*****	********
GENERAL	SCHEDULES	
Name: South Offices	(3rd Flr) Lighting.	: Lights
Floor Area: 1708.	0 sqft Task Ligh	hts.: Lights
Building Weight.: 70.	0 lb/sqft People	: People
Windows Shaded?		t: People
Partitions Used.?		ns: People
LIGHTING	Misc. Lat	tent: People
Overhead Fixture: Recessed		
Lamp Wattage: 3.0	0 W/sqft Cooling.	
Ballast Mult: 1.0		: 0.00 CFM/sqft
Task Lighting: 0.0		——————————————————————————————————————
PEOPLE	When Fan	On.? N
· · · · · · · · · · · · · · · · · · ·	0 sqft/per FLOOR	
Activity Level: Office W		:Above Conditioned Space
JULID 202 201 111 111 111 111 111 111 111 111	0 BTU/hr	
200000000000000000000000000000000000000	0 BTU/hr	
OTHER LOADS	0.77/	
Equipment: 2.0	0 W/SqIt	
Misc. Sensible: 0.		
	0 BTU/hr	
WALL Gross Area   WALL	1 1	WINDOW   Any
Exp (sqft) Type	i ,	· -
EXP (SQIC)   Type		
E 182.0   1	1 1 0 -	1 0 -   N
s 1586.0 1	1 250 -	1 0 - N
=======================================	' ====================================	====================================
ROOF Slope Gross Area	ROOF   SKYLIGHT	
Exp (deg) (sqft)	Type Type Qty	
HOR - 1708.0	1   1 0	
=======================================		=======================================
No partition data for this	space.	
=======================================		=======================================

Prepared by: EINHORN YAFFEE PRESCO	OTT 12-30-94
HAP v3.04	Page 1
**********	***********
GENERAL	SCHEDULES
Name: West Offices (3rd Flr	r) Lighting: Lights
Floor Area: 1372.0 sqft	
Building Weight: 70.0 lb/sq:	
Windows Shaded?	Equipment: People
Partitions Used.?	Misc. Sens: People
LIGHTING	Misc. Latent: People
Overhead Fixture: Recessed	INFILTRATION
Lamp Wattage: 3.00 W/sqf	
Ballast Mult: 1.00	and the state of t
Task Lighting: 0.00 W/sqf	· -
PEOPLE	When Fan On.?
Occupancy: 275.0 sqft/	
Activity Level: Office Work	Type:Above Conditioned Space
Sensible: 245.0 BTU/h:	
Latent 205.0 BTU/h:	
OTHER LOADS	·
Equipment: 1.00 W/sqf	ft
Misc. Sensible: 0.0 BTU/h:	hr
Misc. Latent: 0.0 BTU/h:	
=======================================	
	WINDOW   WINDOW   Any
Exp (sqft) Type Type	Oty Shade Type Qty Shade Doors?
W 1274.0   1   1	235 -   1 0 -   N
1	SKYLIGHT
Exp (deg) (sqft) Type	Type Qty
HOR - 1372.0   1	1 0
No partition data for this space.	
=======================================	=======================================

Prepared by: EINHORN YAFFEE PRESCOTT	12-30-94		
HAP v3.04	Page 1		
**********	***********		
GENERAL	SCHEDULES		
Name: Inner Offices North	Lighting: Lights		
Floor Area: 910.0 sqft	Task Lights.: Lights		
Building Weight.: 70.0 lb/sqft	People: People		
Windows Shaded? N	Equipment: People		
Partitions Used.? N	Misc. Sens: People		
LIGHTING	Misc. Latent: People		
Overhead Fixture: Recessed	INFILTRATION		
Lamp Wattage: 3.00 W/sqft	Cooling: 0.00 CFM/sqft		
Ballast Mult: 1.00	Heating: 0.00 CFM/sqft		
Task Lighting: 0.00 W/sqft	Typical: 0.00 CFM/sqft		
PEOPLE	When Fan On.? N		
Occupancy: 182.0 sqft/per	FLOOR		
Activity Level: Office Work	Type:Above Conditioned Space		
Sensible: 245.0 BTU/hr			
Latent 205.0 BTU/hr			
OTHER LOADS			
Equipment: 1.00 W/sqft			
Misc. Sensible: 0.0 BTU/hr			
Misc. Latent: 0.0 BTU/hr			
=======================================			
WALL Gross Area WALL WINI	DOW   WINDOW   Any		
Exp (sqft) Type Type Qt	ty Shade   Type Qty Shade   Doors?		
s 686.0   1   1 28	36 -   1 0 -   N		
	=======================================		
ROOF Slope Gross Area   ROOF   S			
Exp (deg) (sqft) Type Ty			
HOR - 910.0   1	1 0		
HOR - 910.0   1	•		
No partition data for this space.			

		SPACE	DESC	RIPIION				
Prepared by: EINHO	ORN YAFFEE	PRESCO	${ m TT}$					12-30-94
HAP v3.04								Page 1
******	*****	*****	****	*****	*****	****	*****	******
GENERAL			S	CHEDULE	S			
Name: Inner	Offices E	ast		Lighting	g:	Light	S	
Floor Area:	1320.0	sqft		Task Lig	ghts.:	Light	s	
Building Weight.:	70.0	lb/sq	ft	People.	:	Peopl	е	
Windows Shaded?				Equipmen	nt:	Peopl	e	
Partitions Used.?	N			Misc. S	ens:	Peopl	e	
LIGHTING				Misc. La	atent:	Peopl	е	
Overhead Fixture:	Recessed		I	NFILTRA'	TION			
Lamp Wattage:	3.00	W/sqf	t	Cooling	:		0.00 CF	M/sqft
Ballast Mult:	1.00			Heating	:		0.00 CF	•
Task Lighting:	0.00	W/sqf	t	Typical	:		0.00 CF	M/sqft
PEOPLE				When Fai	n On.?		N	
Occupancy:	189.0	sqft/	per F	LOOR				
Activity Level:				Туре	:A	bove	Conditi	oned Space
Sensible:		BTU/h						
Latent:	205.0	BTU/h	r.					
OTHER LOADS								
Equipment:								
Misc. Sensible:		BTU/h						
Misc. Latent:	0.0	BTU/h	r					
=======================================			=====	======	======	=====	======	
WALL Gross Area			INDOW		1	INDOW		Any
Exp (sqft)	Type	Type	Qty	Shade	Туре	Qty	Shade	Doors?
W 1222.0	1	1	587	-	1	0	-	N
ROOF Slope Gro		===== ROOF		=====: LIGHT	====== 	====	======	=========
Exp (deg)		Type						
HOR -	1320.0		1	0				
No partition data				======	======	=====		

Prepared by: EINHORN YAFFEE PRESCOTT	12-30-94
HAP v3.04	Page 1
**********	***********
GENERAL	SCHEDULES
Name: Inner Offices South	Lighting: Lights
Floor Area 792.0 sqft	Task Lights.: Lights
Building Weight: 70.0 lb/sqft	People: People
Windows Shaded? N	Equipment: People
Partitions Used.? N	Misc. Sens: People
LIGHTING	Misc. Latent: People
Overhead Fixture: Recessed	INFILTRATION
Lamp Wattage: 3.00 W/sqft	Cooling: 0.00 CFM/sqft
Ballast Mult: 1.00	Heating: 0.00 CFM/sqft
Task Lighting: 0.00 W/sqft	Typical: 0.00 CFM/sqft
PEOPLE	When Fan On.? N
Occupancy: 198.0 sqft/per	FLOOR
Activity Level: Office Work	Type:Above Conditioned Space
Sensible: 245.0 BTU/hr	
Latent 205.0 BTU/hr	
OTHER LOADS	
Equipment: 1.00 W/sqft	
Misc. Sensible: 0.0 BTU/hr	
Misc. Latent: 0.0 BTU/hr	
	=======================================
WALL Gross Area   WALL   WINI	
Exp (sqft) Type Type Qt	y Shade   Type Qty Shade   Doors?
N 690.0   1   1 30	95 -   1 0 -   N
=======================================	
ROOI BIOPC GIODE III OI	KYLIGHT
Exp (deg) (sqft)   Type   Ty	mpe Qty
HOR - 792.0   1	1 0
	:======================================
No partition data for this space.	

Prepa	red by: EINHOR	RN YAFFEE	PRESCO'	${ m TT}$		12-30-
HAP v	-					Page
		****	*****	****	*****	*******
GENER.	ΔΤ,			S	CHEDULES	5
	: Inner	Offices We	est		Lighting	g: Lights
	r Area:					ghts.: Lights
	ding Weight.:				-	: People
	ows Shaded?					nt: People
	itions Used.?	N				ens: People
LIGHT						atent: People
	head Fixture:	Recessed		I	NFILTRA	rion
Lamp	Wattage:	3.00	W/sqf	t (	Cooling	: 0.00 CFM/sqft
	ast Mult:				Heating	: 0.00 CFM/sqft
	Lighting:		W/saf			: 0.00 CFM/sqft
PEOPL			, 1	1	When Far	
	pancy:	189.0	saft/	per F	LOOR	
Acti	vity Level:	Office Wo:	rk .		Type	:Above Conditioned Space
	ible:	245.0				
	nt					
	LOADS		·			
	pment:	1.00	W/sqf	t		
Misc	. Sensible:	0.0	BTU/h	r		
	. Latent:		BTU/h	r		
====	=========	=======	=====	====	======	=======================================
WALL	Gross Area	WALL	W	INDOW		WINDOW   Any
Exp	(sqft)	Туре	Туре	Qty	Shade	Type Qty Shade   Doors?
E	1222.0	1	1	587 	- 	1 0 -    N ==================================
	Slope Gro					
		(sqft)				
<b>-</b> HOR		1320.0	1	1	0	
	==========			====	======	=======================================
No pa	rtition data	for this s	pace.			
====	============	========	=====	=====	======	=

Prepared by: EINHORN YAFFEE PRESCOTT 12-30-94 Page 1 HAP v3.04 \*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\* SCHEDULES GENERAL Lighting...: Lights Name....: South Offices (2nd Flr) Task Lights.: Lights Floor Area....: 1320.0 sqft 70.0 lb/sqft People....: People Building Weight.: Equipment...: People Windows Shaded ..? N N Misc. Sens..: People Partitions Used.? Misc. Latent: People LIGHTING INFILTRATION Overhead Fixture: Recessed Lamp Wattage...: 3.00 W/sqft Cooling....: 0.00 CFM/sqft Heating....: 0.00 CFM/sqft 1.00 Ballast Mult...: 0.00 W/sqft 0.00 CFM/sqft Typical....: Task Lighting...: When Fan On.? N PEOPLE 155.0 sqft/per FLOOR Occupancy....: Activity Level..: Office Work Type......Above Conditioned Space Sensible....: 245.0 BTU/hr 205.0 BTU/hr Latent...: OTHER LOADS Equipment....: 1.00 W/sqft 0.0 BTU/hr 0.0 BTU/hr Misc. Sensible..: Misc. Latent...: \_\_\_\_\_\_ WALL Gross Area | WALL | WINDOW | WINDOW | Any Exp (sqft) | Type | Type Qty Shade | Type Qty Shade | Doors? 0 740.0 1 | 1 649 1 S - | 0 740.0 1 | 1 649 1 S - | 1 0 289.0 1 | 1 0  $\mathbf{E}$ \_\_\_\_\_\_\_ No roof or door data for this space. No partition data for this space.

\_\_\_\_\_\_

Prepared by: EINHORN YAFFEE PRESCOTT	01-06-95
HAD 173 04	Page 1
**********	**********
GENERAL	SCHEDULES
Name: Typical Stair Tower E	Lighting: People
Floor Area: 1200.0 sqft	
Building Weight.: 70.0 lb/sqft	
Windows Shaded? N	Equipment: People
Partitions Used.? N	Misc. Sens.: People
LIGHTING	Misc. Latent: People
Overhead Fixture: Recessed	INFILTRATION
Lamp Wattage: 1.00 W/sqft	Cooling: 0.00 CFM/sqft Heating: 0.00 CFM/sqft
Ballast Mult: 1.00	
Task Lighting: 0.00 W/sqft	Typical: 0.00 CFM/sqft When Fan On.? N
PEOPLE	When Fan On.?
Occupancy: 0 People	Type:Above Conditioned Space
Activity Level: Office Work	TypeAbove conditioned bpace
Sensible: 245.0 BTU/hr	
Latent 205.0 BTU/hr	
OTHER LOADS Equipment: 0.00 W/sqft	
/	
Misc. Latent: 0.0 BTU/hr	
WALL Gross Area   WALL   WIN	DOW   WINDOW   Any
MADD Grobb in the	ty Shade   Type Qty Shade   Doors?
EXP (Sqrc)   1/50   1/50 x	
E	50 -   1 0 -   N
=======================================	
ROOF Slope Gross Area   ROOF   S	
Exp (deg) (sqft)   Type   Type	ype Qty
HOR - 300.0   1	1 0
=======================================	=======================================
No partition data for this space.	

Prepared by: EINHORN YAFF	EE PRESCOTT				01-06-95
HAP v3.04					Page 1
******	******	*****	****	*****	*****
GENERAL		SCHEDULES			
Name: Typical Stai	r Tower W	Lighting	: Peop	Le	
Floor Area: 120	0.0 sqft	Task Lig	hts.: Peop	Le	
Building Weight.: 7	0.0 lb/sqft	People	: Peop?	Le	
Windows Shaded?	N	Equipmen	t: Peop	Le	
Partitions Used.?	N	Misc. Se	ns: Peop	Le	
LIGHTING		Misc. La	tent: Peop	Le	
Overhead Fixture: Recess	eđ	INFILTRAT	ION		
	.00 W/sqft	Cooling.	:	0.00 CF	M/sqft
	.00	_	:	0.00 CF	
	.00 W/sqft	Typical.	:	0.00 CF	M/sqft
PEOPLE		When Fan	On.?	N	
Occupancy:	0 People	FLOOR			
Activity Level: Office	Work	Type	:Above	Condition	oned Space
Sensible: 24	5.0 BTU/hr				
Latent 20	5.0 BTU/hr				
OTHER LOADS					
Equipment: 0	.00 W/sqft				
Misc. Sensible:	0.0 BTU/hr				
	0.0 BTU/hr				
=======================================			========	=======	
WALL Gross Area WALL			WINDO		Any
Exp (sqft) Type	Type Qty	Shade	Type Qty	Shade	Doors?
			1 0		
	.   1 210	- 1			N
=======================================		:======= 'VI.TCUT	=======	======	
ROOF Slope Gross Area	Type Typ				
Exp (deg) (sqft)	Type   Typ				
HOR - 300.0	1 1	1 0			
HOR - 300.0	1 ,		========		
No partition data for thi					
-:- <b>Fan-</b>	-				

Prepared by: EINHORN YAFFEE PRESCOTT	01-06-95		
HAP v3.04	Page 1		
TARE V3.01	***********		
GENERAL	SCHEDULES Lighting: People		
Name: Corridors	<u> </u>		
Floor Area: 10000.0 sqft Building Weight.: 70.0 lb/sqft			
	Equipment: People		
Willdows Blidded	Misc. Sens: People		
raicicions oboa	Misc. Latent: People		
LIGHTING Overhead Fixture: Recessed	INFILTRATION		
Lamp Wattage: 1.50 W/sqft			
Ballast Mult: 1.00	Heating: 0.00 CFM/sqft		
Task Lighting: 0.00 W/sqft			
PEOPLE 0.00 N/D420	When Fan On.?		
Occupancy: 0 People	FLOOR		
Activity Level: Office Work	Type:Above Conditioned Space		
Sensible: 245.0 BTU/hr	••		
Latent: 205.0 BTU/hr			
OTHER LOADS			
Equipment: 0.00 W/sqft			
Misc. Sensible: 0.0 BTU/hr			
Misc. Latent: 0.0 BTU/hr			
No external wall or window data for t	his space.		
ROOF Slope Gross Area   ROOF   S			
Exp (deg) (sqft) Type Ty	pe Qty		
HOR = 3500.0   =	1 0		
No partition data for this space.			

SPACE DES	
Prepared by: EINHORN YAFFEE PRESCOTT	01-06-95
UAD 373 04	Page 1
**********	***********
GENERAL	SCHEDULES
Name · Cloak Rm 3rd Flr (Tvp 4)	Lighting: Lights
Floor Area: 1040.0 sqft	Task Lights.: Lights
Floor Area: 1040.0 sqft Building Weight: 70.0 lb/sqft	People: People
Windows Shaded?	Equipment: People
Partitions Used.?	Misc. Sens: People
LIGHTING	Misc. Latent: People
Overhead Fixture: Recessed	INFILTRATION
Lamp Wattage: 2.00 W/sqft	Cooling: 0.00 CFM/sqft
Ballast Mult: 1.00	Heating: 0.00 CFM/sqft
Task Lighting: 0.00 W/sqft	Typical: 0.00 CFM/sqft
PEOPLE	When Fan On.?
Occupancy: 0 People	FLOOR
Activity Level: Office Work	Type:Above Conditioned Space
Sensible: 245.0 BTU/hr	
Latent: 205.0 BTU/hr	
OTHER LOADS	
Equipment: 0.00 W/sqft	
Misc. Sensible: 0.0 BTU/hr	
Misc. Latent: 0.0 BTU/hr	
=======================================	=======================================
No external wall or window data for t	his space.
======================================	
ROOF Slope Gross Area   ROOF   S	
Exp (deg) (sqft) Type Ty	:
HAP (409)	
HOR - 1040.0 1	1 0
No partition data for this space.	

	EM INPUT DATA	10 20 04
Name: Auditorium - Baseline		12-30-94
Type: CONSTANT VOLUME - Single Zon	e CAV	HAP v3.04
Prepared by: EINHORN YAFFEE PRESCO	TT	Page 1
**********	****	****
1. SYSTEM NAME AND TYPE		
Name Auditorium - E		
Type CONSTANT VOLUM	E - Single Zone CAV	
Number of Zones.: 1		
=======================================		=======================================
2. SYSTEM DESCRIPTION		
COOLING SYSTEM DATA	Y	
Is Central Cooling Used? Supply Air	20000.0 CFM	
Coil Bypass Factor	0.100	
Fan Cycled for Cooling?	N	
Supply Air Reset:	Not Used	
HEATING SYSTEM DATA		
Is Central Heating Used?	Y	
Fan Cycled for Heating?	N	
Supply Air Reset:	Not Used	
OUTDOOR VENTILATION DATA		
Type of Control:	Constant Airflow Rate	
Design Ventilation Airflow:	5000.0 CFM	
Dampers Open During Unocc Per.:	N	
Damper Leak Rate:	2 %	
SUPPLY DUCT DATA		
Duct Heat Gain:	2 %	
Duct Leakage Rate:	5 %	
RETURN PLENUM DATA	N	
Is a Return Plenum Used? SUPPLY FAN DATA	14	
Fan Type:	Backward Inclined or Air	rfoil
Configuration:	Draw-Thru	
Fan Total Static:	2.00 in.wg.	
Fan Efficiency:	54 %	
RETURN FAN DATA		
Fan Type:	None	
OUTDOOR AIR ECONOMIZER		
Outdoor Economizer Type:	None	
PREHEAT COIL		
Preheat Coil Used?	N	
PRECOOL COIL	.,	
Precool Coil Used?	N	
HUMIDIFICATION	N	
Humidification System Used?	N	
DEHUMIDIFICATION  Dehumidification System Used?	N	
VENTILATION HEAT RECLAIM	24	
Reclaim Unit Type	None	
SAFETY FACTORS		
Sensible Cooling Factor:	0 %	
Latent Cooling Factor:	0 %	
Heating Factor:	0 %	
		==========

AIR SY Name: Auditorium - Baseline Type: CONSTANT VOLUME - Single Z Prepared by: EINHORN YAFFEE PRES ************************************	COTT		****	12-30-94 HAP v3.04 Page 2
3. ZONE DATA				
ZONE	1	(All Zones	the	Same)
T-Stat Occupied Cooling(F):	75.0			
Unoccupied Cooling(F):	85.0			
Occupied Heating(F):	70.0			
Unoccupied Heating(F):	55.0			
Throttling Range(F):	3.0			
Zone Heating Unit Type:	None			
Trip Temperature(F):	-			
Design Supply Temperature(F):	-			
Fan Total Static(in.wg.):	_			
Fan Efficiency(%):				
Zone Terminal Type	Diffuser N			
Reheat Coil?  Direct Exhaust Airflow(CFM):	0.0			
Direct Exhaust Fan kW(kW):	0.0			
======================================	0.0		====	.========
4. SCHEDULE DATA				
=======================================	=========	=========	====	
HOURLY TSTAT SCHEDULES   0 0 0 0	0 0 0 0 0 0 0 0	1 1 1 1 1 :	L   1   1	1 1 2 2 2 2 2
0 1 2 3	4 5 6 7 8 9	0 1 2 3 4 !	5   6   7	7   8   9   0   1   2   3
			 -     -	- <b></b>
<b>-</b>		X   X   X   X   X   X   X   X   X   X	(   X   2	X   X   X   X   X   X   X   X   X   X
				( X X X X X X  
- : : : : :				( X X X X X X  ( V V V V V V V
Sunday  X X X X	. ^ ^ ^ ^	. ^ ^ ^ ^	-   -   -	( X X X X X X
Cooling Available During Unoccup	ied Period ?	Y		
MONTHLY SCHEDULES   JAN   FEB				OCT   NOV   DEC
Central Heating   XXX   XXX   Central Cooling			(   XXX	

	M INPUT DATA 12-30-94
Name: Classroom 1 & 6 (Flr 1 & 2)	
Type: CONSTANT VOLUME - Single Zone	
Prepared by: EINHORN YAFFEE PRESCOT	**************************************
****	
1. SYSTEM NAME AND TYPE	
Name Classroom 1 & 6	
Type CONSTANT VOLUME	- Single Zone CAV
Number of Zones.: 1	
=======================================	=======================================
a averay beggripmion	
2. SYSTEM DESCRIPTION	
COOLING SYSTEM DATA	
Is Central Cooling Used?	Y
Supply Air:	55.0 F
Coil Bypass Factor	0.100
Fan Cycled for Cooling?	N
Supply Air Reset:	Not Used
HEATING SYSTEM DATA	Not obed
Is Central Heating Used?	Y
Fan Cycled for Heating?	N
Supply Air Reset:	Not Used
OUTDOOR VENTILATION DATA	Not obca
Type of Control:	Constant Airflow Rate
Design Ventilation Airflow:	1650.0 CFM
Dampers Open During Unocc Per.:	N
Damper Leak Rate:	2 %
SUPPLY DUCT DATA	- '
Duct Heat Gain:	2 %
Duct Leakage Rate:	5 %
RETURN PLENUM DATA	• '
Is a Return Plenum Used?	N
SUPPLY FAN DATA	
Fan Type:	Forward Curved
Configuration:	Draw-Thru
Fan Total Static:	1.00 in.wg.
Fan Efficiency:	54 %
RETURN FAN DATA	
Fan Type:	None
OUTDOOR AIR ECONOMIZER	
Outdoor Economizer Type:	None
PREHEAT COIL	
Preheat Coil Used?	N
PRECOOL COIL	
Precool Coil Used?	И
HUMIDIFICATION	
Humidification System Used?	N
DEHUMIDIFICATION	
Dehumidification System Used?	N
VENTILATION HEAT RECLAIM	
Reclaim Unit Type:	None
SAFETY FACTORS	
Sensible Cooling Factor:	0 %
Latent Cooling Factor:	0 %
Heating Factor:	0 %
	=======================================

AIR SYSTEM INPUT DATA  Name: Classroom 1 & 6 (Flr 1 & 2) 12-30-5  Type: CONSTANT VOLUME - Single Zone CAV HAP v3.0  Prepared by: EINHORN YAFFEE PRESCOTT Page							
3. ZONE DATA							
ZONE T-Stat Occupied Cooling(F): Unoccupied Cooling(F): Occupied Heating(F):	1 (All Zones the Same) 75.0 85.0 70.0						
Unoccupied Heating(F): Throttling Range(F):	55.0 3.0						
Zone Heating Unit Type:  Trip Temperature(F):  Design Supply Temperature(F):  Fan Total Static(in.wg.):	None						
Fan Efficiency(%):  Zone Terminal Type?  Reheat Coil?  Direct Exhaust Airflow(CFM):  Direct Exhaust Fan kW(kW):	Diffuser N 0.0 0.0						
4. SCHEDULE DATA							
	0 0 0 0 0 1 1 1 1 1 1 1 1 1 1 2 2 2 2  5 6 7 8 9 0 1 2 3 4 5 6 7 8 9 0 1 2 3						
Design Day							
Cooling Available During Unoccupied							
	R   APR   MAY   JUN   JUL   AUG   SEP   OCT   NOV   DEC						
Central Heating   XXX   XXX   XXX   Central Cooling							

Name: Classroom 2 & 3 (Flr 1 & 2) Type: CONSTANT VOLUME - Single Zone Prepared by: EINHORN YAFFEE PRESCOT ************************************	
1. SYSTEM NAME AND TYPE	
Name: Classroom 2 & 3 Type: CONSTANT VOLUME Number of Zones: 1	(Flr 1 & 2)
2. SYSTEM DESCRIPTION	
COOLING SYSTEM DATA	
Is Central Cooling Used?	Y
Supply Air:	55.0 F
Coil Bypass Factor:	0.100
Fan Cycled for Cooling?	N
Supply Air Reset	Not Used
Is Central Heating Used?	Y
Fan Cycled for Heating?	N
Supply Air Reset:	Not Used
OUTDOOR VENTILATION DATA	
Type of Control:	Constant Airflow Rate
Design Ventilation Airflow:	1650.0 CFM
Dampers Open During Unocc Per.:	И
Damper Leak Rate:	2 %
SUPPLY DUCT DATA	
Duct Heat Gain:	2 %
Duct Leakage Rate:	5 %
RETURN PLENUM DATA	
Is a Return Plenum Used?	N
SUPPLY FAN DATA	
Fan Type:	Forward Curved
Configuration:	Draw-Thru
Fan Total Static:	1.00 in.wg.
Fan Efficiency:	54 %
RETURN FAN DATA	
Fan Type:	None
OUTDOOR AIR ECONOMIZER	
Outdoor Economizer Type:	None
PREHEAT COIL	
Preheat Coil Used?	N
PRECOOL COIL	
Precool Coil Used?	N
HUMIDIFICATION	•
Humidification System Used?	N
DEHUMIDIFICATION	
Dehumidification System Used?	И
VENTILATION HEAT RECLAIM	
Reclaim Unit Type:	None
SAFETY FACTORS	
Sensible Cooling Factor:	0 %
Latent Cooling Factor:	0 %
Heating Factor	0 %
=======================================	=======================================

Name: Classroom 2 & 3 (Flr 1 &	2) 12-	-30-94
Type: CONSTANT VOLUME - Single	Zone CAV HAP	v3.04
Prepared by: EINHORN YAFFEE PRE	Pa Pa	age 2
******************	***********	****
3. ZONE DATA		. <i></i> -
ZONE	1 (All Zones the Same)	
T-Stat Occupied Cooling(F):		
Unoccupied Cooling(F):	85.0	
Occupied Heating(F):		
Unoccupied Heating(F):		
Throttling Range(F):		
Zone Heating Unit Type:		
Trip Temperature(F):	<del>-</del>	
Design Supply Temperature(F):		
Fan Total Static(in.wg.):		
Fan Efficiency(%):	<del>-</del>	
Zone Terminal Type:	Diffuser	
Reheat Coil?		
Direct Exhaust Airflow(CFM):	0.0	
Direct Exhaust Fan kW(kW):	0.0	
_======================================		=====
4 COMPDITE DAMA		
4. SCHEDULE DATA		=====
	0 0 0 0 0 0 0 1 1 1 1 1 1 1 1 1 1 2 :	
HOURLY ISTAL SCREEDSLES  0 0 0 0	3 4 5 6 7 8 9 0 1 2 3 4 5 6 7 8 9 0	1 2 3
0 1 2		
Design Day		
Weekday		
Saturday		
Sunday		
		=====
Cooling Available During Unoccu	upied Period ? N 	
MONTHLY SCHEDULES   JAN   FE	EB   MAR   APR   MAY   JUN   JUL   AUG   SEP   OCT   NO	V   DEC
PIONITIES SCHEDOLES   OTAL   12		
Central Heating   XXX   XX	XX   XXX   XXX   XXX   XXX	x   xxx
Central Cooling		İ
		=====

	TEM INPUT DATA
Name: Classroom 4 (Flr 1 & 2)	12-30-9
Type: CONSTANT VOLUME - Single Zon	ne CAV HAP v3.0
Prepared by: EINHORN YAFFEE PRESCO	)TT
********	*****************************
1. SYSTEM NAME AND TYPE	
I. DISTEM NAME AND ITTE	
Name Classroom 4 (F	'lr 1 & 2)
Type CONSTANT VOLUM	
Number of Zones.: 1	
=======================================	
2. SYSTEM DESCRIPTION	
COOLING SYSTEM DATA	
Is Central Cooling Used?	Y
Supply Air:	55.0 F
Coil Bypass Factor:	0.100
Fan Cycled for Cooling?	N
Supply Air Reset:	Not Used
HEATING SYSTEM DATA	**
Is Central Heating Used?	Y
Fan Cycled for Heating?	N Not Used
Supply Air Reset:	Not Used
OUTDOOR VENTILATION DATA	Constant Airflow Rate
Type of Control	1650.0 CFM
Design Ventilation Airflow:	N
Dampers Open During Unocc Per.: Damper Leak Rate	2 %
SUPPLY DUCT DATA	2 0
Duct Heat Gain:	2 %
Duct Leakage Rate:	5 %
RETURN PLENUM DATA	
Is a Return Plenum Used?	N
SUPPLY FAN DATA	
Fan Type:	Forward Curved
Configuration:	Draw-Thru
Fan Total Static:	1.00 in.wg.
Fan Efficiency:	54 %
RETURN FAN DATA	
Fan Type:	None
OUTDOOR AIR ECONOMIZER	•
Outdoor Economizer Type:	None
PREHEAT COIL	NT.
Preheat Coil Used?	N
PRECOOL COIL	N
Precool Coil Used?	N
HUMIDIFICATION Humidification System Used?	N
DEHUMIDIFICATION	11
Dehumidification System Used?	N
VENTILATION HEAT RECLAIM	<del></del>
Reclaim Unit Type:	None
SAFETY FACTORS	
Sensible Cooling Factor:	0 %
Latent Cooling Factor:	0 %
Datent Cooring Paccor	

Name: Classroom 4 (Flr 1 & 2)  Type: CONSTANT VOLUME - Single Zone CAV  Prepared by: EINHORN YAFFEE PRESCOTT  **********************************					
3. ZONE DATA					
ZONE	1	(All Zones	the Same)		
T-Stat Occupied Cooling(F):	75.0				
Unoccupied Cooling(F):	85.0				
Occupied Heating(F):	70.0				
Unoccupied Heating(F):	55.0				
Throttling Range $(F)$ :	3.0				
Zone Heating Unit Type:	None				
Trip Temperature(F):	-				
Design Supply Temperature(F):	-				
Fan Total Static(in.wg.):	_				
Fan Efficiency(%):	- Diffuser				
Zone Terminal Type Reheat Coil?	N		•		
Direct Exhaust Airflow(CFM):	0.0				
Direct Exhaust Fan kW(kW):	0.0				
======================================	========				
4. SCHEDULE DATA					
HOURLY TSTAT SCHEDULES  0 0 0 0		) 1 1 1 1 1 1 1	1   1   1   1   2   2   2   2		
			6 7 8 9 0 1 2 3		
Design Day		x   x   x   x   x   x   x			
Weekday		x   x   x   x   x   x   x	$ \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x} $		
Saturday					
Sunday					
Cooling Available During Unoccupie	ed Period ?		=======================================		
		=======================================			
MONTHLY SCHEDULES   JAN   FEB   N	MAR   APR   MAY	OUA   JUL   NUC   ?	SEP OCT NOV DEC		
Central Heating   XXX   XXX   X	(XX   XXX				
Central Cooling		xxx   xxx   xxx   x			

Name: Classroom 5 (Flr 1 & 2) Type: CONSTANT VOLUME - Single Zone Prepared by: EINHORN YAFFEE PRESCOT	
1. SYSTEM NAME AND TYPE	
Name: Classroom 5 (Fl Type: CONSTANT VOLUME Number of Zones.: 1	r 1 & 2)
2. SYSTEM DESCRIPTION	
COOLING SYSTEM DATA	
Is Central Cooling Used?	Y
Supply Air:	55.0 F
Coil Bypass Factor:	0.100
Fan Cycled for Cooling?	N
Supply Air Reset: HEATING SYSTEM DATA	Not Used
Is Central Heating Used?	Y
Fan Cycled for Heating?	N
Supply Air Reset:	Not Used
OUTDOOR VENTILATION DATA	
Type of Control:	
Design Ventilation Airflow:	1650.0 CFM
Dampers Open During Unocc Per.:	N
Damper Leak Rate:	2 %
SUPPLY DUCT DATA	2 4
Duct Heat Gain	2 % 5 %
Duct Leakage Rate	5 6
Is a Return Plenum Used?	N
SUPPLY FAN DATA	N
Fan Type:	Forward Curved
Configuration:	Draw-Thru
Fan Total Static:	1.00 in.wg.
Fan Efficiency:	54 %
RETURN FAN DATA	
Fan Type:	None
OUTDOOR AIR ECONOMIZER	
Outdoor Economizer Type:	None
PREHEAT COIL	
Preheat Coil Used?	N
PRECOOL COIL	<b>\*</b>
Precool Coil Used?	N
HUMIDIFICATION	37
Humidification System Used? DEHUMIDIFICATION	Ŋ
Dehumidification System Used?	N
VENTILATION HEAT RECLAIM	
Reclaim Unit Type:	None
SAFETY FACTORS	0. 9.
Sensible Cooling Factor:	0 %
Latent Cooling Factor:	0 % 0 %
Heating Factor:	· · · · · · · · · · · · · · · · · · ·

Name: Classroom 5 (Flr 1 & 2)			12-30-94			
Type: CONSTANT VOLUME - Single Zone CAV HAP V						
Prepared by: EINHORN YAFFEE PRESCOTT Page						
******		*****	******			
3. ZONE DATA						
ZONE	1	(All Zones t	he Same)			
T-Stat Occupied Cooling(F):	75.0	(	,			
Unoccupied Cooling(F):	85.0					
Occupied Heating(F):	70.0					
Unoccupied Heating(F):	55.0					
Throttling Range(F):	3.0					
Zone Heating Unit Type:	None					
Trip Temperature(F):						
Design Supply Temperature(F):	-					
Fan Total Static(in.wg.):	_					
Fan Efficiency(%):	_					
Zone Terminal Type:	Diffuser					
Reheat Coil?	N					
Direct Exhaust Airflow(CFM):	0.0					
Direct Exhaust Fan kW(kW):	0.0					
=======================================	:========	=========	=======================================			
4. SCHEDULE DATA	=========		=======================================			
	0000000000	1 1 1 1 1 1	1 1 1 1 2 2 2 2			
			6 7 8 9 0 1 2 3			
Design Day		$ \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x}$	x   x   x   x   x   x   x   x   x   x			
Weekday		$ \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x} $	x   x   x   x   x   x   x			
Saturday						
Sunday						
	========		=======================================			
Cooling Available During Unoccup			===========			
			SEP   OCT   NOV   DEC			
Central Heating   XXX   XXX	( xxx xxx		XXX   XXX   XXX			
Central Cooling						
Central Cooring		·         ·				

Name: Classrooms 1 & 6 (3rd Flr)	12-30-94								
Type: CONSTANT VOLUME - Single Zon	ne CAV HAP v3.04								
Prepared by: EINHORN YAFFEE PRESCO	OTT Page 1								
**************************************									
1. SYSTEM NAME AND TYPE									
Name Classrooms 1	& 6 (3rd Flr)								
Type CONSTANT VOLUM	ME - Single Zone CAV								
Number of Zones.: 1									
=======================================	=======================================								
2. SYSTEM DESCRIPTION									
COOLING SYSTEM DATA	**								
Is Central Cooling Used?	Y								
Supply Air:	55.0 F								
Coil Bypass Factor	0.100								
Fan Cycled for Cooling?	N								
Supply Air Reset:	Not Used								
HEATING SYSTEM DATA	••								
Is Central Heating Used?	Y								
Fan Cycled for Heating?	N								
Supply Air Reset:	Not Used								
OUTDOOR VENTILATION DATA	Goodbank Binfley Data								
Type of Control:	Constant Airflow Rate								
Design Ventilation Airflow:	1650.0 CFM								
Dampers Open During Unocc Per.:	N								
Damper Leak Rate:	2 %								
SUPPLY DUCT DATA	2 %								
Duct Heat Gain:	2 %								
Duct Leakage Rate:	5 %								
RETURN PLENUM DATA	NT.								
Is a Return Plenum Used?	N								
SUPPLY FAN DATA	Forward Curved								
Fan Type:	Draw-Thru								
Configuration	1.00 in.wg.								
Fan Total Static	54 %								
Fan Efficiency	34 0								
RETURN FAN DATA	None								
Fan Type OUTDOOR AIR ECONOMIZER	110110								
Outdoor Economizer Type:	None								
PREHEAT COIL	110110								
Preheat Coil Used?	N								
PRECOOL COIL	<del>-</del> '								
Precool Coil Used?	N								
HUMIDIFICATION									
Humidification System Used?	N								
DEHUMIDIFICATION									
Dehumidification System Used?	N								
VENTILATION HEAT RECLAIM									
Reclaim Unit Type:	None								
SAFETY FACTORS									
Sensible Cooling Factor:	0 %								
Latent Cooling Factor:	0 %								
Heating Factor:	0 %								
=======================================									

# AIR SYSTEM INPUT DATA 1 & 6 (3rd Flr)

Name: Classrooms 1 & 6 (3rd Flr)			12-30-94
Type: CONSTANT VOLUME - Single Zo		HAP v3.04	
Prepared by: EINHORN YAFFEE PRESC		Page 2	
********	*****	*****	******
3. ZONE DATA			
ZONE	 1	(All Zones	the Same)
ZONE T-Stat Occupied Cooling(F):	75.0	(AII ZOIICS	ciic bame,
Unoccupied Cooling(F):	85.0		
Occupied Heating(F):	70.0		
Unoccupied Heating(F):	55.0		
Throttling Range(F):	3.0		
Zone Heating Unit Type:	None		
Trip Temperature(F):	_		
Design Supply Temperature (F):	_		
Fan Total Static(in.wg.):	_		
Fan Efficiency(%):	_		
Zone Terminal Type:	Diffuser		
Reheat Coil?	N		
Direct Exhaust Airflow(CFM):	0.0		
Direct Exhaust Fan kW(kW):	0.0		
		=========	=========
4. SCHEDULE DATA			
HOURLY TSTAT SCHEDULES  0 0 0 0	000000000	1 1 1 1 1 1	1 1 1 1 1 2 2 2 2 2
	4   5   6   7   8   9	0 1 2 3 4 5	6 7 8 9 0 1 2 3
Davis Davis			
Design Day		$ \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x}$	
Weekday	1		
Saturday			
======================================		!   !         ==========================	
Cooling Available During Unoccupi	led Period ?	N	
MONTHLY SCHEDULES   JAN   FEB			SEP OCT NOV DEC
Central Heating   XXX   XXX			
Central Cooling	xxx	xxx   xxx   xxx	XXX
			=============

# AIR SYSTEM INPUT DATA 2 & 3 (3rd Flr)

Name: Classrooms 2 & 3 (3rd Flr)	12-30-94						
Type: CONSTANT VOLUME - Single Zone	e CAV HAP v3.04						
Prepared by: EINHORN YAFFEE PRESCOTT							
*********	**********						
1. SYSTEM NAME AND TYPE							
Name: Classrooms 2 &							
Type CONSTANT VOLUME	: - Single Zone CAV						
Number of Zones.: 1	=======================================						
2. SYSTEM DESCRIPTION							
COOLING SYSTEM DATA							
Is Central Cooling Used?	Y						
Supply Air	55.0 F						
Coil Bypass Factor	0.100						
Fan Cycled for Cooling?	N						
Supply Air Reset:	Not Used						
HEATING SYSTEM DATA							
Is Central Heating Used?	Y						
Fan Cycled for Heating?	N						
Supply Air Reset:	Not Used						
OUTDOOR VENTILATION DATA							
Type of Control:	Constant Airflow Rate						
Design Ventilation Airflow:	1650.0 CFM						
Dampers Open During Unocc Per.:	N						
Damper Leak Rate:	2 %						
SUPPLY DUCT DATA							
Duct Heat Gain:	2 %						
Duct Leakage Rate:	5 %						
RETURN PLENUM DATA							
Is a Return Plenum Used?	N						
SUPPLY FAN DATA							
Fan Type:	Forward Curved						
Configuration:	Draw-Thru						
Fan Total Static:	1.00 in.wg.						
Fan Efficiency:	54 %						
RETURN FAN DATA							
Fan Type:	None						
OUTDOOR AIR ECONOMIZER	None						
Outdoor Economizer Type:	None						
PREHEAT COIL Preheat Coil Used?	N						
	N						
PRECOOL COIL Precool Coil Used?	N						
HUMIDIFICATION	14						
_	N						
Humidification System Used? DEHUMIDIFICATION	24						
Dehumidification System Used?	N						
VENTILATION HEAT RECLAIM	<del>-</del> ·						
Reclaim Unit Type:	None						
SAFETY FACTORS							
Sensible Cooling Factor:	0 %						
Latent Cooling Factor:	0 %						
Heating Factor:	0 %						

				EM	TIME	ŲΙ	DA	LIA								-			
Name: Classrooms 2 & 3 ()					****							12-30-9							
Type: CONSTANT VOLUME - Single Zone CAV							HAP v3.04 Page 2												
Prepared by: EINHORN YAF:	FEE	PRE	SCC	TT									مات مات	ماد ماد			Pag		٠.
******	****	***	***	***	***	***	**	***	**	***	**	**	* *	* *	**	**	* * 7	* * 7	K 7
3. ZONE DATA					<b>_</b>														
ZONE						1		(Al	1	Zor	es	t	he	S	ame	<u> </u>			
I-Stat Occupied Cooling.	(	F):			7	5.0													
Unoccupied Cooling					8	5.0													
Occupied Heating.					7	0.0													
Unoccupied Heating	g(	F):			5	5.0													
Throttling Range.	(	F):				3.0													
Zone Heating Unit Type		:			N	one	:												
Trip Temperature						-													
Design Supply Temperate						-													
Fan Total Static(i						-													
Fan Efficiency						-													
Zone Terminal Type				Di	ffu														
Reheat Coil						N													
Direct Exhaust Airflow						0.0													
Direct Exhaust Fan kW						0.0													
=======================================	====	===	===	===		===													
4. SCHEDULE DATA																			
======================================	====	===	===	===		===	==	===	==	===	===	==	==	==	===	===	===	===	=:
HOURLY TSTAT SCHEDULES	00	0	0   0	0	0 0	0	0	1   1	.   1	1	1	1	1	1	1   1	L   2	2	2	1:
	0 1	2	3   4	5	6 7	8	9	0   1	. 2	3	4	5	6	7	8   8	∌   o	1	2	1:
																			<u> </u>
Design Day								$X \mid X$											
Weekday						X	X	$X \mid X$	X	X	Χİ	X	хļ	хļ	XĮΣ	۲ļx	ļ		ļ
Saturday							-	ļ			ļ	ļ	ļ						ļ
Sunday			j				- 1				İ		- 1	İ					l
									==	===	===	==	==	==	===	===	===	===	= :
			ріе																_
Cooling Available During																			
Cooling Available During	====	===	===	===   qa	====					ıπ.l	ΔTI	G l	SE					ות ו	57.0
Cooling Available During		===	===	IAR						ur	AU	G	SE					DI	Ξ(
Cooling Available During SCHEDULES Contral Heating	====  JAN 	===  FE 	=== B M	IAR	APR	MA				ן סדן	AU	G   	SE	P		r   N 	OV 	- <b>-</b> -	-
Cooling Available During	====  JAN 	===  FE 	=== B M	IAR	APR	M.A 	Y		   	 !				P	OC7	r   N 	OV 	- <b>-</b> -	-

Name: Classroom 4 (3rd Flr) Type: CONSTANT VOLUME - Single Zone Prepared by: EINHORN YAFFEE PRESCOT ************************************	T Page 1 ************************************
Name: Classroom 4 (3r Type: CONSTANT VOLUME Number of Zones: 1	d Flr) - Single Zone CAV
2 SYSTEM DESCRIPTION	
COOLING SYSTEM DATA	••
Is Central Cooling Used?	Y
Supply Air:	55.0 F
Coil Bypass Factor:	0.100
Fan Cycled for Cooling?	N
Supply Air Reset HEATING SYSTEM DATA	Not Used
Is Central Heating Used?	Y
Fan Cycled for Heating?	N
Supply Air Reset:	Not Used
OUTDOOR VENTILATION DATA	
1/20 01 001101	Constant Airflow Rate
Design Ventilation Airflow:	1650.0 CFM
Dampers Open During Unocc Per.:	N
Damper Leak Rate:	2 %
SUPPLY DUCT DATA	
Duct Heat Gain:	2 %
Duct Leakage Rate:	5 %
RETURN PLENUM DATA	
Is a Return Plenum Used?	N
SUPPLY FAN DATA	_ , , , ,
Fan Type:	Forward Curved
Configuration:	Draw-Thru
Fan Total Static:	1.00 in.wg.
Fan Efficiency:	54 %
RETURN FAN DATA	<b>3</b> *
Fan Type:	None
OUTDOOR AIR ECONOMIZER	None
Outdoor Economizer Type:	None
PREHEAT COIL	N
Preheat Coil Used?	Ŋ
PRECOOL COIL Precool Coil Used?	N
	14
HUMIDIFICATION	N
Humidification System Used?	11
DEHUMIDIFICATION  Dehumidification System Used?	N
	<b>^1</b>
VENTILATION HEAT RECLAIM Reclaim Unit Type:	None
SAFETY FACTORS	1010
Sensible Cooling Factor:	0 %
Latent Cooling Factor:	0 %
Heating Factor	0 %
=======================================	

Name: Classroom 4 (3rd Fl Type: CONSTANT VOLUME - S Prepared by: EINHORN YAFF	lr) Single : FEE PRE:	SCOTT		12-30-94 HAP v3.04 Page 2
3. ZONE DATA				
ZONE T-Stat Occupied Cooling Unoccupied Cooling Occupied Heating Unoccupied Heating Throttling Range	g(F): (F): g(F):	1 75.0 85.0 70.0 55.0 3.0	(All Zones the	e Same)
Zone Heating Unit Type  Trip Temperature  Design Supply Temperature  Fan Total Static(in  Fan Efficiency  Zone Terminal Type  Reheat Coil  Direct Exhaust Airflow  Direct Exhaust Fan kW	(F): ure(F): ure(F):(%):;; .(CFM):(kW):	0.0	============	
4. SCHEDULE DATA				
HOURLY TSTAT SCHEDULES				1 1 1 2 2 2 2   7 8 9 0 1 2 3
Design Day  Weekday  Saturday  Sunday				
Cooling Available During			N	=======================================
MONTHLY SCHEDULES	======   JAN   FE:	:======== :B MAR APR MAY	JUL   AUG   S	EP OCT NOV DEC
Central Heating	XXX   XX	xxx	xxx   xxx   xxx   x	xx   xxx   xxx   xxx

	EM INPUT DATA	
Name: Classroom 5 (3rd Flr)	12-30-9	94
Type: CONSTANT VOLUME - Single Zon		04
Prepared by: EINHORN YAFFEE PRESCO	TT Page	1
***********	***********	**
1. SYSTEM NAME AND TYPE		
Name Classroom 5 (3		
Type CONSTANT VOLUM	E - Single Zone CAV	
Number of Zones.: 1		
=======================================	=======================================	==
2. SYSTEM DESCRIPTION		
<del></del>		
COOLING SYSTEM DATA	Y	
Is Central Cooling Used?	55.0 F	
Supply Air	0.100	
Coil Bypass Factor	N	
Fan Cycled for Cooling?	_	
Supply Air Reset:	Not Used	
HEATING SYSTEM DATA	Y	
Is Central Heating Used?	N	
Fan Cycled for Heating?	Not Used	
Supply Air Reset	NOC OSEC	
OUTDOOR VENTILATION DATA	Constant Airflow Rate	
Type of Control	1650.0 CFM	
Design Ventilation Airflow:	N	
Dampers Open During Unocc Per.: Damper Leak Rate	2 %	
SUPPLY DUCT DATA	2 0	
Duct Heat Gain:	2 %	
	5 %	
Duct Leakage Rate RETURN PLENUM DATA	5 0	
Is a Return Plenum Used?	N	
SUPPLY FAN DATA	•	
Fan Type:	Forward Curved	
Configuration:	Draw-Thru	
Fan Total Static:	1.00 in.wg.	
Fan Efficiency:	54 %	
RETURN FAN DATA		
Fan Type:	None	
OUTDOOR AIR ECONOMIZER		
Outdoor Economizer Type:	None	
PREHEAT COIL		
Preheat Coil Used?	N	
PRECOOL COIL		
Precool Coil Used?	N	
HUMIDIFICATION		
Humidification System Used?	N	
DEHUMIDIFICATION		
Dehumidification System Used?	N	
VENTILATION HEAT RECLAIM		
Reclaim Unit Type:	None	
SAFETY FACTORS		
Sensible Cooling Factor:	0 %	
Latent Cooling Factor:	0 %	
Heating Factor:	0 %	
		==

Name: Classroom 5 (3rd Flr) Type: CONSTANT VOLUME - Sin Prepared by: EINHORN YAFFEE	gle PF	RES	one	e Ci	AV											HA	2 - : P	v3. ge	۰٥.
**************************************	***	k * * :	***	***	***	***	* *	***	***	**;	* * 7	k * 1	***	**	***	**	**	* * 1	**:
<b></b>						 1		(A)	 11	zor	nes	 s t	he		ame	 e)			
T-Stat Occupied Cooling	(F)	:			7	5.0										•			
Unoccupied Cooling					8	5.0													
Occupied Heating					7	0.0													
Unoccupied Heating	(F)	:			5	5.0													
Throttling Range	(F)	:			;	3.0													
Zone Heating Unit Type		. :			No	one													
Trip Temperature	(F)	:				-													
Design Supply Temperature						-													
Fan Total Static(in.w						-													
Fan Efficiency						-													
Zone Terminal Type				Di:	ffu														
Reheat Coil						N													
Direct Exhaust Airflow(C						0.0													
Direct Exhaust Fan kW( ================================						o.o													
=======================================																			
4. SCHEDULE DATA																			
	===	===:	===	===:	===:	===	==	==:			===	===		===		==	==:	===	==
	010	0   0	0	0	0   0	0	0	1	1   1	1	1	1	1	1	1   1	2	2	2	2
					6   7														
	- <del>-</del> -	- <del>-</del>							<u>-</u>	<u> </u>	- <b>-</b> -					·			
Design Day	- 1	1				X	x	$ \mathbf{x} $	$x \mid x$	x	X	Х	x	Х	X   2	x   2			
Weekday	ĺ	ĺ				X	х	$ \mathbf{X} $	$x \mid x$	x	X	X	$ \mathbf{x} $	Х	X D	x   2			
Saturday	-				-														
Sunday													-			1			
										==:	==:	===	===	==	===	==	==	===	==
Cooling Available During Un		_																	
======================================					APR														
	 	 VVV	   v3	 vyl:	 YYY	 I	 !		 I		 I		 I		XXX	 :   x	xx	   x ז	 xx
Central Heating	<u>م</u> ام	n.A.A	^4	AA .	AAA		X.	XX	$x \mid x$	ХХ	x	ХХ	ХX			1		222	, 4.4.
	•																		

Name: Perimeter Fan Coil Units - E Type: TERMINAL UNITS - 2-Pipe Fan Prepared by: EINHORN YAFFEE PRESCO	n Coils HAP v3.04
1. SYSTEM NAME AND TYPE	
Name: Perimeter Fan Type: TERMINAL UNITS Number of Zones.: 14	3 - 2-Pipe Fan Coils
=======================================	
2. SYSTEM DESCRIPTION	
COOLING SYSTEM DATA	
Supply Air:	55.0 F
Fan Cycled for Cooling?	N
Coil Bypass Factor:	0.100
HEATING SYSTEM DATA	
Fan Cycled for Heating?	N
OUTDOOR VENTILATION DATA	
Common Ventilation System Used?	N
SAFETY FACTORS	
Sensible Cooling Factor:	0 %
Latent Cooling Factor:	0 %
Heating Factor:	0 %
OUTDOOR VENTILATION DATA	
Type of Control:	Constant Airflow Rate
Design Ventilation Airflow:	
=======================================	=======================================
3. ZONE DATA	
5. NONE DATA	
ZONE	<pre>1 (All Zones the Same)</pre>
T-Stat Occupied Cooling(F):	75.0
Unoccupied Cooling(F):	85.0
Occupied Heating(F):	70.0
Unoccupied Heating(F):	55.0
Throttling Range(F):	3.0
Zone Terminal Type:	Fan Coil
Fan Total Static(in.wg.):	0.25
Fan Efficiency(%):	54

Name: Perimeter Fan Coil		12-30-94
Type: TERMINAL UNITS - 2		HAP v3.04
Prepared by: EINHORN YAFF		Page 2
******	********	*****
4. SCHEDULE DATA		
HOURLY TSTAT SCHEDULES	0 0 0 0 0 0 0 0 0 0 0 0 1 1 1 1 1 1 1 1	1 1 1 2 2 2 2
	0 1 2 3 4 5 6 7 8 9 0 1 2 3 4 5 6	[7[8[9]0]1[2]3]
		1-1-1-1-1-1-1-1-1
- :	X   X   X   X   X   X   X   X   X   X	
	x   x   x   x   x   x   x   x   x   x	
	$x \mid x \mid x \mid x \mid x \mid x \mid x \mid x \mid x \mid x \mid$	
Sunday	$X \mid X \mid X \mid X \mid X \mid X \mid X \mid X \mid X \mid X \mid$	X X X X X X X
=======================================		==========
Cooling Available During	Unoccupied Period ? N	
	jan   feb   mar   apr   may   jun   jul   aug   si	ED LOCUL NOV   DEC
MONTHLY SCHEDULES	JAN   FEB   MAR   APR   MAY   JUN   JUL   AUG   SI	EP   OCI   NOV   DEC
manufaction	xxx xxx xxx xxx	xxx xxx xxx
Terminal Heating	XXX XXX XXX XXX XXX XXX XXX XXX XXX XX	YY   NAA   NAA
Terminal Cooling		~~!

	EM INPUT DATA
Name: Basement Classrooms (2)-Basel	Line 12-30-94
Type: CONSTANT VOLUME - Single Zone	
Prepared by: EINHORN YAFFEE PRESCO	rT Page 1
++++++++++++++++++++++++++++++++++++++	**********
1 GUGERN NAME AND EVIDE	
1. SYSTEM NAME AND TYPE	
Name : Basement Classi	
Type : CONSTANT VOLUM	s - Single Zone CAV
Number of Zones.: 1	
=======================================	=======================================
2. SYSTEM DESCRIPTION	
COOLING SYSTEM DATA	
Is Central Cooling Used?	Y
Supply Air:	55.0 F
Coil Bypass Factor:	0.100
Fan Cycled for Cooling?	N
Supply Air Reset:	Not Used
HEATING SYSTEM DATA	
Is Central Heating Used?	Y
Fan Cycled for Heating?	N
Supply Air Reset:	Not Used
	1100 0000
OUTDOOR VENTILATION DATA	Constant Airflow Rate
Type of Control	1600.0 CFM
Design Ventilation Airflow:	
Dampers Open During Unocc Per.:	N
Damper Leak Rate:	2 %
SUPPLY DUCT DATA	
Duct Heat Gain:	2 %
Duct Leakage Rate:	5 %
RETURN PLENUM DATA	
Is a Return Plenum Used?	N
SUPPLY FAN DATA	
Fan Type:	Forward Curved
Configuration:	Draw-Thru
Fan Total Static:	1.00 in.wg.
Fan Efficiency:	54 %
RETURN FAN DATA	
Fan Type:	None
OUTDOOR AIR ECONOMIZER	
Outdoor Economizer Type:	None
PREHEAT COIL	110110
Preheat Coil Used?	N
	W .
PRECOOL COIL	N
Precool Coil Used?	N
HUMIDIFICATION	).T
Humidification System Used?	N
DEHUMIDIFICATION	
Dehumidification System Used?	N
VENTILATION HEAT RECLAIM	
Reclaim Unit Type:	None
SAFETY FACTORS	
Sensible Cooling Factor:	0 %
Latent Cooling Factor:	0 %
Heating Factor:	0 %
	=======================================

Name: Basement Classrooms Type: CONSTANT VOLUME - S Prepared by: EINHORN YAFF ***********************************	Sing: FEE H	le 2 PRES	Zone SCO:	e C. FT	AV	k * * * *	***	***	+**	**	**	**	**	**	* *	H	AP P	v ag	·з. е	94 04 2
3. ZONE DATA																				
ZONE						 1	 (	 All	 7	 On	 es	 +	 he	 S	 am	 = )			- <b>-</b>	<b>-</b> -
T-Stat Occupied Cooling	(1	F):			75	5.0	`	7111		011	CD	٠		٥	<b></b>	٠,				
Unoccupied Cooling						5.0														
Occupied Heating					70	0.0														
Unoccupied Heating					5	5.0														
Throttling Range					3	3.0														
Zone Heating Unit Type					No	one														
Trip Temperature						-														
Design Supply Temperatu						-														
Fan Total Static(in						-														
Fan Efficiency	( †	ة):		Dέ	ffus	-														
Zone Terminal Type Reheat Coil				דת	LLui	N														
Direct Exhaust Airflow					(	0.0														
Direct Exhaust Fan kW						0.0														
=======================================			===	===	===	====	===	===	===	==	==	==	==	==	==	==	==	==	==	:==
4. SCHEDULE DATA	<b>_</b> _			<b>-</b>				===	===	==	==	==	==	==	==		==	==	==	==
	00	   0   0	0   0	lol	0 0	000	1	11	1	1	1	1	1	1	1	1	2	2	2	2
	0 1																			
	. <b></b>											- <del>'</del>								· – -
Design Day	$ \mathbf{x} \mathbf{x}$	X   2	Х	X.	$x \mid x$	$ \mathbf{x} $	(   X	X	X	х	$\mathbf{x}$	X	x	X	X	<b>X</b>	x	х	x	x
Weekday	$ \mathbf{x} \mathbf{x}$	X	XΙ	X	$\mathbf{x} \mid \mathbf{x}$	$ \mathbf{x} $	۲   X	X	X	$X \mid$	$\mathbf{x}$	X	X	X	X	<b>X</b>   :	X	x	Χĺ	X
Saturday	$ \mathbf{x} \mathbf{x}$	$ \mathbf{x} $	X X	X.	$\mathbf{x} \mid \mathbf{x}$	$ \mathbf{x} $	۲ x	X	X	x	<b>x</b>   :	Χļ	x	X	x	<b>X</b>   :	X	X	X	X
Sunday	$ \mathbf{x} \mathbf{x}$	X   2	X X	X	$X \mid X$	X   2	(   X	:   X	X	Х	X   .	X	X	X	X	X   .	X	X	X	X
Cooling Available During	Uno	ccup	pie	d E	eri	od 1	?	N												
MONTHLY SCHEDULES	====   JAN																			
Central Heating		   xxx	K   X	xx		XXX			     v v		 vv	   v	 vv		 xx	 x	 XX	 X	xx	xx

Name: Auditorium - PLC Type: CONSTANT VOLUME - Single Zon Prepared by: EINHORN YAFFEE PRESCO' ************************************	
1. SYSTEM NAME AND TYPE	
Name	LC
2. SYSTEM DESCRIPTION	
COOLING SYSTEM DATA	
Is Central Cooling Used?	Y
Supply Air	20000.0 CFM
Coil Bypass Factor:	0.100
Fan Cycled for Cooling?	N
Supply Air Reset HEATING SYSTEM DATA	Not Used
Is Central Heating Used?	Y
Fan Cycled for Heating?	N
Supply Air Reset:	Not Used
OUTDOOR VENTILATION DATA	
Type of Control:	Constant Airflow Rate
Design Ventilation Airflow:	5000.0 CFM
Dampers Open During Unocc Per.:	N
Damper Leak Rate:	2 %
SUPPLY DUCT DATA	2 %
Duct Heat Gain:	2 % 5 %
Duct Leakage Rate:	<b>5</b> %
RETURN PLENUM DATA  Is a Return Plenum Used?	N
	14
SUPPLY FAN DATA  Fan Type:	Backward Inclined or Airfoil
Configuration:	Draw-Thru
Fan Total Static:	2.00 in.wg.
Fan Efficiency:	54 %
RETURN FAN DATA	
Fan Type:	None
OUTDOOR AIR ECONOMIZER	
Outdoor Economizer Type:	None
PREHEAT COIL	
Preheat Coil Used?	N
PRECOOL COIL	
Precool Coil Used?	N
HUMIDIFICATION	
Humidification System Used?	N
DEHUMIDIFICATION	
Dehumidification System Used?	N
VENTILATION HEAT RECLAIM	None
Reclaim Unit Type:	None
SAFETY FACTORS	0 %
Sensible Cooling Factor:	0 %
Latent Cooling Factor	0 %
Heating Factor	:======================================

Name: Auditorium - PLC Type: CONSTANT VOLUME - Si Prepared by: EINHORN YAFFE ***********************************	ngle EE PE	e Zo	ne COTT				****	****	***		IAP v Pag	,
3. ZONE DATA												
ZONE T-Stat Occupied Cooling	. (F) . (F) . (F) . (F) . (F) wg.) . (%)	) : ) : ) : ) : ) : ) : ) : ) :	D	8! 76 5!	1 5.0 5.0 0.0 5.0 3.0 one - -	(A1	l Zor	nes i	the	Same)		
Direct Exhaust Airflow(	(CFM)	):			0.0							
Direct Exhaust Fan kW			===	====:	====	====				====		====
4. SCHEDULE DATA												
										1   1   1   1   8   9		
Design Day				x		X   X 				X   X   X   X 		
Cooling Available During U	Jnoc	cupi	ed	Peri	od?	N						
MONTHLY SCHEDULES   J	JAN   I	FEB	MAR	APR	MAY	אטע	JUL	AUG	SEF	OCT	NOV	DEC
Central Heating X Central Cooling	XXX	xxx     	xxx	XXX 		  xxx  ====	  xxx ====	  xxx  ====	  xxx  ====	:	xxx	xxx

	Coils HAP v3.04
1. SYSTEM NAME AND TYPE	
Name: Perimeter Fan Type TERMINAL UNITS Number of Zones.: 14	Coil Units - PLC
2. SYSTEM DESCRIPTION	
COOLING SYSTEM DATA	
Supply Air:	55.0 F
Fan Cycled for Cooling?	N
Coil Bypass Factor:	0.100
HEATING SYSTEM DATA	N
Fan Cycled for Heating? OUTDOOR VENTILATION DATA	N
Common Ventilation System Used?	N
SAFETY FACTORS	<del>-</del>
Sensible Cooling Factor:	0 %
Latent Cooling Factor:	0 %
Heating Factor:	0 %
OUTDOOR VENTILATION DATA	G of sub-Air-Flow Baba
Type of Control:	Constant Alrilow Rate
Design Ventilation Airflow:	0.0 CFM/person
3. ZONE DATA	
ZONE	1 (All Zones the Same)
T-Stat Occupied Cooling(F):	75.0
Unoccupied Cooling(F):	85.0
Occupied Heating(F):	70.0
Unoccupied Heating(F):	55.0
Throttling Range(F): Zone Terminal Type:	3.0 Fan Coil
Fan Total Static(in.wg.):	0.25
Fan Efficiency(%):	54
	=======================================

AIR DIDIES INTO DILL	
Name: Perimeter Fan Coil Units - PLC	12-30-94
Type: TERMINAL UNITS - 2-Pipe Fan Coils	AP v3.04
Prepared by: EINHORN YAFFEE PRESCOTT	Page 2
***********************	*****
4. SCHEDULE DATA	
	======
HOURLY TSTAT SCHEDULES   0   0   0   0   0   0   0   0   0	2 2 2 2
0 1 2 3 4 5 6 7 8 9 0 1 2 3 4 5 6 7 8 9	0 1 2 3
Design Day	
Weekday	x
Saturday	
Sunday	
=======================================	=======
Cooling Available During Unoccupied Period ? N	
	======
MONTHLY SCHEDULES   JAN   FEB   MAR   APR   MAY   JUN   JUL   AUG   SEP   OCT	NOV DEC
MONTHEL BOMBBBB   John	
Terminal Heating   XXX   XXX   XXX   XXX	xxx xxx
Terminal Cooling	
Terminal Cooring	

Name: Basement Classrooms (2) - PL	C 12-30-94
Type: CONSTANT VOLUME - Single Zon	e CAV HAP v3.04
Prepared by: EINHORN YAFFEE PRESCO	•
prepared by: EINHORN TAFFEE FRESCO	**********
********	
A CHARTE TAND TWDE	
1. SYSTEM NAME AND TYPE	
Danamah Glass	
Name Basement Class	
Type CONSTANT VOLUM	E - Single Zone CAV
Number of Zones.: 1	
=======================================	=======================================
a grampy production	
2. SYSTEM DESCRIPTION	
COOLING SYSTEM DATA	
Is Central Cooling Used?	Y
Supply Air	55.0 F
Coil Bypass Factor:	0.100
Fan Cycled for Cooling?	N
Supply Air Reset:	Not Used
HEATING SYSTEM DATA	
Is Central Heating Used?	Y
Fan Cycled for Heating?	N
Supply Air Reset:	Not Used
OUTDOOR VENTILATION DATA	
Type of Control:	Constant Airflow Rate
Design Ventilation Airflow:	1600.0 CFM
Dampers Open During Unocc Per.:	N
Damper Leak Rate:	2 %
SUPPLY DUCT DATA	
Duct Heat Gain	2 %
Duct Leakage Rate:	5 %
RETURN PLENUM DATA	
Is a Return Plenum Used?	N
SUPPLY FAN DATA	
Fan Type:	Forward Curved
Configuration:	Draw-Thru
Fan Total Static:	1.00 in.wg.
Fan Efficiency:	54 %
RETURN FAN DATA	
Fan Type:	None
OUTDOOR AIR ECONOMIZER	110.13
Outdoor Economizer Type:	None
PREHEAT COIL	
Preheat Coil Used?	N
PRECOOL COIL	•
Precool Coil Used?	N
HUMIDIFICATION	•
Humidification System Used?	N
	**
DEHUMIDIFICATION  Dehumidification System Used 2	N
Dehumidification System Used?	•
VENTILATION HEAT RECLAIM	None
Reclaim Unit Type:	110110
SAFETY FACTORS	0 %
Sensible Cooling Factor:	-
Latent Cooling Factor:	0 %
Heating Factor:	0 % 0 %

Name: Basement Classrooms (2) - PLC 12-30-94 Type: CONSTANT VOLUME - Single Zone CAV HAP v3.04 Prepared by: EINHORN YAFFEE PRESCOTT Page 2 ************************************																								
3. ZONE DATA																								
ZONE									 1		 A)	11	. 2	zor	ies	3 1	 :he	= -	Sat	ne	)			
T-Stat Occupied Cooling.		( E	7):				-	75	. 0															
Unoccupied Cooling									. 0															
Occupied Heating.									.0															
Unoccupied Heating							į		.0															
Throttling Range.								_	.0															
Zone Heating Unit Type Trip Temperature							1	NO:	ne -															
Design Supply Temperatu									_															
Fan Total Static(in									_															
Fan Efficiency									-															
Zone Terminal Type			:			Di	ffι	ıs	er															
Reheat Coil									N	•														
Direct Exhaust Airflow								-	. 0															
Direct Exhaust Fan kW									. 0															
=======================================	===	==	===	===	==		===	==:	==	==	==	==	==		==:	==:	===	==	==:	==:	==	===	==:	
4. SCHEDULE DATA							. <b></b> .			-					===	==:		==	:	:		==:	==:	===
	0	o I	01	o I	0	01	010	)   	o I	0	11	1	1	1	1	1	1	1	1	1	2	2	2	2
																								3
Design Day	- <b></b> 		 	. – - I		 I I		 c   :	 x	 x l	  x	 x l	 х	   x	- <u>-</u> - l x	·	   x	 I x	l x	lх	   x	 I	· 	 
Weekday		ľ		i							x	:			:	:	:	:	:	:	:	:		ii
Saturday		ľ		i	*	i	j	İ	İ	i	İ	j				ĺ		İ	İ	Ì	İ	İ		i i
Sunday	İ	İ		į		İİ	Ì	ĺ	İ	ĺ	İ				ĺ			ĺ						
Cooling Available During					i=:	=== 1 P	=== er:	io:	== d	== ?	=== N	:== [	==	:	===	==:	===	==	==:	==:	==:	===	==:	===
=======================================	===	==	===	===	==	===	===	==	==	==		==	==	===	==:	==:	==:	==	==:	==	==	==:	==:	
	JA																							
Central Heating Central Cooling			XX	XX	X	xx   	XXX	:			xx			ζX				ХХ		XX	X:	ХХ	X:	XX

Name: Auditorium - DDC Type: CONSTANT VOLUME - Single Zon Prepared by: EINHORN YAFFEE PRESCO	
1. SYSTEM NAME AND TYPE	
Name: Auditorium - D Type: CONSTANT VOLUM Number of Zones.: 1	DC
2. SYSTEM DESCRIPTION	
COOLING SYSTEM DATA	Y
Is Central Cooling Used?	20000.0 CFM
Supply IIII	0.100
Coil Bypass Factor	N
Fan Cycled for Cooling?	Not Used
Supply Air Reset:	NOC USEC
HEATING SYSTEM DATA	Y
<pre>Is Central Heating Used? Fan Cycled for Heating?</pre>	Ŋ
Supply Air Reset:	Not Used
OUTDOOR VENTILATION DATA	NOT OBCA
Type of Control:	Constant Airflow Rate
Design Ventilation Airflow:	5000.0 CFM
Dampers Open During Unocc Per.:	N
Damper Leak Rate:	2 %
SUPPLY DUCT DATA	
Duct Heat Gain:	2 %
Duct Leakage Rate:	5 %
RETURN PLENUM DATA	
Is a Return Plenum Used?	N
SUPPLY FAN DATA	Declared Inclined on Ninfeil
Fan Type:	Backward Inclined or Airfoil
Configuration:	Draw-Thru
Fan Total Static:	2.00 in.wg. 54 %
Fan Efficiency	<b>54</b> %
RETURN FAN DATA	None
Fan Type:	None
OUTDOOR AIR ECONOMIZER Outdoor Economizer Type:	Integrated Enthalpy
OA Upper Cutoff Temp:	95.0 F
OA Lower Cutoff Temp	0.0 F
PREHEAT COIL	
Preheat Coil Used?	N
PRECOOL COIL	
Precool Coil Used?	N
HUMIDIFICATION	
Humidification System Used?	N
DEHUMIDIFICATION	
Dehumidification System Used?	N
VENTILATION HEAT RECLAIM	
Reclaim Unit Type:	None
SAFETY FACTORS	
Sensible Cooling Factor:	0 %
Latent Cooling Factor:	0 %
Heating Factor:	0 %
	=======================================

Type: CONSTANT VOLUME - Single Zone CAV HAP v3.0
Prepared by: EINHORN YAFFEE PRESCOTT Page
***********************
3. ZONE DATA
ZONE 1 (All Zones the Same)
ZONE 1 (All Zones the Same) T-Stat Occupied Cooling(F): 75.0
Unoccupied Cooling(F): 85.0
Occupied Heating(F): 70.0
Unoccupied Heating(F): 55.0
Throttling Range(F): 3.0
Zone Heating Unit Type: None
Trip Temperature(F):
Design Supply Temperature(F):
Fan Total Static(in.wg.):
Fan Efficiency(%):
Zone Terminal Type Diffuser
Reheat Coil?
Direct Exhaust Airflow(CFM): 0.0
Direct Exhaust Fan kW(kW): 0.0
4. SCHEDULE DATA
HOURLY TSTAT SCHEDULES  0 0 0 0 0 0 0 0 1 1 1 1 1 1 1 1 1 2 2 2 2
0 1 2 3 4 5 6 7 8 9 0 1 2 3 4 5 6 7 8 9 0 1 2 3
Design Day
Saturday
Sunday
Cooling Available During Unoccupied Period ? N
MONTHLY SCHEDULES   JAN   FEB   MAR   APR   MAY   JUN   JUL   AUG   SEP   OCT   NOV   DEC
Central Heating   XXX
Central Cooling

Name: Perimeter Fan Coil Units - D	DDC 12-30	)-94
Type: TERMINAL UNITS - 2-Pipe Fan		3.04
Prepared by: EINHORN YAFFEE PRESCO	)TT Page	
*********	*******	***
1. SYSTEM NAME AND TYPE		
Name: Perimeter Fan Type: TERMINAL UNITS Number of Zones.: 14	Coil Units - DDC S - 2-Pipe Fan Coils	
	:======================================	
2. SYSTEM DESCRIPTION		
COOLING SYSTEM DATA		
Supply Air:	55.0 F	
Fan Cycled for Cooling?	N	
Coil Bypass Factor:	0.100	
HEATING SYSTEM DATA	NT.	
Fan Cycled for Heating?	N	
OUTDOOR VENTILATION DATA	N	
Common Ventilation System Used? SAFETY FACTORS	21	
Sensible Cooling Factor:	0 %	
Latent Cooling Factor:	0 %	
Heating Factor:	0 %	
OUTDOOR VENTILATION DATA		
Type of Control:	Constant Airflow Rate	
Design Ventilation Airflow:	0.0 CFM/person	
=======================================		===
3. ZONE DATA		
ZONE	1 (All Zones the Same)	
T-Stat Occupied Cooling(F):	75.0 85.0	
Unoccupied Cooling(F): Occupied Heating(F):	70.0	
Unoccupied Heating(F):	55.0	
Throttling Range(F):	3.0	
Zone Terminal Type:	Fan Coil	
Fan Total Static(in.wg.):	0.25	
Fan Efficiency(%):	54	
	-======================================	====

Name: Perimeter Fan Coil Units - DDC  Type: TERMINAL UNITS - 2-Pipe Fan Coils  Prepared by: EINHORN YAFFEE PRESCOTT  **********************************	12-30-94 HAP v3.04 Page 2
4. SCHEDULE DATA	========
HOURLY TSTAT SCHEDULES  0 0 0 0 0 0 0 0 0 1 1 1 1 1 1 1 1 1 1	1 2 2 2 2  9 0 1 2 3
Design Day.	
Cooling Available During Unoccupied Period ? N	
MONTHLY SCHEDULES   JAN   FEB   MAR   APR   MAY   JUN   JUL   AUG   SEP   OC	T NOV DEC
Terminal Heating   XXX	X   XXX   XXX

Name: Basement Classrooms (2) - DDC	12-30-94
Type: CONSTANT VOLUME - Single Zone	CAV HAP v3.04
Prepared by: EINHORN YAFFEE PRESCOT	T Page 1
*********	***********
1. SYSTEM NAME AND TYPE	
Name Basement Classr	ooms (2) - DDC
Type CONSTANT VOLUME	- Single Zone CAV
Number of Zones.: 1	
	=======================================
2. SYSTEM DESCRIPTION	
COOLING SYSTEM DATA	••
Is Central Cooling Used?	Y
Supply Air:	55.0 F
Coil Bypass Factor	0.100
Fan Cycled for Cooling?	N
Supply Air Reset:	Not Used
HEATING SYSTEM DATA	
Is Central Heating Used?	Y
Fan Cycled for Heating?	N
Supply Air Reset:	Not Used
OUTDOOR VENTILATION DATA	m
Type of Control:	Constant Airflow Rate
Design Ventilation Airflow:	1650.0 CFM
Dampers Open During Unocc Per.:	N
Damper Leak Rate:	2 %
SUPPLY DUCT DATA	2 %
Duct Heat Gain:	2 %
Duct Leakage Rate:	5 % .
RETURN PLENUM DATA	NT
Is a Return Plenum Used?	N
SUPPLY FAN DATA	Forward Curved
Fan Type:	Draw-Thru
Configuration:	1.00 in.wg.
Fan Total Static	54 %
Fan Efficiency	31 0
RETURN FAN DATA	None
Fan Type:	Notice
OUTDOOR AIR ECONOMIZER Outdoor Economizer Type:	None
PREHEAT COIL	1010
Preheat Coil Used?	N
PRECOOL COIL	<del>-</del> '
Precool Coil Used?	N
HUMIDIFICATION	
Humidification System Used?	N
DEHUMIDIFICATION	
Dehumidification System Used?	N
VENTILATION HEAT RECLAIM	
Reclaim Unit Type:	None
SAFETY FACTORS	
Sensible Cooling Factor:	0 %
Latent Cooling Factor:	0 %
Heating Factor:	0 %
=======================================	

Name: Basement Classrooms (2) - DDC 12-30-94 Type: CONSTANT VOLUME - Single Zone CAV HAP v3.04 Prepared by: EINHORN YAFFEE PRESCOTT Page 2 ************************************							
3. ZONE DATA							
ZONE T-Stat Occupied Cooling(I Unoccupied Cooling(I Occupied Heating(I Unoccupied Heating(I Throttling Range(I	F): F): F):	75.0 35.0 70.0 55.0 3.0	nes the Same)				
Zone Heating Unit Type(I Trip Temperature(I Design Supply Temperature(I Fan Total Static(in.wg. Fan Efficiency(§ Zone Terminal Type(§ Reheat Coil	F): F): .): %): : Diff ? M):	None					
4. SCHEDULE DATA							
HOURLY TSTAT SCHEDULES   0   0			1   1   1   1   1   1   2   2   2   2				
Design Day							
Cooling Available During Unoo	ccupied Per	iod ? N					
MONTHLY SCHEDULES   JAN	FEB   MAR   AP	UUL   NUL   YAM   S	AUG   SEP   OCT   NOV   DEC				
Central Heating   XXX   Central Cooling	xxx   xxx   xx	xxx   xxx   xxx					

Name: Auditorium - Baseline Type: CONSTANT VOLUME - Sing Prepared by: EINHORN YAFFEE	PRESCOTT		12-30-94 HAP v3.04 Page 1
1. SPACE SELECTION	*****	****	
Space Name	Qty	Space Name	Qty
SPACES IN ZONE 1 (Zone 1)			
12. Auditorium	1		

Name: Classroom 1 & 6 (Flr 1 Type: CONSTANT VOLUME - Single Prepared by: EINHORN YAFFEE PRESENTED PROPERTY OF THE PROPERTY OF	e Zone CAV RESCOTT		12-30-94 HAP v3.04 Page 1
1. SPACE SELECTION	<b></b>		
Space Name	Qty	Space Name	Qty
SPACES IN ZONE 1 (Zone 1)			
3. Classrm 1&6 (Typ 1 & 2)	1		

Name: Classroom 2 & 3 (Flr 1 Type: CONSTANT VOLUME - Single Prepared by: EINHORN YAFFEE P:	e Zone CAV RESCOTT	********	12-30-94 HAP v3.04 Page 1						
1. SPACE SELECTION									
Space Name	Qty	Space Name	Qty						
SPACES IN ZONE 1 (Zone 1)		:=====================================							
4. Classrm 2&3 (Typ 1 & 2)	1								

Name: Classroom 4 (Flr 1 & 2 Type: CONSTANT VOLUME - Sing: Prepared by: EINHORN YAFFEE: **********************************	le Zone PRESCOTT		12-30-94 HAP v3.04 Page 1
1. SPACE SELECTION			
Space Name	Qty	Space Name	Qty
SPACES IN ZONE 1 (Zone 1)			
5. Classrm 4 (Typ 1 & 2)	1		

Name: Classroom 5 (Flr 1 & 2) Type: CONSTANT VOLUME - Singl Prepared by: EINHORN YAFFEE F *********************************	e Zone RESCOTT		12-30-94 HAP v3.04 Page 1
1. SPACE SELECTION			
Space Name	Qty	Space Name	Qty
SPACES IN ZONE 1 (Zone 1)			
6. Classrm 5 (Typ 1 & 2)	1		

Name: Classrooms 1 & 6 (3rd F Type: CONSTANT VOLUME - Singl Prepared by: EINHORN YAFFEE F *********************************	e Zone C. RESCOTT		12-30-94 HAP v3.04 Page 1
1. SPACE SELECTION			
Space Name	Qty	Space Name	Qty
SPACES IN ZONE 1 (Zone 1)	=======		
13. Classrm 1&6 (3rd Flr)	1		

AIR Name: Classrooms 2 & 3 (3rd F Type: CONSTANT VOLUME - Singl Prepared by: EINHORN YAFFEE P	e Zone CAV RESCOTT		12-30-94 HAP v3.04 Page 1
1. SPACE SELECTION			
Space Name	Qty	Space Name	Qty
SPACES IN ZONE 1 (Zone 1)			
14. Classrm 2&3 (3rd Flr)	1		

Name: Classroom 4 (3rd Flr) Type: CONSTANT VOLUME - Sing Prepared by: EINHORN YAFFEE **********************************	PRESCOTT		12-30-94 HAP v3.04 Page 1
1. SPACE SELECTION			
Space Name	Qty	Space Name	Qty
SPACES IN ZONE 1 (Zone 1)			
15. Classrm 4 (3rd Flr)	1		

Name: Classroom 5 (3rd Flr) Type: CONSTANT VOLUME - Sing	le Zone	CAV	12-30-94 HAP v3.04
Prepared by: EINHORN YAFFEE :			Page 1
1. SPACE SELECTION			
Space Name	Qty	Space Name	Qty
SPACES IN ZONE 1 (Zone 1)	======		
16. Classrm 5 (3rd Flr)	1	·	·

Name: Perimeter Fan Coil Unit Type: TERMINAL UNITS - 2-Pip Prepared by: EINHORN YAFFEE I	pe Fan Co PRESCOTT	oils	12-30-94 HAP v3.04 Page 1
1. SPACE SELECTION			
Space Name		Space Name	Qty
SPACES IN ZONE 1 (Zone 1)			
2. Basement Offices	1		
SPACES IN ZONE 2 (Zone 2)			
7. North Offices (Typ 1 &	2 2		
SPACES IN ZONE 3 (Zone 3)			
8. East Offices (Typ 1 & 2	2) 2	<b></b>	
SPACES IN ZONE 4 (Zone 4)			
9. South Offices (Typ 1 &	2 2		
SPACES IN ZONE 5 (Zone 5)			
10. West Offices (Typ 1 & 2	2) 2		
SPACES IN ZONE 6 (Zone 6)			
17. North Offices (3rd Flr)	) 1		
SPACES IN ZONE 7 (Zone 7)			
18. East Offices (3rd Flr)	1		
SPACES IN ZONE 8 (Zone 8)	======	:=====================================	
19. South Offices (3rd Flr)			
SPACES IN ZONE 9 (Zone 9)			
20. West Offices (3rd Flr)	1		
SPACES IN ZONE 10 (Zone 10)			,
21. Inner Offices North	1		
SPACES IN ZONE 11 (Zone 11)			
22. Inner Offices East	1		
SPACES IN ZONE 12 (Zone 12)			
23. Inner Offices South	1		
SPACES IN ZONE 13 (Zone 13)			
24. Inner Offices West	1		
		•	

Name: Perimeter Fan Coil Unit Type: TERMINAL UNITS - 2-Pip Prepared by: EINHORN YAFFEE P	e Fan Coils RESCOTT	*******	12-30-94 HAP v3.04 Page 2
1. SPACE SELECTION (CONTINUED	)		
Space Name	Qty	Space Name	Qty
SPACES IN ZONE 14 (Zone 14)			
25. South Offices (2nd Flr)	1		

Name: Basement Classrooms (2) Type: CONSTANT VOLUME - Singl Prepared by: EINHORN YAFFEE P ***********************************	e Zone CAV RESCOTT	*****	12-30-94 HAP v3.04 Page 1
1. SPACE SELECTION			
Space Name	Qty	Space Name	Qty
SPACES IN ZONE 1 (Zone 1)			
1. Basement Classrooms	1		

Name: Auditorium - PLC Type: CONSTANT VOLUME - Sing Prepared by: EINHORN YAFFEE **********************************	PRESCOTT		12-30-94 HAP v3.04 Page 1
1. SPACE SELECTION			
Space Name	Qty	Space Name	Qty
SPACES IN ZONE 1 (Zone 1)			
12. Auditorium	1		· 

# AIR SYSTEM INPUT DATA r Fan Coil Units - PLC

Type: Prepar	Perimeter Fan Coil Un TERMINAL UNITS - 2-1 red by: EINHORN YAFFE	Pipe Fan Coils E PRESCOTT	*****	12-30-94 HAP v3.04 Page 1
1. SPA	ACE SELECTION			
			Space Name	
	IN ZONE 1 (Zone 1)		=======================================	=======================================
	Basement Offices	1		
	IN ZONE 2 (Zone 2)			
7.	North Offices (Typ 1	& 2 2		
	IN ZONE 3 (Zone 3)			
8.	East Offices (Typ 1 8	§ 2) 2		
	IN ZONE 4 (Zone 4)			
	South Offices (Typ 1	& 2 2		
SPACES	IN ZONE 5 (Zone 5)			
10.	West Offices (Typ 1 8			
	IN ZONE 6 (Zone 6)			
	North Offices (3rd F			
SPACES	S IN ZONE 7 (Zone 7)			
18.	East Offices (3rd Fl	•		
	S IN ZONE 8 (Zone 8)			
	South Offices (3rd F			.===========
SPACES	S IN ZONE 9 (Zone 9)			
20.	West Offices (3rd Fl	r) 1		
SPACES	S IN ZONE 10 (Zone 10)	)		
21.	Inner Offices North	1		
SDACES	S IN ZONE 11 (Zone 11	)		
22.	Inner Offices East	1		
SPACES	S IN ZONE 12 (Zone 12	) .		
23.	Inner Offices South	1		
SPACES	S IN ZONE 13 (Zone 13	)		
	Inner Offices West	1 ====================================	===========	.==========

Name: Perimeter Fan Coil Unit Type: TERMINAL UNITS - 2-Pip Prepared by: EINHORN YAFFEE P ***********************************	e Fan Coils RESCOTT	********	12-30-94 HAP v3.04 Page 2
1. SPACE SELECTION (CONTINUED	)		
Space Name	Qty	Space Name	Qty
SPACES IN ZONE 14 (Zone 14)			
25. South Offices (2nd Flr)	1		

Name: Basement Classrooms (2) Type: CONSTANT VOLUME - Sing: Prepared by: EINHORN YAFFEE	le Zone CAV		12-30-94 HAP v3.04 Page 1
*****************		*******	-
1. SPACE SELECTION			
Space Name	Oty	Space Name	Qty
-	~ 1	-	•
-	~ 1	space Name	•

Name: Auditorium - DDC Type: CONSTANT VOLUME - Sing Prepared by: EINHORN YAFFEE **********************************	PRESCOT'	Γ	12-30-94 HAP v3.04 Page 1
1. SPACE SELECTION			
Space Name	Qty	Space Name	Qty
SPACES IN ZONE 1 (Zone 1)			
12. Auditorium	1		

Name: Perimeter Fan Coil Unit Type: TERMINAL UNITS - 2-Pip Prepared by: EINHORN YAFFEE P	e Fan Coils RESCOTT		12-30-94 HAP v3.04 Page 1
1. SPACE SELECTION			
Space Name	Qty	Space Name	Qty
SPACES IN ZONE 1 (Zone 1)			
	1	· <b></b>	
SPACES IN ZONE 2 (Zone 2)			
7. North Offices (Typ 1 &		<b></b>	
SPACES IN ZONE 3 (Zone 3)		.======================================	:========
8. East Offices (Typ 1 & 2		=======================================	
SPACES IN ZONE 4 (Zone 4)	<b>_</b>	. <b></b>	
9. South Offices (Typ 1 &		:======================================	
SPACES IN ZONE 5 (Zone 5)			
10. West Offices (Typ 1 & 2	2) 2		
SPACES IN ZONE 6 (Zone 6)			
17. North Offices (3rd Flr)			
SPACES IN ZONE 7 (Zone 7)	=========	=======================================	:======================================
18. East Offices (3rd Flr)			
=======================================			:========
SPACES IN ZONE 8 (Zone 8)			
19. South Offices (3rd Flr)		=======================================	-========
SPACES IN ZONE 9 (Zone 9)	. <b></b>		
20. West Offices (3rd Flr)			
SPACES IN ZONE 10 (Zone 10)			
21. Inner Offices North	1		
SPACES IN ZONE 11 (Zone 11)			
22. Inner Offices East	<b></b>		
SPACES IN ZONE 12 (Zone 12)		=======================================	
23. Inner Offices South			=======================================
SPACES IN ZONE 13 (Zone 13)	<b></b> -		
24. Inner Offices West	1 ===========		

Name: Perimeter Fan Coil Units - DDC 12-30-9 Type: TERMINAL UNITS - 2-Pipe Fan Coils HAP v3.0 Prepared by: EINHORN YAFFEE PRESCOTT Page								
1. SPACE SELECTION (CONTINUED	·)							
Space Name	Qty	Space Name	Qty					
SPACES IN ZONE 14 (Zone 14)								
25. South Offices (2nd Flr)	1							

Name: Stair Towers		01-06-95			
Type: TERMINAL UNITS - Convective Htg and Clg					
Prepared by EINHORN YAFI	EE PRESCOTT	Page 1			
*******	*********	*****			
1. SYSTEM NAME AND TYPE					
Name Stair	Towers				
Type TERM	NAL UNITS - Convective Htg and	Clg			
Number of Zones.: 2	·				
=======================================		==========			
2. SYSTEM DESCRIPTION					
COOLING SYSTEM DATA					
Is Cooling System Used.	? N				
HEATING SYSTEM DATA					
Is Heating System Used.	? Y				
OUTDOOR VENTILATION DATA					
Common Ventilation Syste	m Used? N				
SAFETY FACTORS Sensible Cooling Factor	0 %				
Latent Cooling Factor					
Heating Factor	: 0 %				
=======================================		=======================================			
3. ZONE DATA					
ZONE	1 (All Zones t	he Same)			
T-Stat Zone Setpoint	(F): 70.0				
=======================================		=======================================			
4. SCHEDULE DATA	:======================================				
HOURLY TSTAT SCHEDULES	0 0 0 0 0 0 0 0 0 1 1 1 1 1 1	1 1 1 1 2 2 2 2			
HOURLI ISIAI SCHEDULES	0 1 2 3 4 5 6 7 8 9 0 1 2 3 4 5	6 7 8 9 0 1 2 3			
Design Day	X   X   X   X   X   X   X   X   X   X	X   X   X   X   X   X   X   X			
Weekday	X X X X X X X X X X X X X X X X X X X	X   X   X   X   X   X   X   X   X   X			
Saturday	X   X   X   X   X   X   X   X   X   X	x   x   x   x   x   x   x   x   x			
Sunday					
MONTHLY SCHEDULES	JAN   FEB   MAR   APR   MAY   JUN   JUL   AUG	SEP OCT NOV DEC			
Terminal Heating		xxx   xxx   xxx			
=======================================	=======================================	=======================================			

	AIR SYSTEM II	NPUT DATA	
Name: Corridors			01-06-95
Type: TERMINAL UNITS -	Convective Htg	and Clq	HAP v3.04
Prepared by: EINHORN YAF	FEE PRESCOTT	7	Page 1
************	++++++++++	*******	
****		, , , , , , , , , , , , , , , , , , , ,	
1. SYSTEM NAME AND TYPE			
Name Corr	idors		
Type TERM	INAL UNITS - (	Convective Htg	and Clg
Number of Zones.: 3			·
=======================================	=========	========	=======================================
2. SYSTEM DESCRIPTION			
COOLING SYSTEM DATA			
	າ	N	
Is Cooling System Used.		TA	
HEATING SYSTEM DATA	•	37	
Is Heating System Used.		Y	
OUTDOOR VENTILATION DATA			
Common Ventilation Syst	em Used?	N	
SAFETY FACTORS			
Sensible Cooling Factor	:	0 %	
Latent Cooling Factor	:	0 %	
Heating Factor	:	0 %	
	=========	============	=======================================
3. ZONE DATA			
ZONE		1 (All Zor	es the Same)
T-Stat Zone Setpoint	(F):	70.0	
=======================================	···(-/· =============		=======================================
=======================================			
4 COMEDITE DATA			
4. SCHEDULE DATA			
HOURLY TSTAT SCHEDULES			1 1 1 1 1 2 2 2 2
HOURLY TSTAT SCHEDULES	0 0 0 0 0 0 0 0	17 0 0 0 1 1 1 2 3	4 5 6 7 8 9 0 1 2 3
	10 1 2 3 4 3 0	1/[0]9[0]1[2]3	
			VIVIVIVIVIVIVIVIVIVI
Design Day	X X X X X X		
Weekday	X   X   X   X   X   X	A   A   A   A   A   A   A   A	
	$ \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x}$	$ \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x} \mathbf{x}$	x   x   x   x   x   x   x   x   x   x
Sunday	X X X X X X X	X X X X X X X X	x x x x x x x x x x
=======================================	=======================================	=======================================	
MONTHLY SCHEDULES	JAN FEB MAR A	PR   MAY   JUN   JUL	AUG   SEP   OCT   NOV   DEC
Terminal Heating	XXX   XXX   XXX   X	xx	
=======================================			

Name: Stair Towers			01-06-95
Type: TERMINAL UNITS - Conve	ctive Htg and	d Clg	HAP v3.04
Prepared by: EINHORN YAFFEE Pl	RESCOTT		Page 1
********	*****	******	*****
1. SPACE SELECTION			
Space Name	Qty	Space Name	Qty
=======================================			========
SPACES IN ZONE 1 (Zone 1)			
Z/. Typicai boazi io	2		
======================================	=======	===========	
SPACES IN ZONE 2 (Zone 2)			
28. Typical Stair Tower W	2		
	_	=======================================	========

Name: Corridors			01-06-95
Type: TERMINAL UNITS - Conv	rective H	tg and Clg	HAP v3.04
Decembered by, FINHODN VAFFEE	PRESCOTT		Page 1
*****************	******	*******	*****
1. SPACE SELECTION			
Name -		Space Name	Qty
Space Name	QLY		
SPACES IN ZONE 1 (Zone 1)	:=	<del></del>	
SPACED IN ZONE I (ZONE I)	<b></b>		
29. Corridors	1		
=======================================	=======	=======================================	=========
SPACES IN ZONE 2 (Zone 2)			
11. Cloak Rm (Typ 4/Flr)	8	29. Corridors	1
=======================================	:======		========
SPACES IN ZONE 3 (Zone 3)			
		30. Cloak Rm 3rd Flr (	
29. Corridors			-16 -/ -

Plant: Cooling Plant - Baseline Prepared By: EINHORN YAFFEE PRESCOTT ***********************************	*****	01-09-95 Page 1 ******
PLANT NAME, CLASSIFICATION & TYPE		
Plant name: Cooling Tooling Tooling Type: Water-Cooling Type of simulation model: Computer-Type of chiller: W/C Centrype of heat rejection model: Open Cool	oled Chill -Generated rifugal Ling Tower	er Model
AIR SYSTEM SELECTIONS		
Air System Name	Type	Quantity
1. Auditorium - Baseline	(SZ CAV) (SZ CAV) (SZ CAV) (SZ CAV) (SZ CAV) (SZ CAV) (SZ CAV) (SZ CAV) (SZ CAV) (SZ CAV) (SZ CAV)	4 4 2 2 2 2 1 1 1
WATER-COOLED CENTRIFUGAL CHILLER DATA		
Design ECWT  Design LCHWT  Chiller capacity at design	381.7 Tons 85.0 F 44.0 F 305.0 Tons 0.700 kW/T N 20.0 %	

Plant: Cooling Plant - Baseline	01-09-95
Prepared By: EINHORN YAFFEE PRESCOTT	Page 2
************	*****

### PART-LOAD PERFORMANCE DATA

LCHWT = 44.0 F					
% Load	   % kW	ECWT			
100.0 90.0 80.0 70.0 60.0 50.0 40.0 30.0 20.0	100.0 85.0 72.0 61.0 51.0 43.0 37.0 31.0 26.0	85.0 82.5 80.0 77.5 75.0 72.5 70.0 67.5			

\_\_\_\_\_\_

#### PUMP AND PIPING SYSTEM DATA

Pump or Piping System	Delta-T (F)	Head		encies Elec (%)	Pump Power (kW)	Piping Gain/Loss (%)
Chilled Water	10.0	51.00	70.0	85.0	11.82	5.0
Condenser Water	10.0	37.50	70.0	80.0	11.07	

# FREE COOLING DATA

#### OPEN COOLING TOWER DATA

Design inlet water temperature...: 95.0 F
Design outlet water temperature...: 85.0 F
Tower design airflow rate...: 250.0 CFM/Ton
Tower fan power....: 12.5 kW
Minimum outlet temperature...: 60.0 F
Use fan cycling or water bypass...? Fan Cycling
Make-up water temperature...: 55.0 F

Prepared By: E	Plant - Basel INHORN YAFFEE *******	PRESCOTT	*****	*****	*****	01-06-95 Page 1
PLANT NAME, CI	ASSIFICATION &	TYPE				
Plant name Classificati Type	on	: Heati	ng ater Boil		.e	
AIR SYSTEM SEI	ECTIONS					
Air Syste	m Name		Pre-Heat	Central	Category Terminal	Zone
	ım - Baseline			1	_	-
	1 1 & 6 (Flr 1			4	<del>-</del>	-
	1 2 & 3 (Flr 1 1 4 (Flr 1 & 2)			4 2	- -	<u>-</u>
	1 5 (Flr 1 & 2)			2	-	-
6. Classroom	ns 1 & 6 (3rd F	'lr)		2	-	-
7. Classroom	ns 2 & 3 (3rd F	`lr)		2	-	-
	1 4 (3rd Flr)			1	-	-
	1 5 (3rd Flr)			1	<del>-</del>	<u>-</u>
	Fan Coil Unit			1 1	<del>-</del>	- -
	Classrooms (2)			2	_	_
	· · · · · · · · · · · · · · · · · · ·			1	-	-
Gross output Energy input Overall effi	ximum heating at design at design	: : .gn:	4474.0 6391.4 70.0	MBH MBH		
Combustion a	gy type ir blower kW	:	Nat. Gas 0.000	kW		<b></b>
	LOAD PERFORMAN					
% Load Over	call Eff. (%)	% Load	Overall	Eff. (%)		
90	70.0	40	60	0.0		
80	70.0	30		0.0		
70	70.0	20		0.0		
60 50	70.0 70.0	10 0		).0 ).0		
	, , , , , , , , , , , , , , , , , , ,	<b></b>				

Plant: Heating Plant - Baseline Prepared By: EINHORN YAFFEE PRESCOTT ***********************************								
PUMP AND PIPING SYSTEM DATA								
		Pump	Efficie	encies	Pump	Piping		
Pump or	Delta-T	Head	Mech	Elec	Power	Gain/Loss		
Piping System	(F)	(ft wg)	(왕)	(왕)	(kW)	(왕)		
	20.0	75.00	70.0	80.0	11.28	0.0		
Hot Water	20.0	73.00	,0.0	00.0	11.20	0.0		

Plant: Cooling Plant - PLC Prepared By: EINHORN YAFFEE PRESCOTT ***********************************	01-06-95 Page 1 ******						
PLANT NAME, CLASSIFICATION & TYPE							
Plant name: Cooling Plant - PLC Classification: Cooling Type: Water-Cooled Chiller Type of simulation model: Computer-Generated Type of chiller: W/C Centrifugal Type of heat rejection model: Open Cooling Tower Model							
AIR SYSTEM SELECTIONS	. <b></b>	<b></b>					
Air System Name	Time	Quantity					
2. Classroom 1 & 6 (Flr 1 & 2) 3. Classroom 2 & 3 (Flr 1 & 2) 4. Classroom 4 (Flr 1 & 2) 5. Classroom 5 (Flr 1 & 2) 6. Classrooms 1 & 6 (3rd Flr) 7. Classrooms 2 & 3 (3rd Flr) 8. Classroom 4 (3rd Flr) 9. Classroom 5 (3rd Flr) 13. Auditorium - PLC 14. Perimeter Fan Coil Units - PLC 16. Basement Classrooms (2) - PLC	(SZ CAV) (SZ CAV) (SZ CAV) (SZ CAV) (SZ CAV) (SZ CAV) (SZ CAV) (SZ CAV) (SZ CAV) (SZ CAV)	4 2 2 2 2 1 1 1					
Design ECWT:  Design LCHWT:  Chiller capacity at design:  Chiller input power at design:  Is chilled water reset used?	02.1 Tons 85.0 F 44.0 F 05.0 Tons 0.700 kW/To N 20.0 %	on					

Plant: Cooling Plant - PLC	01-06-95	5
Prepared By: EINHORN YAFFEE PRESCOTT	Page 2	2
**************	**********	*

# PART-LOAD PERFORMANCE DATA

% Load	LCHWT = 44.0 F						
90.0 85.0 82.5 80.0 72.0 80.0 70.0 61.0 77.5 60.0 51.0 75.0 50.0 43.0 72.5 40.0 37.0 70.0 30.0 31.0 67.5	   % Load	   % kW	!!				
	90.0 80.0 70.0 60.0 50.0 40.0 30.0	85.0 72.0 61.0 51.0 43.0 37.0 31.0	82.5 80.0 77.5 75.0 72.5 70.0 67.5				

## PUMP AND PIPING SYSTEM DATA

Pump or Piping System	Delta-T (F)	Pump Head (ft wg)	Efficie Mech (%)	encies Elec (%)	Pump Power (kW)	Piping Gain/Loss (%)
Chilled Water	10.0	51.00	70.0	85.0	11.82	5.0
Condenser Water	10.0	37.50	70.0	80.0	11.07	

#### FREE COOLING DATA

Туре о	of	free	cooling	 	 :	Not	Used	i			
		_ <b></b> -		 	 		<b>-</b> -	- <b>-</b>	- <b></b> -	 	 

#### OPEN COOLING TOWER DATA

		_
Design inlet water temperature:	95.0	F
Design outlet water temperature:		_
Tower design airflow rate:	250.0	CFM/Ton
Tower fan power:	12.5	kW
Minimum outlet temperature:	60.0	F
Use fan cycling or water bypass?	Fan Cycl:	ing
Make-up water temperature:		

repared	ating Plant - 1 By: EINHORN YAI	FFEE PRES	COTT ****	****	*****	*****	01-06-95 Page 1
PLANT NAM	E, CLASSIFICAT	ION & TYP	E				
Plant n Classif Type	ameication	: : 	Heati Hot W	ng ater Boil			
AIR SYSTE	M SELECTIONS						
Air	System Name			Pre-Heat	Central	Category Terminal	
2. Clas	sroom 1 & 6 (F)				4		_
3. Clas	sroom 2 & 3 (F	lr 1 & 2)			4	-	-
4. Clas	sroom 4 (Flr 1	& 2)			2	-	-
	sroom 5 (Flr 1				2	_	-
6. Clas	srooms 1 & 6 (	3rd Flr).			2	-	-
	srooms 2 & 3 (				2	-	-
	sroom 4 (3rd F)				1	-	-
	sroom 5 (3rd F				1	_	<u>-</u>
	r Towers				1 1	<del>-</del>	_
	torium - PLC meter Fan Coil				1	_	_
	idors				1	_	_
	ment Classroom				2	_	_
OT WATER	BOILER DATA				  MRH		
	utput at design			4474.0			
	input at design			6391.4	MBH		
	efficiency at			70.0	<b>ઝ</b>		
Combust	energy type ion air blower	k₩	:	Nat. Gas 0.000	kW		
BOILER PART-LOAD PERFORMANCE DATA							
% Load	Overall Eff.	 (왕) 왕 	Load	Overall	Eff. (%)		
90	70.0		40	60	0.0		
80	70.0		30	60			
70	70.0		20	60	0.0		
70 60	70.0 70.0		20 10		).0 ).0		

Plant: Heating Plant Prepared By: EINHORN **********	YAFFEE PRI	ESCOTT	*****	*****	*****	01-06-95 Page 2 ******
PUMP AND PIPING SYSTE	M DATA			- <b>-</b>		
Pump or Piping System	Delta-T (F)	Pump Head (ft wg)	Efficie Mech (%)	encies Elec (%)	Pump Power (kW)	Piping Gain/Loss (%)
Hot Water	20.0	75.00	70.0	80.0	11.28	5.0

PLANT INPUT Plant: Cooling Plant - DDC Prepared By: EINHORN YAFFEE PRESCOTT ***********************************	01-06-95 Page 1					
PLANT NAME, CLASSIFICATION & TYPE						
Plant name: Cooling Plant - DDC Classification: Cooling Type: Water-Cooled Chiller Type of simulation model: Computer-Generated Type of chiller: W/C Centrifugal Type of heat rejection model: Open Cooling Tower Model						
AIR SYSTEM SELECTIONS						
Air System Name	Type Quantity					
2. Classroom 1 & 6 (Flr 1 & 2)	(SZ CAV) 4 (SZ CAV) 4 (SZ CAV) 2 (SZ CAV) 2 (SZ CAV) 2 (SZ CAV) 2 (SZ CAV) 1 (SZ CAV) 1 (SZ CAV) 1 (SZ CAV) 1 (SZ CAV) 1 (SZ CAV) 2 (SZ CAV) 2					
Design ECWT	402.5 Tons 85.0 F 44.0 F 305.0 Tons 0.700 kW/Ton N 20.0 %					

Plant: Cooling Plant - DDC		01-06-95
Prepared By: EINHORN YAFFEE	PRESCOTT	Page 2
*******	*******	******

#### PART-LOAD PERFORMANCE DATA

1	l ECWT
% Load % kW	(F)
100.0	82.5 80.0 77.5 75.0 72.5 70.0 67.5

# PUMP AND PIPING SYSTEM DATA

Pump or Piping System	Delta-T (F)	<b>-</b> _	Efficie Mech (%)	encies Elec (%)	Pump Power (kW)	Piping Gain/Loss (%)
Chilled Water	10.0	51.00	70.0	85.0	11.82	5.0
Condenser Water		37.50	70.0	80.0	11.07	-

#### FREE COOLING DATA

Type of free cooling:	Not Used

#### OPEN COOLING TOWER DATA

Design inlet water temperature 95.0 F	
Design outlet water temperature 85.0 F	
Tower design airflow rate 250.0 CFM/Ton	
Tower fan power 12.5 kW	
Minimum outlet temperature 60.0 F	
Use fan cycling or water bypass? Fan Cycling	
Make-up water temperature 55.0 F	
	· <b>-</b> -

Dranared F	ating Plant - DDC By: EINHORN YAFFEE	PRESCOTT		*****	*****	01-06-95 Page 1
PLANT NAME	E, CLASSIFICATION	& TYPÉ				
Plant na Classifi	ame	: Heati	ng ater Boil			·
AIR SYSTEM	M SELECTIONS					
Air S	System Name		Hea Pre-Heat	ting Coil Central	Category Terminal	Zone
2. Class	room 1 & 6 (Flr 1			4	-	-
3. Class	eroom 2 & 3 (Flr 1	& 2)		4	-	-
4. Class	sroom 4 (Flr 1 & 2	)		2	-	-
	sroom 5 (Flr 1 & 2			2	-	-
6. Class	rooms 1 & 6 (3rd	Flr)		2 2	_	_
7. Class	srooms 2 & 3 (3rd	Fir)		1	- -	_
8. Class	sroom 4 (3rd Flr). sroom 5 (3rd Flr).			1	_	_
	r Towers			1	-	_
	idors			1	_	-
	corium - DDC			1	-	-
	meter Fan Coil Uni			1	-	-
20. Baset	ment Classrooms (2	) - DDC		2	-	-
Estimate Gross of Energy:	BOILER DATA  ed maximum heating  utput at design  input at design  efficiency at des	: : sign:	4474.0 6391.4 70.0	MBH MBH		<del>-</del>
Fuel or Combust	energy type ion air blower kW.	 ; 	0.000	kW		
BOILER	PART-LOAD PERFORM					
% Load	Overall Eff. (%)	% Load	Overall	Eff. (%)		
90	70.0	40	60	0.0		
80	70.0	30	60	0.0		
70	70.0	20		0.0		
60 50	70.0 70.0	10 0		0.0 0.0		

Plant: Heating Plant - Prepared By: EINHORN Y	AFFEE PRI	ESCOTT	*****	*****	*****	01-06-95 Page 2 *****
PUMP AND PIPING SYSTEM	1 DATA					
Pump or Piping System	Delta-T (F)	Pump Head (ft wg)	Efficie Mech (%)		Pump Power (kW)	Piping Gain/Loss (%)
Hot Water	20.0	75.00	70.0	80.0	11.28	5.0

## BUILDING INPUT DATA

### DUILDING NAME: Building 247 - Baseline    PLANT SELECTION		*****	YAFFEE *****	*****	****	*****	01-06-95 Page 1 *****
Plant Name   Type Quantity			: Bu	ilding 247 -	Basell	ne 	
Plant Name	PLANT SELECTION	ON					
1. Cooling Plant - Baseline	Plant Nat	<b>-</b> - ne			Туре	Quantity	
Max. Power Use	1. Cooling	Plant - Plant -	Baseli Baseli	ne (W/ ne (HW	C CHIL	LER) 1	
Reference Name	MISCELLANEOUS	ELECTR	IC POWE	R USE			
Empty 0.0 NA Empty 0.0 NA Empty 0.0 NA Empty 0.0 NA Empty 0.0 NA  MISCELLANEOUS FUEL USE	Reference Name	e	<u> </u>	Max. Powe		Schedule Name	
Empty 0.0 NA Empty 0.0 NA Empty 0.0 NA Empty 0.0 NA  MISCELLANEOUS FUEL USE  Reference Fuel Fuel Conversion Max. Name Type Units kBTU/Units Use Schedule Name  Empty NG THM 100.0000 0.0 NA Empty NG THM 100.0000 0.0 NA Empty NG THM 100.0000 0.0 NA Empty NG THM 100.0000 0.0 NA Empty NG THM 100.0000 0.0 NA Empty NG THM 100.0000 0.0 NA  Fuel Types: NG=Nat.Gas FO=Fuel Oil PR=Propane RH=Rmt Htg  ELECTRIC RATE  Electric rate					0.0	NA	
Empty 0.0 NA  Empty 0.0 NA  MISCELLANEOUS FUEL USE  Reference Fuel Fuel Conversion Max. Name Type Units kBTU/Units Use Schedule Name  Empty NG THM 100.0000 0.0 NA  Empty NG THM 100.0000 0.0 NA  Empty NG THM 100.0000 0.0 NA  Empty NG THM 100.0000 0.0 NA  Empty NG THM 100.0000 0.0 NA  Empty NG THM 100.0000 0.0 NA  Empty NG THM 100.0000 0.0 NA  Empty NG THM 100.0000 0.0 NA  Fuel Types: NG=Nat.Gas FO=Fuel Oil PR=Propane RH=Rmt Htg  ELECTRIC RATE  Electric rate	<del>-</del> -						
MISCELLANEOUS FUEL USE  Reference Fuel Fuel Conversion Max. Name Type Units kBTU/Units Use Schedule Name  Empty NG THM 100.0000 0.0 NA Empty NG THM 100.0000 0.0 NA Empty NG THM 100.0000 0.0 NA Empty NG THM 100.0000 0.0 NA Empty NG THM 100.0000 0.0 NA  Empty NG THM 100.0000 For NA  Empty NG THM 100.0000 NA  Empty NG THM 100.0000 NA  Empty NG THM 100.0000 NA  Fuel Types: NG=Nat.Gas FO=Fuel Oil FR=Propane RH=Rmt Htg  ELECTRIC RATE  Electric rate							
Reference Fuel Fuel Conversion Max. Name Type Units kBTU/Units Use Schedule Name  Empty NG THM 100.0000 0.0 NA Empty NG THM 100.0000 0.0 NA Empty NG THM 100.0000 0.0 NA Empty NG THM 100.0000 0.0 NA Empty NG THM 100.0000 0.0 NA  Fuel Types: NG=Nat.Gas FO=Fuel Oil PR=Propane RH=Rmt Htg  ELECTRIC RATE  Electric rate	Empty					NA 	
Name         Type         Units         kBTU/Units         Use         Schedule Name           Empty         NG         THM         100.0000         0.0         NA           Empty         NG         THM         100.0000         0.0         NA           Empty         NG         THM         100.0000         0.0         NA           Fuel Types:         NG=Nat.Gas         FO=Fuel Oil         PR=Propane         RH=Rmt         Htg           ELECTRIC         RATE         Electric rate		<b></b>			<b></b> -		
Empty NG THM 100.0000 0.0 NA Empty NG THM 100.0000 0.0 NA Empty NG THM 100.0000 0.0 NA Empty NG THM 100.0000 0.0 NA Empty NG THM 100.0000 0.0 NA Empty NG THM 100.0000 0.0 NA  Fuel Types: NG=Nat.Gas FO=Fuel Oil PR=Propane RH=Rmt Htg  ELECTRIC RATE  Electric rate: Virginia Power - Kwh Only Average building power factor.: NA  FUEL RATES  Natural gas	Name	Type	Units	kBTU/Units	Use	Schedule Name	
Empty NG THM 100.0000 0.0 NA Empty NG THM 100.0000 0.0 NA  Fuel Types: NG=Nat.Gas FO=Fuel Oil PR=Propane RH=Rmt Htg  ELECTRIC RATE  Electric rate			THM	100.0000	0.0	NA	
Empty NG THM 100.0000 0.0 NA  Fuel Types: NG=Nat.Gas FO=Fuel Oil PR=Propane RH=Rmt Htg  ELECTRIC RATE  Electric rate: Virginia Power - Kwh Only Average building power factor: NA  FUEL RATES  Natural gas: Washington Gas Rate Schedule 2 Fuel oil: None Propane: None Remote source heating: None Remote source cooling: None  MISCELLANEOUS DATA  Additional building floor area: 4729.0 sqft							
ELECTRIC RATE  Electric rate	_						
ELECTRIC RATE  Electric rate	Fuel Types: N	 G=Nat.G	as FO=	Fuel Oil PR=	Propan	ne RH=Rmt Htg	
Electric rate: Virginia Power - Kwh Only Average building power factor: NA  FUEL RATES  Natural gas: Washington Gas Rate Schedule 2 Fuel oil: None Propane: None Remote source heating: None Remote source cooling: None MISCELLANEOUS DATA  Additional building floor area: 4729.0 sqft							
Average building power factor: NA  FUEL RATES  Natural gas: Washington Gas Rate Schedule 2 Fuel oil	ELECTRIC RATE					<b></b>	
FUEL RATES  Natural gas: Washington Gas Rate Schedule 2 Fuel oil	Average buil	ding po	wer fac		a Powe	er - Kwh Only	
Natural gas: Washington Gas Rate Schedule 2 Fuel oil: None Propane: None Remote source heating: None Remote source cooling: None  MISCELLANEOUS DATA  Additional building floor area: 4729.0 sqft							
Propane	Natural gas.			: Washing	ton Ga	as Rate Schedule	2
MISCELLANEOUS DATA  Additional building floor area	Propane Remote sourc	e heati	 .ng	: None			
Additional building floor area	Remote sourc			: None			<b></b>
Additional building floor area	MISCELLANEOUS	DATA					
	Additional b Source elect	uilding	floor nerating	area		: 4729. : 100.0	_

#### BUILDING INPUT DATA

Prepared by: HAP v3.04						01-06-95 Page
BUILDING NAME		: Bu	ilding 247 -	PLC	******	
<del>-</del>						
PLANT SELECTI	ON	<b>-</b>				
Plant Na					Quantity	<b></b>
5. Cooling	Plant - Plant -	PLC	(W/	C CHIL BOILE	LER) 1	
MISCELLANEOUS			R USE			. <b></b>
			Max. Powe	er Use		
Reference Nam	ie			(kW)	Schedule Name	. <b></b>
Empty				0.0	NA	
Empty				0.0	NA	
Empty				0.0	NA	
Empty				0.0	NA 	<b></b>
MISCELLANEOUS						
 Reference			Conversion	Max.		
Name	Type	Units	kBTU/Units	Use	Schedule Name	
Empty	NG		100.0000		NA	
Empty	NG		100.0000		NA	
Empty	NG	THM			NA	
Empty	NG	THM	100.0000	0.0	NA 	. <b></b>
Fuel Types: N	G=Nat.G	as FO=	Fuel Oil PR=	Propar	ne RH=Rmt Htg	
ELECTRIC RATE						
Electric rat Average buil	e		: Virgini		er - Kwh Only	
FUEL RATES						
Natural gas.			: Washing		as Rate Schedule	2
Fuel oil Propane Remote source	ce heati	ng	: None			
Remote source	ce cooli	ng	: None			
MISCELLANEOUS						
Additional P	uildire		area			 0 sqft
Source elect	cric ger	neratino	g efficiency.		: 100.0	0 %

## BUILDING INPUT DATA

			PRESCOTT		*****	01-06-9 Page
************* BUILDING NAME						
PLANT SELECTI						
Plant Na					Quantity	
9. Cooling 10. Heating	Plant - Plant -	DDC	(W/	C CHIL	LER) 1	
MISCELLANEOUS			R USE			
Reference Nam			Max. Powe	r Use (kW)	Schedule Name	
					N7	
Empty				0.0	NA NA	
Empty Empty				0.0	NA	
Empty			•	0.0	NA	
MISCELLANEOUS						
	Fuel	Fuel	Conversion	Max.		
Name	Туре	Units	kBTU/Units	Use	Schedule Name	
	NG		100.0000		NA	
Empty	NG	THM	100.0000	0.0	NA	
Empty	NG	THM	100.0000	0.0	NA	
Zmm tra r	NG	THM	100.0000	0.0	NA	
Empcy		as F0=	Fuel Oil PR=	Propan	e RH=Rmt Htg	
Empty  Fuel Types: N	G=Nat.G					
	G=Nat.G 					
Fuel Types: N ELECTRIC RATE Electric rat	 : 		: Virgini	.a. Powe	r - Kwh Only	
Fuel Types: N	e	ower fac	: Virgini	.a. Powe	r - Kwh Only	
Fuel Types: N  ELECTRIC RATE  Electric rat  Average buil	e	ower fac	: Virgini	.a. Powe	r - Kwh Only	
Fuel Types: N ELECTRIC RATE Electric rat Average buil	e	ower fac	tor.: NA	. <b></b>		
Fuel Types: N ELECTRIC RATE Electric rat Average buil FUEL RATES Natural gas.	e	wer fac	tor.: NA	. <b></b>		
Fuel Types: N ELECTRIC RATE Electric rat Average buil FUEL RATES Natural gas. Fuel oil	e	ower fac	tor.: NA: Washing: None	. <b></b>		
FUEL RATES  Natural gas. Fuel oil	e	ower fac	tor:: NA: Washing: None: None	. <b></b>		
Fuel Types: N ELECTRIC RATE Electric rat Average buil FUEL RATES Natural gas. Fuel oil Propane Remote sourc	eding po	wer fac	tor: NA: Washing: None: None: None	yton Ga	s Rate Schedule	
FUEL RATES  Natural gas. Fuel oil Propane Remote sourc	eding po	wer fac	tor: NA: Washing: None: None: None	yton Ga		2
FUEL RATES  Natural gas. Fuel oil Propane Remote sourc	eding po	ower fac	tor:: NA: Washing: None: None: None	gton Ga	s Rate Schedule	2
Fuel Types: N ELECTRIC RATE Electric rat Average buil FUEL RATES Natural gas. Fuel oil Propane Remote source Remote source	eding po	wer fac	tor: NA: Washing: None: None: None	yton Ga	s Rate Schedule	

**BUILDING 1425** 

HAP v3.04 Page 1 of 1

#### TABLE 1. SIMULATION WEATHER DATA DESIGN PARAMETERS

	City:	Washington
	Location:	Dist. of Columbia
	Type of Data:	Typical Meteorological Year
	Latitude:	38.9 deg
	Longitude:	77.0 deg
	Elevation:	14.0 ft
*	Average Ground Reflectivity:	0.20
	Local Time Zone (GMT +/- N hours):	5.0 hours
*	Daylight Savings Time Considered?	И

<sup>\* =</sup> User-defined design parameters. All other values are fixed.

TABLE 2. DRY-BULB TEMPERATURE STATISTICS (F)

Month	Absolute Maximum	Average Maximum	Average	Average Minimum	Absolute Minimum	
January	60.4	39.3	30.7	21.0	-1.9	
February	62.1	42.8	33.1	22.9	7.5	
March	75.5	53.9	43.3	32.4	17.1	
April	85.5	65.7	55.0	44.3	31.2	
May	91.9	73.3	63.5	53.8	40.5	
June	93.5	80.8	70.0	58.8	48.8	
July	91.0	84.9	75.9	66.5	55.8	
August	96.8	85.1	74.3	64.5	49.6	
September	91.6	79.3	69.3	60.0	46.5	
October	84.7	67.5	56.8	46.7	23.4	
November	75.7	56.4	46.6	35.7	17.3	
December	59.0	42.7	36.9	30.9	20.5	

TABLE 3. DAILY TOTAL SOLAR RADIATION STATISTICS

		(BTU/sqft)		[ Daily Clearness Number] (Dimensionless)				
Month	Maximum	Average	Minimum	Maximum	Average	Minimum		
January	1043.4	609.1	137.7	0.648	0.430	0.107		
February	1448.6	815.5	79.9	0.685	0.433	0.048		
March	1861.2	1183.4	211.6	0.680	0.473	0.094		
April	2371.0	1484.8	247.6	0.717	0.479	0.079		
May	2579.4	1712.0	355.4	0.711	0.487	0.104		
June	2551.8	1890.8	515.8	0.697	0.514	0.140		
July	2398.3	1714.6	629.5	0.657	0.478	0.171		
August	2378.9	1696.2	708.2	0.694	0.522	0.227		
September	1943.6	1307.6	258.0	0.674	0.482	0.094		
October	1546.1	977.2	92.6	0.656	0.469	0.045		
November	1143.4	672.4	129.4	0.647	0.437	0.094		
December	803.2	488.0	73.1	0.618	0.382	0.057		

Notes: \* All solar data is daily total flux on a horizontal surface.

<sup>\*</sup> Clearness number is (Daily Total Solar)/(Extraterrestrial Solar) Values between 0.70 and 0.80 represent clear conditions.

#### CALENDAR DATA

Prepared By: EINHORN YAFFEE PRESCOTT	12 <b>-</b> 30-94
HAP v3.04	Page 1 of 1
*************	**************
Calendar Name: Sample Calendar	Day Type Assignments  Monday = Weekday
January first is on: Friday	Tuesday = Weekday
	Wednesday = Weekday
Day Type Names	Thursday = Weekday
Day Type 1 = Weekday	Friday = Weekday
Day Type 2 = Saturday	Saturday = Saturday
Day Type 3 = Sunday	Sunday = Sunday
• • •	Holiday = Sunday
Holidays	
(No holidays specified)	

. C-260

#### SCHEDULE DATA

1111 13.01										f 1		
**************************************										***		
Hour>	00	01	02	03	04	05	06	07	08	09	10	11
DESIGN DAY Weekday Saturday Sunday	0 0	0   0   0	0   0   0	0   0   0	0 0 0	0 0 0 0	0 0 0 0	50 50 0	75   75   0   0	100  100   0	100  100   0	100  100   0
Hour>	12	13	14	15	16	17	18	19	20	21	22	23
DESIGN DAY Weekday Saturday Sunday	100  100   0   0	100  100   0   0	100  100   0   0	100  100   0   0	100  100   0   0	50 50 0 0	25 25 0 0	0 0 0 0	0   0   0   0	0   0   0   0	0   0   0   0	0   0   0   0
Schedule Name	: Lig	hts		<b></b>			Hou	cly P	ercen	tages 		
Hour>	00	01	02	03	04	05	06	07	80	09	10	11
DESIGN DAY Weekday Saturday Sunday	25   25   25   25	25   25   25   25	25   25   25   25	25 25 25 25	25 25 25 25 25	25 25 25 25 25	25 25 25 25	50 50 25 25	100  100   25   25	100  100   25   25	100  100   25   25	100  100   25   25
Hour>	12	13	14	15	16	17	18	19	20	21	22	23
DESIGN DAY Weekday Saturday Sunday	100  100   25   25	100  100   25   25	100  100   25   25	100  100   25   25	100  100   25   25	75 75 25 25	50 50 25 25	25 25 25 25	25   25   25   25	25   25   25   25	25 25 25 25	25   25   25   25

## WALL CONSTRUCTION TYPES

Prepared by: EINHORN YAFFEE PRESCOTT 12-30-9 HAP v3.04 Page ************************************								
WALL TYPE 1: (CUSTOM WALL)								
Description: Brick Ca	avity Wall							
Layer Description	Thickness	Density	Spec.Ht	R-Val	Weight			
Inside surface resistance 4-in (102 mm) LW concrete block Airspace 4-in (102 mm) common brick Outside surface resistance	2.00 4.00	38.0 0.0 120.0	0.00 0.20	0.91	12.7 0.0			
Totals	10.00				52.7			
	nsity: lb/cu ecific Heat:	_		nt: lb/	sqft			

## ROOF CONSTRUCTION TYPES

Prepared by: EINHORN YAFFEE PRESCOTT       12-30-94         HAP v3.04       Page 1         ************************************								
ROOF TYPE 1: (CUSTOM ROOF)								
Description: Built-u Absorptivity: 0.900								
Layer Description	Thickness	Density	Spec.Ht	R-Val	Weight			
Inside surface resistance Acoustic Ceiling Tile R-19 (RSI-3.3) batt insulation 4-in (102 mm) LW concrete Built-up roofing 1/2-in (13 mm) vegetable board Outside surface resistance	0.75 6.00 5.00 0.38 1.00	18.0	0.14 0.20 0.20 0.35 0.31	1.90 19.23 4.17 0.33 2.60 0.33	1.1 0.3 16.7 2.2 1.5			
Totals	13.13			29.25	21.7			
Thickness: in De R-value : (hr-sqft-F)/BTU Sp	nsity: lb/cu	.ft	Weigh		sqft			

## WINDOW TYPE CONSTRUCTIONS

	N TINDON I	ILD COMBINGELLON	~				
Prepared by: EIN	ORN YAFFEE PRES	COTT		12-30-94			
HAP v3.04				Page 1			
****	*****	*****	******	*****			
WINDOW TYPE 1:	(PRE-DEFINED WIN	DOW)					
	<del>-</del>						
Glass Group	: DOUBLE	PANE, CLEAR					
Glass Type	: 1/8" c	lear + 1/8" cle	ar				
Window Description	on: Double	Hung Double Pane	Window				
Height	: 1.00	ft					
Width	: 1.00	ft					
Frame Type	Frame Type Aluminum with thermal breaks						
Interior Shade Type: No Shades Used							
Overall U-value.	0.632	BTU/hr/sqft/F					
Overall Shade Coe							
	Predef	ined Glass Data					
Glass	Glass	Glass	Glass	Shade			
Transmissivity	Peflectivity	Absorptivity	U-Value	Coefficient			
	0.134	0 154	0.490	0.890			
0.712	U.134	0.134	0.400	0.000			

# ELECTRIC RATE DATA

HAP v3.04	INHORN YAFFEE PRESCOTT	12-30-94 Page 1
BASIC ELECTRIC	RATE INFORMATION	
ELECTRIC RATE INFORMATION:	Rate schedule name: Ft. Belvoir Equivalent Currency symbol \$ Type of rate schedule Simple	\$/kWh
	Flat rate 0.01968	\$/kWh

## FUEL RATE DATA

HAP v3.04	NHORN YAFFEE PRESCOTT	12-30-94 Page 1
******	********	*******
BASIC FUEL RATE	INFORMATION	
FUEL RATE INFORMATION:	Rate schedule name: Ft. Currency symbol:	\$
	Units of measurement:  Fuel conversion factor:  Type of rate schedule:	1000.00000 kBTU/1000 lb
	Flat rate:	

## FUEL RATE DATA

HAP v3.04	NHORN YAFFEE PRESCOTT	12-30-94 Page 1
******	**************	*****
BASIC FUEL RATE	INFORMATION	
FUEL RATE INFORMATION:	Rate schedule name: Washington Gas F Currency symbol: \$ Units of measurement: Therm	Rate Schedule 2
	Fuel conversion factor: 100.00000  Type of rate schedule: Simple	kBTU/Therm
	Flat rate 0.60790	\$/Therm

Prepared by: EINHORN YAFFEE PRESCOTT 12-30-94								
Page I								
**********	****	****	***	******	*****	*****	*****	*****
GENERAL  Name: First F Floor Area: Building Weight.: Windows Shaded? Partitions Used.? LIGHTING Overhead Fixture: F Lamp Wattage:	Floor - So 1476.0 70.0 N N Recessed 2.30	outh	£t :	CHEDULES Lighting Task Lig People Equipmen Misc. Se Misc. La INFILTRAT Cooling.	yhts.:: it: ens: atent: TION	Lights Lights People People People	3 5 6 6 6	M/sqft
Ballast Mult:				Heating.			0.00 CF	
Task Lighting:	0.00	W/sqf	t	Typical.		(	0.00 CF	M/sqrt
PEOPLE		,		When Far	i On.?		N	
Occupancy:		sqft/	per :			1 1 0		
Activity Level: 0	Office Wo	rk		Type				420 0 Em
Sensible:		BTU/h		Perimete				430.0 ft
Latent:	205.0	BTU/h	r	Slab Flo				1476.0 sqft
OTHER LOADS				Floor R-				2.40
Equipment: Misc. Sensible: Misc. Latent:	0.0 0.0	W/sqf BTU/h BTU/h	r r	Insulati	ion R-v			0.00
	WALL		INDO		TW.	NDOW		Any
WALL Gross Area				 Shade			Shade	Doors?
Exp (sqft)	Туре							
S 960.0   E 180.0   W 180.0	1   1   1		291 45 45	-	1   1   1	0 0 0	- - -	N   N   N
=======================================	_======	=====	====	=======	=====		======	========
No roof or door data for this space.								
No partition data for								

Prepared by: EINHORN YAFFEE PRESCOTT 12-30-94					
HAP v3.04 Page	1				
	* *				
GENERAL SCHEDULES					
Name: First Floor - North Lighting: Lights					
Floor Area: 936.0 sqft Task Lights: Lights					
Building Weight: 70.0 lb/sqft People: People					
Windows Shaded? N Equipment: People					
Partitions Used.? N Misc. Sens.: People					
LIGHTING Misc. Latent: People					
Overhead Fixture: Recessed INFILTRATION					
Lamp Wattage: 2.30 W/sqft Cooling: 0.00 CFM/sqft					
Ballast Mult: 1.00 Heating: 0.00 CFM/sqft					
Task Lighting: 0.00 W/sqft Typical: 0.00 CFM/sqft					
PEOPLE When Fan On.? N					
Occupancy: 150.0 sqft/per FLOOR					
Activity Level: Office Work Type:Slab On Grade					
Sensible: 245.0 BTU/hr Perimeter 70.0 ft	<b>-</b> .				
Latent: 205.0 BTU/hr Slab Floor Area: 936.0 sq.	Еt				
OTHER LOADS Floor R-Value: 2.40					
Equipment: 2.00 W/sqft Insulation R-value: 0.00					
Misc. Sensible: 0.0 BTU/hr					
Misc. Latent: 0.0 BTU/hr					
TANDON AND AND AND AND AND AND AND AND AND AN	==				
WALL Gross Area   WALL   WINDOW   WINDOW   Any					
Exp (sqft)   Type   Type Qty Shade   Type Qty Shade   Doors?					
N 520.0   1   1 180 -   1 0 -   N					
W 180.0 1 1 45 - 1 0 - N					
	==				
No roof or door data for this space.					
	==				
No partition data for this space.					

Prepared by: EINHORN YAFFEE PRESCOTT	12-30-94
HAP v3.04	Page 1
*********	************
GENERAL	SCHEDULES
Name: First Floor - West	Lighting: Lights
Floor Area: 1368.0 sqft	Task Lights.: Lights
Building Weight.: 70.0 lb/sqft	People: People
Windows Shaded? N	Equipment: People
Partitions Used.? N	Misc. Sens: People
LIGHTING	Misc. Latent: People
Overhead Fixture: Recessed	INFILTRATION
Lamp Wattage: 2.30 W/sqft	
Ballast Mult: 1.00	Heating: 0.00 CFM/sqft
Task Lighting: 0.00 W/sqft	Typical: 0.00 CFM/sqft
PEOPLE	When Fan On.? N
Occupancy: 150.0 sqft/per	FLOOR
Activity Level: Office Work	Type:Slab On Grade
Sensible: 245.0 BTU/hr	
Latent 205.0 BTU/hr	
OTHER LOADS	Floor R-Value 2.40
Equipment: 2.00 W/sqft	Insulation R-value: 0.00
Misc. Sensible: 0.0 BTU/hr	
Misc. Latent: 0.0 BTU/hr	
=======================================	
WALL Gross Area   WALL   WINT	OOW WINDOW Any
Exp (sqft)   Type   Type Qt	ry Shade   Type Qty Shade   Doors?
	00 -   1 0 -   N
N 760.0   1   1 20	
120.0	1 1 0 1 1
No roof or door data for this space.	=======================================
No partition data for this space.	
no partition data for this space.	=======================================

Prepared by: EINHORN YAFFEE PRESCOTT 12-30-94 HAP v3.04 Page 1						
	****************************					
GENERAL  Name: First Floor - East Floor Area: 1836.0 sq Building Weight:: 70.0 lb Windows Shaded? N	SCHEDULES Lighting: Lights ft Task Lights.: Lights /sqft People: People Equipment: People					
Partitions Used.? N LIGHTING Overhead Fixture: Recessed	Misc. Sens: People Misc. Latent: People INFILTRATION					
Lamp Wattage: 2.30 W/S Ballast Mult: 1.00 Task Lighting: 0.00 W/S	Heating: 0.00 CFM/sqft					
PEOPLE Occupancy: 150.0 sq Activity Level: Office Work	When Fan On.? N ft/per FLOOR Type:Slab On Grade					
Latent: 205.0 BT	U/hr Slab Floor Area: 1836.0 sqft Floor R-Value: 2.40					
Equipment: 2.00 W/Misc. Sensible: 0.0 BTMisc. Latent: 0.0 BTMisc. Latent: 0.0 BTMISC. Latent: 0.0 BTMISC. Latent: 0.0 BTMISC. Latent: 0.0 BTMISC. Latent: 0.0 BTMISC. Latent: 0.0 BTMISC. Latent	U/hr U/hr					
WALL Gross Area   WALL	WINDOW   WINDOW   Any pe Qty Shade   Type Qty Shade   Doors?					
E 1020.0 1	1 45 -   1 0 -   N 1 270 -   1 0 -   N					
No roof or door data for this space.						
No partition data for this space.						

Prepared by: EINHORN YAFFEE	PRESCOTT				12-30-94
HAP v3.04					Page 1
******	******	******	*****	*****	*****
GENERAL		SCHEDULES	5		
Name: 1st Floor Corr.	& Lobby	Lighting	g: Lig	hts	
Floor Area: 1266.0			hts.: Lig		
	lb/sqft		: Pec		
Windows Shaded? N			nt: Pec	_	
Partitions Used.? N			ens: Pec	_	
LIGHTING		Misc. La	atent: Pec	ple	
Overhead Fixture: Recessed		INFILTRA	rion		
Lamp Wattage: 2.00	W/sqft	Cooling	:	0.0 C	FM
Ballast Mult: 1.00	_		:	0.0 C	FM
Task Lighting: 0.00	W/sqft	Typical.	:	0.0 C	FM
PEOPLE		When Far	n On.?	N	
Occupancy: 0	People	FLOOR			
Activity Level: Office Wo	rk		:Slak	On Grad	
Sensible 245.0			er		0.0 ft
Latent 205.0	BTU/hr		oor Area		1266.0 sqft
OTHER LOADS			-Value		2.40
Equipment: 0.00	W/sqft	Insulati	ion R-valu	e:	0.00
Misc. Sensible: 0.0	BTU/hr				
Misc. Latent: 0.0	BTU/hr				
=======================================			<b></b>	=======	===========
WALL Gross Area   WALL	WINDO		WIND		Any
Exp (sqft)   Type	Type Qty	y Shade	Type Qt	y Shade	Doors?
100.0	1 40	·	   1	0 -	N
N 120.0   1   S 140.0   1	1 40		<b>!</b>	0 -	N N
		) -	<del>-</del>   1	0 -	l N
W 50.0   1			_	.=======	** ==========
No roof or door data for this space.					
=======================================		=======			
No partition data for this s					
<u>F</u>	•				

Prepared	d by: EINHOR	N YAFFEE	PRESCO	TT					12-30-94
HAP v3.0	•								Page 1
		******	****	****	*****	*****	****	*****	*****
GENERAL				S	CHEDULES	3			
	: Second	d Floor -	South		Lighting	7 :	Light	s	
	Area:				Task Lig				
	ng Weight.:				People.				
	Shaded?	N			Equipmen				
	ons Used.?	N			Misc. Se				
LIGHTING		_			Misc. La		_		
	d Fixture:	Recessed			NFILTRA'		-		
	ittage:			t	Cooling	:		0.00 CF	M/sqft
-	Mult:		_		Heating			0.00 CF	M/sqft
	ghting:				Typical			0.00 CF	M/sqft
PEOPLE	-JJ		, -		When Far	n On.?		N	_
	ncy:	150.0	saft/	per F	LOOR				
Activit	y Level:	Office Wo	rk	-	Type	:A	bove	Conditi	loned Space
	e:	245.0	BTU/h						
OTHER LO									
Equipme	ent:	2.00	W/sqf	t					
Misc. S	Sensible:	0.0	BTU/h	r					
	Latent:		BTU/h						
======		=======	=====	=====	======	======		======	
WALL Gr	coss Area	WALL	W	INDOW		I	MODULI		Any
Exp	(sqft)	Туре	Type	Qty	Shade	Type	Qty	Shade	Doors?
						<del></del>			·
S	870.0	1	1	290	-	1	0	-	N
W	180.0	1	1	45	-	1	0	-	N
E	180.0	1	1	45	-	1	0	-	N
=======						-=====	====	======	=======================================
ROOF S	Lope Gros			SKY					
Exp (d	leg)	(sqft)	Туре	Туре	Qty				
	<del></del>					1			
HOR	-	1566.0	1	1	-	l			
				=====	======	======	====		==========
No parti	ition data 1	or this s	pace.						

Prepared by: EINHORN YAFFEE PRESCOTT	12-30-94
HAP v3.04	Page 1
********	******
GENERAL	SCHEDULES
Name: Second Floor - North	Lighting: Lights
Floor Area: 936.0 sqft	
Building Weight.: 70.0 lb/sqft	
Windows Shaded?	Equipment: People
Partitions Used.?	Misc. Sens: People
LIGHTING	Misc. Latent: People
Overhead Fixture: Recessed	INFILTRATION
	Cooling: 0.00 CFM/sqft
Ballast Mult: 1.00	Heating: 0.00 CFM/sqft
Task Lighting: 0.00 W/sqft	
PEOPLE	When Fan On.? N
Occupancy: 150.0 sqft/pe	er FLOOR
Activity Level: Office Work	Type:Above Conditioned Space
Sensible: 245.0 BTU/hr	
Latent 205.0 BTU/hr	
OTHER LOADS	
Equipment: 2.00 W/sqft	
Misc. Sensible: 0.0 BTU/hr	
Misc. Latent: 0.0 BTU/hr	
	.======================================
WALL Gross Area   WALL   WIN	
Exp (sqft) Type Type Q	ty Shade   Type Qty Shade   Doors?
1 - 1	.80 - 1 0 - N
n = 1 =	45 -   1 0 -   N
	======================================
	Type Qty
Exp (deg) (sqft)   Type   T	
HOR - 936.0   1	1 0
No partition data for this space.	

Prepared by: EINHORN YAFFEE	PRESCOTT	12-30-94			
HAP v3.04		Page 1			
*******	*******	********			
GENERAL	SCHEDULES	5			
Name: Second Floor -	West Lighting	g: Lights			
		hts.: Lights			
	0 lb/sqft People	: People			
	N Equipmer	Equipment: People			
Partitions Used.?	N Misc. Se	ens: People			
LIGHTING	Misc. La	atent: People			
Overhead Fixture: Recessed	INFILTRAT	TION			
Lamp Wattage: 2.3	0 W/sqft Cooling.	: 0.00 CFM/sqft			
Ballast Mult: 1.0	0 Heating.				
Task Lighting: 0.0	0 W/sqft Typical.	: 0.00 CFM/sqft			
PEOPLE	When Far	n On.? N			
Occupancy: 150.	0 sqft/per FLOOR				
Activity Level: Office W		:Above Conditioned Space			
	0 BTU/hr				
Latent 205.	0 BTU/hr				
OTHER LOADS					
Equipment: 2.0	0 W/sqft				
Misc. Sensible: 0.					
Misc. Latent: 0.	0 BTU/hr				
=======================================	· ·				
WALL Gross Area WALL	WINDOW	WINDOW Any			
Exp (sqft) Type	Type Qty Shade	Type Qty Shade   Doors?			
	1	1 0 N			
		1 0 -   N   1 0 -   N			
W 120.0   1	1 45 -	= ,			
	ROOF   SKYLIGHT	======================================			
ROOF Slope Gross Area	Type Type Qty				
Exp (deg) (sqft)	Type   Type Qcy				
HOR - 1368.0	1 1 1 0				
HOR - 1300.0		 ====================================			
No partition data for this					
no parereren data for emp					

Prepared by: EINHORN YAFF	EE PRESCOTT	12-30-94
HAP v3.04		Page 1
******	******	*******
GENERAL	SCHEDULES	
Name: Second Floor	- East Lighting.	: Lights
		nts.: Lights
Building Weight.: 7	<del>-</del>	: People
Windows Shaded?	N Equipment	c: People
Partitions Used.?	N Misc. Sen	ns: People
LIGHTING	Misc. Lat	tent: People
Overhead Fixture: Recess	ed INFILTRATI	ION
Lamp Wattage: 2	.30 W/sqft Cooling	: 0.00 CFM/sqft
	.00 Heating	: 0.00 CFM/sqft
Task Lighting: 0	.00 W/sqft Typical	: 0.00 CFM/sqft
PEOPLE	When Fan	On.? N
Occupancy: 15	0.0 sqft/per FLOOR	
Activity Level: Office	Work Type	:Above Conditioned Space
Sensible 24	5.0 BTU/hr	
Latent 20	5.0 BTU/hr	
OTHER LOADS		
Equipment: 2	.00 W/sqft	
	0.0 BTU/hr	
Misc. Latent:	0.0 BTU/hr	
=======================================	=======================================	=======================================
WALL Gross Area WALL	•	WINDOW Any
Exp (sqft) Type	Type Qty Shade	Type Qty Shade   Doors?
		1 0 N
	1 65 -	1 0 - N 1 0 - N
E 1020.0   1	_ =	± 0 1
		=======================================
ROOF Slope Gross Area		
Exp (deg) (sqft)	Type   Type Qcy	
HOR - 1950.0	1 1 1 0	
HOR - 1930.0		=======================================
No partition data for thi	s space.	
110 Parerers ages ror one	<u>-</u>	

Prepa	red by: EIN	HORN YAFFEE	PRESCO?	ГT					12-30-94
HAP v									Page 1
****	*****	*****	*****	****	****	*****	****	*****	*****
GENER	AL			S	CHEDULES	3			
Name	2nd	Floor Corr.	& Sta	irs	Lighting	g:	Light	S	
Floo	r Area	.: 1034.0	sqft		Task Lig	ghts.:	Light	s	
Buil	ding Weight	.: 70.0			People.	:	People	9	
	lows Shaded.				Equipmen	nt:	People	е	
Part	itions Used	? N		]	Misc. Se	ens: People			
LIGHT	'ING			1	Misc. La	atent:	People	е	
Over	head Fixtur	e: Recessed		I	NFILTRA	rion			
Lamp	Wattage	.: 2.00	W/sqft		Cooling				
Ball	ast Mult	.: 1.00			Heating				
Task	Lighting	.: 0.00	W/sqft	; '	Typical	:		0.00 CF	M/sqft
PEOPL	E				When Far	n On.?		N	
Occu	pancy	.: 0	People						
		.: Office Wo			Type	:A	bove (	Conditi	oned Space
		.: 245.0							
Late	nt	.: 205.0	BTU/h:	2					
	LOADS								
Equi	pment	.: 0.00	W/sqft	=					
Misc	. Sensible.	.: 0.0	BTU/hi	2					
	. Latent		BTU/h:						
							TNDOM	======	=======================================
		WALL	- W.	LNDOW	01 J -		INDOW		Any
Exp	(sqft)	Туре	туре	Qty	snade	13be	QLY	Silade	DOOLS:
 N	50.0	1 1	1	0	_	1 1	0	_	l N
S	80.0					1	0	_	N
W	50.0	1 1	1 1	0	_	1	0	-	N
		=======================================				' ======	=====	======	' =========
ROOF	Slope G	ross Area	ROOF	SKY	LIGHT				
		(sqft)	Туре	Туре	Qty				
HOR		1034.0	1	1	0	 			
				====	=		=====	======	========
No pa	rtition dat	a for this s	pace.						

\_\_\_\_\_\_

Name: Fan Coil Units - NO EMS	01-04-95
Type: TERMINAL UNITS - 2-Pipe Fan	Coils HAP v3.04
Prepared by: EINHORN YAFFEE PRESCO	TT Page 1
********	**********
1. SYSTEM NAME AND TYPE	
Name: Fan Coil Units Type: TERMINAL UNITS Number of Zones.: 8	
2. SYSTEM DESCRIPTION	
COOLING SYSTEM DATA	
Supply Air:	55.0 F
Fan Cycled for Cooling?	N
Coil Bypass Factor:	0.100
HEATING SYSTEM DATA	
Fan Cycled for Heating?	N
OUTDOOR VENTILATION DATA	N
Common Ventilation System Used? SAFETY FACTORS	14
Sensible Cooling Factor:	0 %
Latent Cooling Factor:	0 %
Heating Factor:	0 %
OUTDOOR VENTILATION DATA	
Type of Control:	Constant Airflow Rate
Design Ventilation Airflow:	
3. ZONE DATA	
ZONE	1 (All Zones the Same)
T-Stat Occupied Cooling(F):	75.0
Unoccupied Cooling(F):	85.0
Occupied Heating(F):	70.0
Unoccupied Heating(F):	55.0
Throttling Range(F):	3.0
Zone Terminal Type	
Fan Total Static(in.wg.):	0.25 54
Fan Efficiency(%):	J1 :====================================

Name: Fan Coil Units - NO EMS	01-04-95
Type: TERMINAL UNITS - 2-Pipe Fan Coils	HAP v3.04
Prepared by: EINHORN YAFFEE PRESCOTT	Page 2
****************	******
4. SCHEDULE DATA	
HOURLY TSTAT SCHEDULES   0   0   0   0   0   0   0   0   0	11111122222
0 1 2 3 4 5 6 7 8 9 0 1 2 3 4 5	5 6 7 8 9 0 1 2 3
Design Day   X   X   X   X   X   X   X   X	
Weekday $ X X X X X X X X X X X X X X X X X X X$	
Saturday   X   X   X   X   X   X   X   X	
Sunday $ X X X X X X X X X X X X X X X X X X X$	X X X X X X X X X
=======================================	=======================================
Cooling Available During Unoccupied Period ? Y	
MONTHLY SCHEDULES   JAN   FEB   MAR   APR   MAY   JUN   JUL   AUG	SER OCT NOVIDEC
MONTHLY SCHEDULES   JAN   FEB   MAR   APR   MAY   JUN   JUL   AUG	S DEF OCT NOV DEC
Managinal Hosting   YYY YYY YYY	
Terminal Heating   XXX	
Terminal Cooling             XXX XXX XXX XXX	

Name: Convectors - Baseline Type: TERMINAL UNITS - Convective Htg and Cl Prepared by: EINHORN YAFFEE PRESCOTT ***********************************	12-30-94 g HAP v3.04 Page 1
1. SYSTEM NAME AND TYPE	
Name: Convectors - Baseline Type: TERMINAL UNITS - Convect Number of Zones: 2	
2. SYSTEM DESCRIPTION	
15 COO21113 D/20011 020011 11111111	N
HEATING SYSTEM DATA  Is Heating System Used?	Y
Common vondended by	N
SAFETY FACTORS  Sensible Cooling Factor:  Latent Cooling Factor:  Heating Factor:	0 % 0 % 0 %
3. ZONE DATA	
ZONE 1 T-Stat Zone Setpoint(F): 70.0	(All Zones the Same)
4. SCHEDULE DATA	
HOURLY TSTAT SCHEDULES  0 0 0 0 0 0 0 0 0	1 1 1 1 1 1 1 1 1 2 2 2 2  0 1 2 3 4 5 6 7 8 9 0 1 2 3
Design Day	X   X   X   X   X   X   X   X   X   X
• • • • • • • • • • • • • • • • • • • •	JUN   JUL   AUG   SEP   OCT   NOV   DEC
Terminal Heating   XXX   XXX   XXX   XXX	

Name: Fan Coil Units - PLC	01-04-	95
Type: TERMINAL UNITS - 2-Pipe Fan	n Coils HAP v3.	04
Prepared by: EINHORN YAFFEE PRESCO		1
*********	********	**
1. SYSTEM NAME AND TYPE		
Name: Fan Coil Units Type: TERMINAL UNITS Number of Zones.: 8		:==
2. SYSTEM DESCRIPTION		
COOLING SYSTEM DATA		
Supply Air:	55.0 F	
Fan Cycled for Cooling?	N	
Coil Bypass Factor:	0.100	
HEATING SYSTEM DATA		
Fan Cycled for Heating?	N	
OUTDOOR VENTILATION DATA	17	
Common Ventilation System Used?	N	
SAFETY FACTORS Sensible Cooling Factor:	0 %	
Latent Cooling Factor:	0 %	
Heating Factor:	0 %	
OUTDOOR VENTILATION DATA		
Type of Control:	Constant Airflow Rate	
Design Ventilation Airflow:	0.15 CFM/sqft	
=======================================		==
2 CONTE DAMA		
3. ZONE DATA		
ZONE	1 (All Zones the Same)	
T-Stat Occupied Cooling(F):	75.0	
Unoccupied Cooling(F):	85.0	
Occupied Heating $(F)$ :	70.0	
Unoccupied Heating(F):	55.0	
Throttling Range(F):	3.0	
Zone Terminal Type	Fan Coil	
Fan Total Static(in.wg.):	0.25 54	
Fan Efficiency(%):	54 ====================================	==

Name: Fan Coil Units - PLC	01-04-95
Type: TERMINAL UNITS - 2-Pipe Fan Coils	HAP v3.04
Prepared by: EINHORN YAFFEE PRESCOTT	Page 2
****************	******
4. SCHEDULE DATA	
	1/2/2/2/2/
HOURLY TSTAT SCHEDULES  0 0 0 0 0 0 0 0 0 1 1 1 1 1 1 1 1 1   0 1 2 3 4 5 6 7 8 9 0 1 2 3 4 5 6 7 8	0 0 1 1 2 2 2
[0]1 2 3 4 5 6 7 8 9 0 1 2 3 4 5 6 7 8	9 0 1 2 3
Design Day	
Weekday	
Saturday	
Sunday	
	:=======
Cooling Available During Unoccupied Period ? N	
MONTHLY SCHEDULES   JAN   FEB   MAR   APR   MAY   JUN   JUL   AUG   SEP   OC	T   NOV   DEC
	! ! !
Terminal Heating   XXX   XXX   XXX   XXX   XXX   XXX	XX XXX XXX
Terminal Cooling	
	:========

Name: Convectors - PLC	12-30-94
Type: TERMINAL UNITS - Convective Htg and Clg	HAP v3.04
Prepared by: EINHORN YAFFEE PRESCOTT	Page 1
******************	*****
1. SYSTEM NAME AND TYPE	
Name Convectors - PLC	
Type TERMINAL UNITS - Convective Htg and Clg	
Number of Zones.: 2	
=======================================	
2. SYSTEM DESCRIPTION	
	<b></b>
COOLING SYSTEM DATA	
Is Cooling System Used?	
HEATING SYSTEM DATA	
Is Heating System Used? Y	
OUTDOOR VENTILATION DATA	
Common Ventilation System Used? N	
SAFETY FACTORS	
Sensible Cooling Factor: 0 %	
Latent Cooling Factor 0 %	
Heating Factor 0 %	
=======================================	=========
3. ZONE DATA	
ZONE 1 (All Zones the S	ame)
T-Stat Zone Setpoint(F): 70.0	
	=========
4. SCHEDULE DATA	
HOURLY TSTAT SCHEDULES   0   0   0   0   0   0   0   0   0	1   1   2   2   2   2
0 1 2 3 4 5 6 7 8 9 0 1 2 3 4 5 6 7	8 9 0 1 2 3
Design Day   X   X   X   X   X   X   X   X	X   X   X   X   X   X   X
Weekday   X   X   X   X   X   X   X   X	
Saturday   X   X   X   X   X   X   X   X	X   X   X   X   X   X   X
Sunday $ x x x x x x x x x x x x x x x x x x x$	x x x x x x
MONTHLY SCHEDULES   JAN   FEB   MAR   APR   MAY   JUN   JUL   AUG   SEP	OCT   MOV   DEC
	vvvlvvvlvvvl
Telminar neading	XXX   XXX   XXX
=======================================	

Name: Fan Coil Units - DDC 01-04-	
Type: TERMINAL UNITS - 2-Pipe Fan Coils HAP v3.	04
Prepared by: EINHORN YAFFEE PRESCOTT Page	1
************************	**
1. SYSTEM NAME AND TYPE	
Name: Fan Coil Units - DDC Type: TERMINAL UNITS - 2-Pipe Fan Coils Number of Zones.: 8	
=======================================	:==
2. SYSTEM DESCRIPTION	- <b>-</b>
COOLING SYSTEM DATA	
Supply Air 55.0 F	
Fan Cycled for Cooling? N	
Coil Bypass Factor 0.100	
HEATING SYSTEM DATA	
Fan Cycled for Heating? N OUTDOOR VENTILATION DATA	
Common Ventilation System Used? N	
SAFETY FACTORS	
Sensible Cooling Factor: 0 %	
Latent Cooling Factor: 0 %	
Heating Factor 0 %	
OUTDOOR VENTILATION DATA  Type of Control	
Design Ventilation Airflow: 0.15 CFM/sqft	
======================================	-==
3. ZONE DATA	
ZONE 1 (All Zones the Same)	
T-Stat Occupied Cooling(F): 75.0	
Unoccupied Cooling(F): 85.0	
Occupied Heating(F): 70.0	
Unoccupied Heating(F): 55.0	
Throttling Range(F): 3.0	
Zone Terminal Type Fan Coil	
Fan Total Static(in.wg.): 0.25	
Fan Efficiency(%): 54	==

Name: Fan Coil Units - DDC Type: TERMINAL UNITS - 2-E Prepared by: EINHORN YAFFEE	Pipe Fan Coils	01-04-95 HAP v3.04 Page 2
4. SCHEDULE DATA		1 1 1 1 1 2 2 2 2
Design Day		
Cooling Available During Ur	noccupied Period ? N	
MONTHLY SCHEDULES JA	AN FEB MAR APR MAY JUN JUL	AUG   SEP   OCT   NOV   DEC
Terminal Heating   XX Terminal Cooling		

Name: Convectors - DDC	12-30-94
Type: TERMINAL UNITS - Convective Htg and Clg	HAP v3.04
Prepared by: EINHORN YAFFEE PRESCOTT	Page 1
****************	*****
1. SYSTEM NAME AND TYPE	
Name: Convectors - DDC	
Type TERMINAL UNITS - Convective Htg and Clg	
Number of Zones.: 2	
=======================================	
2. SYSTEM DESCRIPTION	
COOLING SYSTEM DATA	
Is Cooling System Used?	
HEATING SYSTEM DATA	
Is Heating System Used? Y	
OUTDOOR VENTILATION DATA	
Common Ventilation System Used?	
SAFETY FACTORS	
Sensible Cooling Factor: 0 %	
Latent Cooling Factor 0 %	
Heating Factor 0 %	
=======================================	==========
3. ZONE DATA	
ZONE 1 (All Zones the	Came \
	Salle)
T-Stat Zone Setpoint(F): 70.0	.=========
4. SCHEDULE DATA	
HOURLY TSTAT SCHEDULES  0 0 0 0 0 0 0 0 0 1 1 1 1 1 1 1 1   0 1 2 3 4 5 6 7 8 9 0 1 2 3 4 5 6 7	
[0]1 2 3 4 5 6 7 6 9 0 1 2 3 4 5 6 7	
Design Day $ X X X X X X X X X X X X X X X X X X X$	x x x x x x
Weekday   X   X   X   X   X   X   X   X	x   x   x   x   x   x
Saturday   X   X   X   X   X   X   X   X	xxxxxxx
Sunday $ X X X X X X X X X X X X X X X X X X X$	xxxxxx
=======================================	
MONTHLY SCHEDULES   JAN   FEB   MAR   APR   MAY   JUN   JUL   AUG   SEF	OCT NOV DEC
	·
Terminal Heating   XXX   XXX   XXX   XXX	xxx   xxx   xxx
=======================================	=========

Name: Fan Coil Units - NO EM Type: TERMINAL UNITS - 4-Pi Prepared by: EINHORN YAFFEE **********************************	is .pe Fan Co PRESCOTT		12-30-94 HAP v3.04 Page 1
1. SPACE SELECTION			
		Space Name	
SPACES IN ZONE 1 (Zone 1)			
1. First Floor - South	1		
SPACES IN ZONE 2 (Zone 2)			
2. First Floor - North	1		
SPACES IN ZONE 3 (Zone 3)			
3. First Floor - West	1		
SPACES IN ZONE 4 (Zone 4)			
1. 11100 1100	1		
SPACES IN ZONE 5 (Zone 5)			
6. Second Floor - South			·
======================================			.===========
	1		<b></b>
=======================================	<del></del>	=======================================	=========
SPACES IN ZONE 7 (Zone 7)			
8. Second Floor - West		=======================================	:=========
SPACES IN ZONE 8 (Zone 8)			
9. Second Floor - East	1		
=======================================	=======	=======================================	=======================================

Name: Fan Coil Units - Base	eline		12-30-94
Type: TERMINAL UNITS - 4-1	Pipe Fan Coi	ils	HAP v3.04
Prepared by: EINHORN YAFFER	E PRESCOTT		Page 1
*******	******	********	******
1. SPACE SELECTION			
Space Name	Qty	Space Name	Qty
SPACES IN ZONE 1 (Zone 1)			
1. First Floor - South	1		
SPACES IN ZONE 2 (Zone 2)			
2. First Floor - North	1		
SPACES IN ZONE 3 (Zone 3)			
3. First Floor - West	1		
SPACES IN ZONE 4 (Zone 4)			
4. First Floor - East	1		
SPACES IN ZONE 5 (Zone 5)			
6. Second Floor - South	1		
SPACES IN ZONE 6 (Zone 6)			
7. Second Floor - North	1		
SPACES IN ZONE 7 (Zone 7)			
8. Second Floor - West	1		
SPACES IN ZONE 8 (Zone 8)		=======================================	<del>-</del>
9. Second Floor - East	1	·	
=======================================	-=======	=======================================	-=========

Name: Convectors - Baseline Type: TERMINAL UNITS - Conve Prepared by: EINHORN YAFFEE P.	RESCOTT		12-30-94 HAP v3.04 Page 1 ******
1. SPACE SELECTION			
Space Name	Qty	-	Qty
SPACES IN ZONE 1 (Zone 1)	=======		
5. 1st Floor Corr. & Lobby			
SPACES IN ZONE 2 (Zone 2)			
10. 2nd Floor Corr. & Stair	s 1 =========	============	=========

Name: Fan Coil Units - PLC			12-30-94
Type: TERMINAL UNITS - 4-Pi	pe Fan Coil:	s	HAP v3.04
Prepared by: EINHORN YAFFEE	PRESCOTT		Page 1
*******	******	******	******
1. SPACE SELECTION			
Space Name	Qty	Space Name	Qty
=======================================	========		:========
SPACES IN ZONE 1 (Zone 1)			
1. First Floor - South	1		•
	:=======		:=========
SPACES IN ZONE 2 (Zone 2)			
2. First Floor - North	1		
=======================================			:=========
SPACES IN ZONE 3 (Zone 3)	<b></b>		
3. First Floor - West			
=======================================			:=========
SPACES IN ZONE 4 (Zone 4)			
			·
T. PIESC PICOP ZGS	1		
=======================================	========		:=========
SPACES IN ZONE 5 (Zone 5)			
6. Second Floor - South	1		=======================================
SPACES IN ZONE 6 (Zone 6)	= <b></b>		
SPACES IN ZONE 0 (ZONE 0)			
7. Second Floor - North			
=======================================	========		
SPACES IN ZONE 7 (Zone 7)			
8. Second Floor - West			
	========		
SPACES IN ZONE 8 (Zone 8)			
9. Second Floor - East	1		
=======================================	========	=======================================	==========

Name: Convectors - PLC Type: TERMINAL UNITS - Converge Prepared by: EINHORN YAFFEE PROPERTY - AMARKAN	RESCOTT		12-30-94 HAP v3.04 Page 1
1. SPACE SELECTION			
Space Name	Qty	Space Name	Qty
	========		
SPACES IN ZONE 1 (Zone 1)			
5. 1st Floor Corr. & Lobby			
SPACES IN ZONE 2 (Zone 2)			
10. 2nd Floor Corr. & Stair			

Name: Fan Coil Units - DDC			12-30-94
Type: TERMINAL UNITS - 4-P	ipe Fan Coi	ls	' HAP v3.04
Prepared by: EINHORN YAFFEE	PRESCOTT		Page 1
******	******	******	*****
1. SPACE SELECTION			
		Space Name	Oty
=======================================			~ .
SPACES IN ZONE 1 (Zone 1)			
1. First Floor - South			
SPACES IN ZONE 2 (Zone 2)	==		
			<del>-</del>
2. First Floor - North	1		
=======================================	=========	=======================================	=======================================
SPACES IN ZONE 3 (Zone 3)			
3. First Floor - West			
=======================================			=========
SPACES IN ZONE 4 (Zone 4)			
4. First Floor - East			
SPACES IN ZONE 5 (Zone 5)	========		
6. Second Floor - South			
	========	=======================================	=======================================
SPACES IN ZONE 6 (Zone 6)			
7. Second Floor - North			
	=========	=======================================	=======================================
SPACES IN ZONE 7 (Zone 7)			
8. Second Floor - West			==========
SPACES IN ZONE 8 (Zone 8)			
9. Second Floor - East	1		
=======================================	========	=======================================	==========

Name: Convectors - DDC			12-30-94
Type: TERMINAL UNITS - Con-		d Clg	HAP v3.04
Prepared by: EINHORN YAFFEE	PRESCOTT		Page 1
******	******	******	******
1. SPACE SELECTION			
Chago Name	Qty	Space Name	Qty
Space Name	<del>-</del>	======================================	~~ <i>y</i>
SPACES IN ZONE 1 (Zone 1)	==== <b></b>		
5. 1st Floor Corr. & Lobl	_		
	=========		
SPACES IN ZONE 2 (Zone 2)			
10. 2nd Floor Corr. & Sta	ırs I		
		=======================================	========

Plant: Cooling Plant - Prepared By: EINHORN Y	AFFEE PRESCOTT				12-30-94 Page 1
***********	*****	*****	*****	******	*****
PLANT NAME, CLASSIFICA					
Plant name	: Cooli:: Cooli:: Air-C nodel: Compu: A/C R	ng poled Chi ter-Gener eciprocat	ller ated ing		
AIR SYSTEM SELECTIONS				<del></del> -	
Air System Name		Type	Qua	antity	
1. Fan Coil Units	- NO EMS	(4P-	FC)	1	
AIR-COOLED RECIPROCATION CONTROL CONTR	ooling load: design:	NA 40.0		<b></b>	<del>-</del>
Chiller configuration Is chilled water res	on set used?	Mult. Com N		/ Ckt.,	Unloaded
Is hot gas bypass us % load for minimum u Crankcase heater kW.	nloading:		ĸw		
PUMP AND PIPING SYSTEM	M DATA				
Pump or	Pum Delta-T Hea (F) (ft wg	p Effici d Mech ) (%)	encies Elec (%)	Pump Power (kW)	Piping Gain/Loss (%)
Chilled Water	6.0 75.0	 0 70.0	81.0	3.96	0.0

Plant: Heating Plant		RCCOURT				12-30-94 Page 1
Prepared By: EINHORN T	YAFFEE PRI	******	*****	*****	****	
PLANT NAME, CLASSIFICA			<b></b>			
Plant name				- NO EMS		
Classification Type				Heating		
AIR SYSTEM SELECTIONS						
	<b></b>					
Air System Name		P:		ting Coil Central		_
			- <b></b>		<del></del> -	
1. Fan Coil Units - 3. Convectors - Base						-
REMOTE SOURCE HEATING	DATA					
					<b></b>	
Estimated maximum he Gross heating capac:	eating loa itv	ad:	NA 1052.0	MBH		
PUMP AND PIPING SYSTEM	M DATA					
Pump or	Delta-T	Pump Head	Effici Mech	encies. Elec	Pump Power	Piping Gain/Loss
Piping System	(F)	(ft wg)	(%)	(%)	(kW)	(왕)
Hot Water	16.7	95.00	70.0	81.0	3.97	5.0

Flanc. Cooling Flanc 120	0-94 e 1 ****						
PLANT NAME, CLASSIFICATION & TYPE							
Plant name: Cooling Plant - PLC Classification: Cooling Type: Air-Cooled Chiller Type of simulation model: Computer-Generated Type of chiller A/C Reciprocating							
AIR SYSTEM SELECTIONS	<b></b>						
Air System Name Type Quantity							
4. Fan Coil Units - PLC (4P-FC) 1							
AIR-COOLED RECIPROCATING CHILLER DATA							
Estimated maximum cooling load: 37.0 Tons Chiller capacity at design: 40.0 Tons Chiller input power at design: 1.125 kW/Ton Chiller configuration: Mult. Compressors / Ckt., Unloaded Is chilled water reset used? N Is hot gas bypass used? N % load for minimum unloading: 20.0 % Crankcase heater kW							
PUMP AND PIPING SYSTEM DATA							
Pump Efficiencies Pump Pi Pump or Delta-T Head Mech Elec Power Gain/ Piping System (F) (ft wg) (%) (%) (kW)	ping Loss (%)						
	0.0						

		LANT INPU	T DATA			
Plant: Heating Plant -						12-30-94
Prepared By: EINHORN Y	AFFEE PRI ******	SSCOTT *******	*****	*****	****	Page 1
PLANT NAME, CLASSIFICA	TION & TY	PE				
Plant name		: Heating				
Classification						
Type						
					<b>-</b>	<b></b>
AIR SYSTEM SELECTIONS						
				ting Coil		
Air System Name		Pr		Central		
4. Fan Coil Units -						
4. Fan Coll Units - 5. Convectors - PLC.				1		_
	D 2 M 2					
REMOTE SOURCE HEATING	DATA 	. <b></b> .		. <b>.</b>		
Estimated maximum he	ating loa	ad:	282.1	MBH		
Gross heating capaci	ty	:	1052.0	MBH		
PUMP AND PIPING SYSTEM						
•						Piping Gain/Loss
						(%)
Hot Water				81.0	3.98	0.0

Plant: Cooling Plant	- DDC					12-30-94
Prepared By: EINHORN	YAFFEE PRESCO	TT				Page 1
*****	******	****	*****	****	******	*****
PLANT NAME, CLASSIFIC						
Plant name				DDC		
Classification Type	۲۸ ،	r-Coo	led Chil	ler		
Type of simulation	model Co	mpute	r-Genera	ted		
Type of chiller	A/	C Rec	iprocati	ng		
			- <b></b>	<b></b> -	<b></b>	
AIR SYSTEM SELECTIONS						
Air System Name			Туре	Q	uantity	
					1	
6. Fan Coil Units				· C )		
AIR-COOLED RECIPROCAT	ING CHILLER D	ATA				
AIR COOLID RECIPROSIT				. <b>-</b>		
Estimated maximum c	ooling load	.:	37.0 T	ons		
Chiller capacity at	design	.:	40.0 T	ons		
Chiller input power	at design	.:	1.125 k	W/Ton		
Chiller configurati				ressor	s / Ckt.,	Unloaded
Is chilled water re			N			
Is hot gas bypass u			N 20 0 °	_		
% load for minimum			20.0 %			
Crankcase heater kW			0.000 k			
PUMP AND PIPING SYSTE	א מידיא					
		. <b></b>				
		Pump	Efficie	encies	Pump	Piping
	Delta-T	Head	Mech	Elec	Power	Gain/Loss
Pump or Piping System		Head	Mech	Elec	Power	Gain/Loss
Pump or	Delta-T (F) (ft	Head wg)	Mech (%)	Elec (%)	Power (kW)	Gain/Loss

Plant: Heating Plant -	DDC					12-30-94
Prepared By: EINHORN Y	AFFEE PRE	SCOTT *****	*****	*****	*****	Page 1 *****
*****						
PLANT NAME, CLASSIFICA	TION & TY	PE				
Plant name	:	Heating	Plant	- DDC		
Classification						
Type	:	Remote	Source	Heating		
AIR SYSTEM SELECTIONS			<b></b>			
				ting Coil		
Air System Name		Pr	e-Heat <b></b>	Central	Termina.	L Zone
6. Fan Coil Units -				1	-	-
7. Convectors - DDC.			<u>-</u>	1	_	-
REMOTE SOURCE HEATING	DATA					
Estimated maximum he	ating loa	 .d :	282.1	MBH		
Gross heating capaci						
			·			
PUMP AND PIPING SYSTEM	I DATA					
		Pilmo	Effici		Pump	Piping
Pump or	Delta-T	Head	Mech	Elec	Power	Gain/Loss
Piping System	(F)	(ft wg)	(왕)	(%)	(kW)	(왕) 
						0.0
			. <b></b>		<del></del>	

# BUILDING INPUT DATA

Prepared by: HAP v3.04					*****	01-06-95 Page 1
**************************************			ilding 1425 -	NO EM		
PLANT SELECTI	ON				. <b></b>	
Plant Na					Quantity	
1. Cooling	Plant -	NO EMS	3(A/	C CHIL	LER) 1 ITG) 1	·
MISCELLANEOUS						
			Max. Powe	r Use	·	
Reference Nam				(kW)	Schedule Name	
Empty	·		·	0.0	NA	
Empty				0.0	NA	
Empty				0.0	NA NA	
Empty						
MISCELLANEOUS						
	Fuel	Fuel	Conversion			
Name	Туре	Units	kBTU/Units		Schedule Name	
Empty	ŊG	THM	100.0000	0.0	NA	
Empty	NG		100.0000			
Empty	NG		100.0000 100.0000			
Empty	NG					
Fuel Types: N	IG=Nat.0	as FO=	Fuel Oil PR=	Propar	ne RH=Rmt Htg	
	. <i></i> -					
ELECTRIC RATE		. <b></b> .			<b></b>	
Electric rat Average buil	ding po	wer fac	ctor.: NA		Equivalent \$/kWh	
FUEL RATES						
Natural gas.						
Fuel oil						
Propane	. <b></b>	. <b></b> .	: None			
Remote source	ce heati	ing	: Ft. Bel	lvoir I	District Steam	
Remote source	ce cooli	ing	: None			
MISCELLANEOUS	5 DATA					
יייייייייייייייייייייייייייייייייייייי						.0 saft
Source elect	tric ger	nerating	g efficiency.		: 1694 : 100.	00 %

6-300

# BUILDING INPUT DATA

Prepared by: HAP v3.04					*****	01-06-95 Page 1
			ilding 1425 -			
PLANT SELECT	ION					
Plant Na	 ame				Quantity	
				. <b></b>		
6. Heating	Plant - Plant -	PLC		EMOTE H	TG) 1	
MISCELLANEOUS	S ELECTR	IC POWE	R USE			
			Max. Powe	er Use		
Reference Nar				(kW)	Schedule Name	
 Empty				0.0	NA	
Empty				0.0	NA	
Empty				0.0	NA	
Empty 			<b></b>	0.0	NA 	
MISCELLANEOUS				. <b></b> -		
Reference	Fuel	Fuel	Conversion		Schedule Name	
Name 						<b></b>
Empty	NG	THM	100.0000		NA	
Empty	NG	THM	100.0000		NA	
Empty	NG NG	THM THM	100.0000 100.0000		NA NA	
Empty				. <b>-</b>		
Fuel Types: 1	NG=Nat.G	as FO=	Fuel Oil PR=	-Propan	ne RH=Rmt Htg	
ELECTRIC RAT	 E 					
Electric rat	lding po	wer fac	ctor.: NA	lvoir E	Equivalent \$/kWh	
FUEL RATES						
Natural gas			: None			
Fuel oil						
Propane			: None			
Remote sour	ce heati	.ng	: Ft. Be	lvoir I	District Steam	
Remote sour	 ce cool:	.ng	: None			
MISCELLANEOU	s data					
Additional Source elec	building	floor	areag efficiency.		: 1694.0	-
		·				. <b></b>

### BUILDING INPUT DATA

<b>a a b a b</b>		י אור מו אור איני	BOILDING INFO	JI DAIA	Δ		01-06-9
Prepared by: 1 HAP v3.04	TINHORN	YAFFEE	PRESCUII				Page
******	*****	*****	*****	*****	*****	*****	
BUILDING NAME		: Bu	ilding 1425 -	DDC			
PLANT SELECTION	NC						
				. <b></b> -		<b></b>	
Plant Nar					. Quant		
7 Cooling 1			(A/		.T.EP) 1		
8. Heating	Plant -	DDC	(RE	MOTE H	TG) 1		
MISCELLANEOUS	ELECTR	TG POWE	R USE	. <b></b> -	<b>-</b> -	<b></b>	
			Max. Powe	r Use			
Reference Name	<b>e</b>			(kW)	Schedule	Name	
Empty				0.0	NA NA		
Empty				0.0	NA NA		
Empty Empty				0.0	NA		
	- <i>-</i>			- <b></b>		<b></b> -	
MISCELLANEOUS	FUEL U	SE 			. <b></b>		
Reference	Fuel	Fuel	Conversion	Max.			
Name	Type	Units	kBTU/Units		Schedule	Name	
		THM	100.0000		NA		
Empty Empty		THM	100.0000	0.0	NA		
Empty		THM	100.0000	0.0	NA		
Empty	NG	THM	100.0000	0.0	NA		
			Tuel Oil DD	Dropar	DU_Dmt	 Wta	
Fuel Types: No	3=Nat.G 	as FO=	Fuel Oll PR		e kn=kiiic	лсу 	
ELECTRIC RATE							
	<b></b>		: Ft. Bel	voir F	Equivalent	 \$/kWh	
Average build	ding po	wer fac	tor.: NA				
		<b>-</b> -		<b></b> -	<del>-</del>		
FUEL RATES	<b>--</b>			<b></b> -	<b></b>		<b></b> _
Natural gas.			: None				
Fuel oil							
Propane			: None	laada T	detodet C	toom	
Remote source	e neati	.11g na	: Ft. Bel	rvoir I	TRUITE S	LEAIII	
			·				
MISCELLANEOUS	DATA						
							_
					<b></b> -		<b></b>
MISCELLANEOUS	DATA  uilding	floor	area g efficiency.		 :	1694.0	 sqft

**BUILDING 3136** 

		DILL					
Data: V	Washington,	Dist.	of	Columbia	(TN	IY)	

HAP v3.04 Page 1 of 1

12-30-94

#### TABLE 1. SIMULATION WEATHER DATA DESIGN PARAMETERS

_		
	City:	Washington
	Location:	Dist. of Columbia
	Type of Data:	Typical Meteorological Year
	Latitude:	_
	Longitude:	77.0 deg
	Elevation:	14.0 ft
*	Average Ground Reflectivity:	0.20

Local Time Zone (GMT +/- N hours).....: 5.0 hours
\* Daylight Savings Time Considered.....? N

------

\* = User-defined design parameters. All other values are fixed.

TABLE 2. DRY-BULB TEMPERATURE STATISTICS (F)

Month	Absolute Maximum	Average Maximum	Average	Average Minimum	Absolute Minimum	
January	60.4	39.3	30.7	21.0	-1.9	
February	62.1	42.8	33.1	22.9	7.5	
March	75.5	53.9	43.3	32.4	17.1	
April	85.5	65.7	55.0	44.3	31.2	
May	91.9	73.3	63.5	53.8	40.5	
June	93.5	80.8	70.0	58.8	48.8	
July	91.0	84.9	75.9	66.5	55.8	
August	96.8	85.1	74.3	64.5	49.6	
September	91.6	79.3	69.3	60.0	46.5	
October	84.7	67.5	56.8	46.7	23.4	
November	75.7	56.4	46.6	35.7	17.3	
December	59.0	42.7	36.9	30.9	20.5	_1

TABLE 3. DAILY TOTAL SOLAR RADIATION STATISTICS

[---- Daily Total Solar ---] [-- Daily Clearness Number --]

		(BTU/sqft)	•	(Di	mensionless	)
Month	Maximum	Average	Minimum	Maximum	Average	Minimum
	<b></b>					
January	1043.4	609.1	137.7	0.648	0.430	0.107
February	1448.6	815.5	79.9	0.685	0.433	0.048
March	1861.2	1183.4	211.6	0.680	0.473	0.094
April	2371.0	1484.8	247.6	0.717	0.479	0.079
May	2579.4	1712.0	355.4	0.711	0.487	0.104
June	2551.8	1890.8	515.8	0.697	0.514	0.140
July	2398.3	1714.6	629.5	0.657	0.478	0.171
August	2378.9	1696.2	708.2	0.694	0.522	0.227
September	1943.6	1307.6	258.0	0.674	0.482	0.094
October	1546.1	977.2	92.6	0.656	0.469	0.045
November	1143.4	672.4	129.4	0.647	0.437	0.094
December	803.2	488.0	73.1	0.618	0.382	0.057

Notes: \* All solar data is daily total flux on a horizontal surface.

<sup>\*</sup> Clearness number is (Daily Total Solar)/(Extraterrestrial Solar) Values between 0.70 and 0.80 represent clear conditions.

# CALENDAR DATA

Prepared By: EINHORN YAFFEE PRESCOTT	12-30-94
HAP v3.04	Page 1 of 1
********	*******
Calendar Name: Sample Calendar	Day Type Assignments
	Monday = Weekday
January first is on: Friday	Tuesday = Weekday
	Wednesday = Weekday
Day Type Names	Thursday = Weekday
Day Type 1 = Weekday	Friday = Weekday
Day Type 2 = Saturday	Saturday = Saturday
Day Type 3 = Sunday	Sunday = Sunday
	Holiday = Sunday
•	
Holidays	
(No holidays specified)	

### SCHEDULE DATA

Prepared By: EINHORN YAFFEE PRESCOTT 12-30-94 HAP v3.04 Page 1 of 1 ************************************						f 1						
Schedule Name: People Hourly Percentages												
Hour>	00	01	02	03	04	05	06	07	08	09	10	11
DESIGN DAY Weekday Saturday Sunday	0 0	0 0 0	0   0   0	0   0   0	0 0 0	0   0   0	0   0   0	50 50 0	75 75 0	100  100   0	100  100   0	100  100   0
Hour>	12	13	14	15	16	17	18	19	20	21	22	23
DESIGN DAY Weekday Saturday Sunday *********	100  100   0   0   0	100  100   0   0	100  100   0   0	100  100   0   0	100  100   0   0	50   50   0   0	25   25   0   0	0   0   0   0	0   0   0   0	0   0   0   0	0   0   0   0	0   0   0   0
Schedule Name	: Peo	ple 2	4 Hrs				Hou	rly P	ercen	tages 		
Hour>	00	01	02	03	04	05	06 	07 	08	09 	10	11
DESIGN DAY Weekday Saturday Sunday	100  100  100  100	100  100  100  100	100 100 100 100	100  100  100  100	100  100  100  100	100  100  100  100	100  100  100  100	100  100  100  100	100  100  100  100	100  100  100  100	100  100  100  100	100  100  100  100
Hour>	12	13	14	15	16	17	18	19	20	21	22	23
DESIGN DAY Weekday Saturday Sunday ************************************	100  100  100  100	100  100  100  100	100  100  100  100	100  100  100  100	100  100  100  100	100  100  100  100	100  100  100  100	100  100  100  100	100  100  100  100	100  100  100  100	100  100  100  100	100  100  100  100
Schedule Name			<b>_</b>					rly P			<b>_</b>	
Hour>	00	01	02	03	04	05	06 	07	08 	09	10 	11
DESIGN DAY Weekday Saturday Sunday	25   25   25   25	25   25   25   25	25   25   25   25	25 25 25 25 25	25   25   25   25	25 25 25 25 25	25 25 25 25	25 25 25 25	50   50   25   25	100  100   25   25	100  100   25   25	100  100   25   25
Hour>	12	13	14	15	16	17	18	19 	20	21	22	23
DESIGN DAY Weekday Saturday Sunday **********	100  100   25   25	100  100   25   25	100  100   25   25	100  100   25   25	100  100   25   25	100  100   25   25  ****	75 75 25 25 25	25 25 25 25 25	25 25 25 25 25	25 25 25 25 25	25 25 25 25 25	25 25 25 25 25

# WALL CONSTRUCTION TYPES

Prepared by: EINHORN YAFFEE PRES HAP v3.04 ************************************			*****	1	2-30-94 Page 1 *****
WALL TYPE 2: (CUSTOM WALL)			<b></b>		
Description: Block Ca	vity Wall				
Layer Description	Thickness	Density	Spec.Ht	R-Val	Weight
Inside surface resistance 4-in (102 mm) LW concrete block Airspace 4-in (102 mm) LW concrete block Outside surface resistance	2.00 4.00	38.0 0.0 38.0	0.00 0.20	0.91	0.0
Totals	10.00			4.96	25.3
	nsity: lb/cu ecific Heat:		Weigh	nt: lb/s	sqft

### ROOF CONSTRUCTION TYPES

Prepared by: EINHORN YAFFEE PRESCOTT 12-30- HAP v3.04 Page							
ROOF TYPE 1: (CUSTOM ROOF)			<b></b> -	<b></b> .			
Description: Built-up Absorptivity: 0.900	Roof		= =		<b>-</b>		
Layer Description	Thickness	Density	Spec.Ht	R-Val	Weight		
Inside surface resistance Built-up roofing 2-1/2" Poured Gypsum 1-in (13 mm) vegetable board R-11 (RSI-1.9) batt insulation 3/4-in (13 mm) acoustic tile Outside surface resistance	3.50 0.75 -	40.0 18.0 0.5	0.35 0.20 0.31 0.20 0.14	2.08 2.60 11.22 2.50 0.33	8.3 1.5 0.1 1.1		
Totals	8.13			19.76 	13.3		
	ity: lb/cu ific Heat:		_	nt: lb/s	sqft		

# WINDOW TYPE CONSTRUCTIONS

	MINDONI	III COMPINOCITOR	-	
Prepared by: EIN	HORN YAFFEE PRES	COTT		12-30-94
HAP v3.04				Page 1
*****	*****	*****	*****	*****
TITATOOTI MITTOO 1	/DDD DEETMED WIN	DOM)		
WINDOW TYPE 1:	(BKE-DELINED MIN	DOW) - <b></b>		
Glass Group				
Glass Type	: 1/8" c	lear		
Window Description				
Height	: 1.00	ft		
Width				
Frame Type			reaks	
Interior Shade T				
Overall U-value.	: 1.094	BTU/nr/sqit/F		
Overall Shade Co	eff: 0.903			
	Predef	ined Glass Data		
Glass	Glass	Glass	Glass	Shade
Transmissivity				
	Kerrectivity	ADSOLUTIVITY	o varue	1 000
0.841	0.078	0.081	1.110	1.000

# ELECTRIC RATE DATA

HAP v3.04	NHORN YAFFEE PRESCOTT	12-30-94 Page 1
BASIC ELECTRIC	RATE INFORMATION	
ELECTRIC RATE INFORMATION:	Rate schedule name: Ft. Belvoir Equivalent Currency symbol: \$ Type of rate schedule: Simple Flat rate: 0.01968	

# FUEL RATE DATA

Prepared by: EI HAP v3.04	NHORN YAFFEE PRESCOTT	12-30-94 Page 1
*****	*************	*****
BASIC FUEL RATE	INFORMATION	
FUEL RATE	Rate schedule name: Ft. Belvoir District	Steam
INFORMATION:	Currency symbol \$	
	Units of measurement 1000 lb	
	Fuel conversion factor: 1000.00000 kBTU	/1000 lb
	Type of rate schedule Simple	
	Flat rate 7.98000 \$/100	00 lb

# FUEL RATE DATA

Prepared by: EI	NHORN YAFFEE PRESCOTT	12-30-94
HAP v3.04	• •	Page 1
******	***********	*****
BASIC FUEL RATE	INFORMATION	
FUEL RATE	Rate schedule name: Washington Gas Ra	ate Schedule 2
INFORMATION:	Currency symbol \$	
	Units of measurement Therm	
	Fuel conversion factor: 100.00000 }	cBTU/Therm
	Type of rate schedule Simple	
	Flat rate 0.60790 \$	5/Therm

SPACE DE	SCRIPTION				
Prepared by: EINHORN YAFFEE PRESCOTT	12-30-94				
HAP v3.04	Page 1				
*********	***********				
GENERAL	SCHEDULES				
Name: First Floor - North	Lighting: People 24 Hrs.				
Floor Area: 2650.0 sqft	Task Lights.: People 24 Hrs.				
Building Weight.: 70.0 lb/sqft	People: People 24 Hrs.				
Windows Shaded? N	Equipment: People 24 Hrs.				
Partitions Used.? N	Misc. Sens: People 24 Hrs.				
LIGHTING	Misc. Latent: People 24 Hrs.				
Overhead Fixture: Recessed	INFILTRATION				
Lamp Wattage: 3.00 W/sqft	Cooling: 0.00 CFM/sqft				
Ballast Mult: 1.00	Heating: 0.00 CFM/sqft				
Task Lighting: 0.00 W/sqft	Typical: 0.00 CFM/sqft				
PEOPLE	When Fan On.? N				
Occupancy: 150.0 sqft/per	FLOOR				
Activity Level: Office Work	Type:Above Unconditioned Space				
Sensible: 245.0 BTU/hr	Floor Area 2650.0 sqft				
Latent 205.0 BTU/hr	U-value 0.420				
OTHER LOADS	Max Space Temp 95.0 F				
Equipment: 2.00 W/sqft	Ambient Temp @ Max: 95.0 F				
Misc. Sensible: 0.0 BTU/hr	Min Space Temp: 0.0 F				
Misc. Latent: 0.0 BTU/hr	Ambient Temp @ Minimum: 0.0 F				
=======================================					
WALL Gross Area   WALL   WIND	· · · · · · · · · · · · · · · · · · ·				
Exp (sqft) Type Type Qt	y Shade   Type Qty Shade   Doors?				
	0 - 1 0 - N				
SE 275.0 2 1	0 - 1 0 - N				
NE 980.0   2   1 62	3 -   1 0 -   N				
No roof or door data for this space.					
	=======================================				
No partition data for this space.					

Prepared by: EINHORN	Prepared by: EINHORN YAFFEE PRESCOTT 12-30-94							
HAP v3.04								Page 1
*******	****	****				*****	*****	*****
GENERAL				SCHEDULES				
Name: First H				Lighting				
12001 11201111111	2650.0			Task Lig		_		
Building Weight.:	70.0	lb/sq:	ft	People				
Windows Shaded?	N			Equipmen		_		
Partitions Used.?	N			Misc. Se		_		
LIGHTING				Misc. La		People		
Overhead Fixture: F	=			INFILTRAT				
Lamp Wattage:	3.00	W/sqf	t					M/sqft
Ballast Mult:	1.00			Heating.				M/sqft
Task Lighting:	0.00	W/sqf	t	Typical.	:	0	.00 CF	M/sqft
PEOPLE				When Far	n On.?		N	
Occupancy:	150.0	sqft/	per :					
Activity Level: (	Office Wo:	rk						tioned Space
Sensible:	245.0	BTU/h:	r	Floor A	rea		:	2650.0 sqft
Latent:	205.0	BTU/h:	r	U-value			:	0.420
OTHER LOADS				Max Space	ce Temp		:	95.0 F
Equipment:	2.00	W/sqf	t	Ambient	Temp @	Max	:	95.0 F
Misc. Sensible:	0.0	BTU/h:	r	Min Spac	ce Temp		:	0.0 F
Misc. Latent:	0.0	BTU/h:	r	Ambient	Temp @	Minim	um:	0.0 F
=======================================	=======	====	====	=======	======	=====	=====	
WALL Gross Area	WALL		INDO'		1	INDOW		Any
Exp (sqft)	Type	Туре	Qty	Shade	Туре	Qty	Shade	Doors?
000 0	2	1	623		   1	0		N
SW 980.0	2	1	023		1 1	0	_	N
NW 275.0	2	7	0	_	1 1	0	_	N
SE 275.0	- 1				! <del>-</del>			** :==========
		=====:	_===					
No roof or door data for this space.								
			=					
No partition data fo	or cure s	pace.						

Prepared by: EINHORN YA	AFFEE P	RESCOT	T					12-30-94
HAP v3.04								Page 1
*****	****	****	***	******	*****	****	****	*****
GENERAL			s	CHEDULES	3			
Name: Second Flo	or - N	orth		Lighting	j:	Light	S	
	2650.0			Task Lig		-		
	70.0			People.	:	People	<b>e</b>	
Windows Shaded?	N	_		Equipmer	nt:	People	3	
Partitions Used.?	N			Misc. Se	ens:	People	≘	
LIGHTING			:	Misc. La	atent:	People	2	
Overhead Fixture: Rece	essed		I	NFILTRAT	CION			
Lamp Wattage:	3.00	W/sqft	:	Cooling.	:		0.00 CF	
Ballast Mult:	1.00			Heating.	:		0.00 CF	
Task Lighting:	0.00	W/sqft	: '	Typical.	:		0.00 CF	M/sqft
PEOPLE				When Far	on.?		N	
Occupancy:	150.0	sqft/p	er F	LOOR				
Activity Level: Offi	.ce Wor	k	:	Туре	:A	bove (	Condition	oned Space
Sensible:	245.0	BTU/hr	:					
Latent:	205.0	BTU/hr	-					
OTHER LOADS								
Equipment:	2.00	W/sqft	:					
Misc. Sensible:	0.0							
Misc. Latent:	0.0	•	:					
=======================================			====	======	======	=====	=	=======================================
	ALL		NDOW			INDOW	G1 . 1 .	Any
Exp (sqft)   T	zpe	Туре	Qty	Shade	Туре	Qty	Shade	Doors?
								l N
NW 275.0	2	1	0 623	-	1   1	0	_	l N
NE 998.0	2	1			_			14
		ROOF		====== LIGHT	====== 	<del>-</del>		- <b></b>
ROOF Slope Gross Ar								
Exp (deg) (sqf	. C /	Type	TAbe	QCy				
HOR - 2650	) 0	1	1	0				
HOR - 2650	,		± ====:		 ======	=====		=========
No partition data for t			— <b>—</b>					
NO Partition data for t	TITO SP							

				RIPIION				
Prepared by: EINHOR	RN YAFFEE	PRESCO	${f T}{f T}$					12-30-94
HAP v3.04								Page 1
*****	*****	*****	****	*****	*****	****	*****	*****
GENERAL			-	CHEDULES				·
Name: Second				Lighting				
Floor Area:				Task Lig	_	_		
Building Weight.:	70.0	lb/sq	ft	People.				
Windows Shaded?	N			Equipment: People				
Partitions Used.?	N	Ī		Misc. Se		_		
LIGHTING				Misc. La		People	е	
Overhead Fixture:				NFILTRA				, _
Lamp Wattage:		W/sqf		Cooling				
Ballast Mult:				Heating.			0.00 CF	
Task Lighting:	0.00	W/sqf		Typical		,	0.00 CF	M/sqit
PEOPLE		<b>.</b>		When Far	n On.?		N	
Occupancy:		sqft/	per F	LOOR	7	1	a 2 2 - 2	
Activity Level: Office Work Type:Above Conditioned Space								
Sensible:	245.0							
Latent:	205.0	BTU/h	r					
OTHER LOADS	0.00	T.T / =	_					
Equipment:		w/sqr	C					
Misc. Sensible:		BTU/h BTU/h						
Misc. Latent:								
WALL Gross Area	WALL		INDOW		l w	INDOW		Any
Exp (sqft)				Shade	1		Shade	Doors?
EXP (SQLC)						~		
SW 980.0	2	1	623	-	1	0	-	N
NW 275.0	2	1	0	_	1	0	-	N
SE 275.0	2	1	0	-	1	0	=	N
	========	=====	====	======	======			=========
ROOF Slope Gros	ss Area	ROOF						
Exp (deg)	(sqft)	Туре	Туре	Qty	 			
HOR -	2650.0	1	1		! 			
=======================================			=====	======	=====	=====	=====	=========
No partition data								
=======================================	=======	==	_====					

	TEM INPUT DATA
Name: Fan Coil Units - Baseline	01-04-95
Type: TERMINAL UNITS - 2-Pipe Far	n Coils HAP v3.04
Prepared by: EINHORN YAFFEE PRESCO	OTT Page 1
*********	**********
1. SYSTEM NAME AND TYPE	
Name Fan Coil Units	
Type TERMINAL UNITS	
Number of Zones.: 4	2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2
	=======================================
a avamem regarineton	*
2. SYSTEM DESCRIPTION	
COOLING SYSTEM DATA	
Supply Air	55.0 F
Fan Cycled for Cooling?	N
Coil Bypass Factor:	0.100
HEATING SYSTEM DATA	<u>.</u>
Fan Cycled for Heating?	N
OUTDOOR VENTILATION DATA	
Common Ventilation System Used?	N
SAFETY FACTORS	
Sensible Cooling Factor:	0 %
Latent Cooling Factor:	0 %
Heating Factor:	0 %
OUTDOOR VENTILATION DATA	
Type of Control:	Constant Airflow Rate
Design Ventilation Airflow:	0.15 CFM/sqft
	=======================================
3. ZONE DATA	
ZONE	<pre>1 (All Zones the Same)</pre>
T-Stat Occupied Cooling(F):	75.0
Unoccupied Cooling(F):	85.0
Occupied Heating(F):	70.0
Unoccupied Heating(F):	55.0
Throttling Range(F):	3.0
Zone Terminal Type:	Fan Coil
Fan Total Static(in.wg.):	0.25
Fan Efficiency(%):	54
	=======================================

Name: Fan Coil Units - Baseline 01-04-95 Type: TERMINAL UNITS - 2-Pipe Fan Coils HAP v3.04 Prepared by: EINHORN YAFFEE PRESCOTT Page 2 ************************************		
4. SCHEDULE DATA		
HOURLY TSTAT SCHEDULES   0   0   0   0   0   0   0   0   0	2 2 2 2   0 1 2 3	
Design Day.        X X X X X X X X X X X X X X X X X X X	X   X   X   X     X   X   X   X	
Cooling Available During Unoccupied Period ? Y		
MONTHLY SCHEDULES   JAN   FEB   MAR   APR   MAY   JUN   JUL   AUG   SEP   OCT	NOV DEC	
Terminal Heating   XXX	xxx   xxx   	

Name: Fan Coil Units - PLC	12-30-94
Type: TERMINAL UNITS - 2-Pipe Far	n Coils HAP v3.04
Prepared by: EINHORN YAFFEE PRESCO	OTT Page 1
*********	***********
1. SYSTEM NAME AND TYPE	
Name: Fan Coil Units Type: TERMINAL UNITS Number of Zones.: 3	
2. SYSTEM DESCRIPTION	
COOLING SYSTEM DATA	
Supply Air:	55.0 F
Fan Cycled for Cooling?	N
Coil Bypass Factor:	0.100
HEATING SYSTEM DATA	
Fan Cycled for Heating?	N
OUTDOOR VENTILATION DATA	
Common Ventilation System Used?	N
SAFETY FACTORS	
Sensible Cooling Factor:	0 %
Latent Cooling Factor:	0 %
Heating Factor	0 %
OUTDOOR VENTILATION DATA  Type of Control	Constant Airflow Rate
Design Ventilation Airflow:	0.15 CFM/saft
	=======================================
3. ZONE DATA	
COME	1 (All Zones the Same)
ZONE T-Stat Occupied Cooling(F):	75.0
Unoccupied Cooling(F):	85.0
Occupied Heating(F):	70.0
Unoccupied Heating(F):	55.0
Throttling Range(F):	3.0
Zone Terminal Type:	Fan Coil
Fan Total Static(in.wg.):	0.25
Fan Efficiency(%):	54
	=======================================

Name: Fan Coil Units - PLC  Type: TERMINAL UNITS - 2-Pipe Fan Coils  Prepared by: EINHORN YAFFEE PRESCOTT  Page 2  ***********************************
Prepared by: EINHORN YAFFEE PRESCOTT Page 2  ***********************************
4. SCHEDULE DATA  ==================================
4. SCHEDULE DATA  HOURLY TSTAT SCHEDULES   0   0   0   0   0   0   0   0   1   1
HOURLY TSTAT SCHEDULES   0   0   0   0   0   0   0   0   0
Design Day
Design Day
Design Day
Weekday
Weekday
Saturday
Sunday
Cooling Available During Unoccupied Period ? N
MONTHLY SCHEDULES   JAN   FEB   MAR   APR   MAY   JUN   JUL   AUG   SEP   OCT   NOV   DEC
Terminal Heating   XXX
Terminal Cooling             XXX XXX XXX XXX

Name: Fan Coil Units (1 North) - PLC 12-3	0-94
Type: TERMINAL UNITS - 2-Pipe Fan Coils HAP v	3.04
Prepared by: EINHORN YAFFEE PRESCOTT Pag	e 1
******************	***
1. SYSTEM NAME AND TYPE	
Name: Fan Coil Units (1 North) - PLC Type: TERMINAL UNITS - 2-Pipe Fan Coils Number of Zones:: 1	
2. SYSTEM DESCRIPTION	
COOLING SYSTEM DATA	
Supply Air 55.0 F	
Fan Cycled for Cooling?	
Coil Bypass Factor 0.100	
HEATING SYSTEM DATA	
Fan Cycled for Heating N	
OUTDOOR VENTILATION DATA	
Common Ventilation System Used? N SAFETY FACTORS	
Sensible Cooling Factor: 0 %	
Latent Cooling Factor: 0 %	
Heating Factor	
Type of Control Constant Airflow Rate	
Design Ventilation Airflow: 0.15 CFM/sqft	
=======================================	====
3. ZONE DATA	
ZONE 1 (All Zones the Same)	
ZONE I (All zones the same) T-Stat Occupied Cooling(F): 75.0	
Unoccupied Cooling(F): 85.0	
Occupied Heating(F): 70.0	
Unoccupied Heating(F): 55.0	
Throttling Range(F): 3.0	
Zone Terminal Type Fan Coil	
Fan Total Static(in.wg.): 0.25	
Fan Efficiency(%): 54	

Name: Fan Coil Units (1 North) - PLC	12-30-94
Type: TERMINAL UNITS - 2-Pipe Fan Coils	HAP v3.04
Prepared by: EINHORN YAFFEE PRESCOTT	Page 2
***********	********
4. SCHEDULE DATA	
HOURLY TSTAT SCHEDULES   0 0 0 0 0 0 0 0 0 0 0 0	1 1 1 1 1 1 1 1 2 2 2 2
0 1 2 3 4 5 6 7 8 9	0 1 2 3 4 5 6 7 8 9 0 1 2 3
	X   X   X   X   X   X   X   X   X   X
	X X X X X X X X X X X X X X
	X X X X X X X X X X X X X X
Sunday $ X X X X X X X X X X X X X X X X X X X$	X X X X X X X X X X X X X X
Cooling Available During Unoccupied Period ?	N
=======================================	
MONTHLY SCHEDULES   JAN   FEB   MAR   APR   MAY	JUN   JUL   AUG   SEP   OCT   NOV   DEC
Terminal Heating   XXX   XXX   XXX   XXX	
Terminal Cooling         XXX	xxx   xxx   xxx   xxx

Name: Fan Coil Units - DDC	12-30-94
Type: TERMINAL UNITS - 2-Pipe Far	n Coils HAP v3.04
Prepared by: EINHORN YAFFEE PRESCO	
********	************
1. SYSTEM NAME AND TYPE	
I. SISTEM NAME AND TIFE	
Name Fan Coil Units	s - DDC
Type TERMINAL UNITS	s - DDC s - 2-Bine Fan Coils
	5 - 2-Fipe ran Coils
Number of Zones.: 3	=======================================
=======================================	=======================================
2. SYSTEM DESCRIPTION	
COOLING SYSTEM DATA	
Supply Air:	55.0 F
Fan Cycled for Cooling?	N
Coil Bypass Factor:	0.100
HEATING SYSTEM DATA	
Fan Cycled for Heating?	N
OUTDOOR VENTILATION DATA	
Common Ventilation System Used?	N
SAFETY FACTORS	
Sensible Cooling Factor:	0 %
Latent Cooling Factor:	0 %
Heating Factor:	0 %
OUTDOOR VENTILATION DATA	
Type of Control:	Constant Airflow Rate
Design Ventilation Airflow:	0.15 CFM/sqft
	=======================================
3. ZONE DATA	
ZONE	1 (All Zones the Same)
T-Stat Occupied Cooling(F):	75.0
Unoccupied Cooling(F):	85.0
Occupied Heating(F):	70.0
Unoccupied Heating(F):	55.0
Throttling Range(F):	3.0
	Fan Coil
Fan Total Static(in.wg.):	0.25
Fan Efficiency(%):	54

C-322

AIR DIDIES INFO	
Name: Fan Coil Units - DDC	12-30-94
Type. Indition of the street o	HAP v3.04
Prepared by: EINHORN YAFFEE PRESCOTT	Page 2
******************	*****
4. SCHEDULE DATA	
**************************************	
HOURLY TSTAT SCHEDULES  0 0 0 0 0 0 0 0 0 1 1 1 1 1 1 1 1 1   1	101112121
[0]1[2]3[4]5[6]/[6]9[0]1[2]3[4]5[6]/[6]9	10 1 2 3
Design Day	1 1 1 1 1
Saturday	
Sunday	
Cooling Available During Unoccupied Period ? N	
Cooling Available builing choccupies relies . A	=======
MONTHLY SCHEDULES   JAN   FEB   MAR   APR   MAY   JUN   JUL   AUG   SEP   OCT	NOVIDEC
MONTHEL SCHEDOLES   OTHER   THE CALL   THE CALL   OTHER   THE CALL   OTHER   O	
Terminal Heating   XXX   XXX   XXX   XXX	xxx xxx
Terminal Cooling XXX XXX XXX XXX XXX	
Terminar cooring	·

Name: Fan Coil Units (1 North) - D Type: TERMINAL UNITS - 2-Pipe Fan Prepared by: EINHORN YAFFEE PRESCO	Coils HAP v3.04
1. SYSTEM NAME AND TYPE	
Name: Fan Coil Units Type TERMINAL UNITS Number of Zones.: 1	
2. SYSTEM DESCRIPTION	
COOLING SYSTEM DATA	
Supply Air	55.0 F
Fan Cycled for Cooling?	N
Coil Bypass Factor:	0.100
HEATING SYSTEM DATA	
Fan Cycled for Heating?	N
OUTDOOR VENTILATION DATA	M
Common Ventilation System Used?	N
SAFETY FACTORS Sensible Cooling Factor:	0 %
Latent Cooling Factor:	0 %
Heating Factor:	0 %
OUTDOOR VENTILATION DATA	
Type of Control:	Constant Airflow Rate
Design Ventilation Airflow:	
=======================================	
3. ZONE DATA	
ZONE	1 (All Zones the Same)
ZONE T-Stat Occupied Cooling(F):	75.0
Unoccupied Cooling(F):	85.0
Occupied Heating(F):	70.0
Unoccupied Heating(F):	55.0
Throttling Range $(F)$ :	3.0
Zone Terminal Type:	Fan Coil
Fan Total Static(in.wg.):	0.25
Fan Efficiency(%):	54

Name: Fan Coil Units (1 North) - DDC  Type: TERMINAL UNITS - 2-Pipe Fan Coils	12-30-94 HAP v3.04
Prepared by: EINHORN YAFFEE PRESCOTT ***********************************	Page 2
4. SCHEDULE DATA	
HOURLY TSTAT SCHEDULES   0   0   0   0   0   0   0   0   0	1 1 1 2 2 2 2  7 8 9 0 1 2 3
Design Day.        X X X X X X X X X X X X X X X X X X X	x   x   x   x   x   x   x   x   x   x
Cooling Available During Unoccupied Period ? N	
MONTHLY SCHEDULES   JAN   FEB   MAR   APR   MAY   JUN   JUL   AUG   SE	P OCT NOV DEC
Terminal Heating   XXX	

Name: Fan Coil Units - Base Type: TERMINAL UNITS - 2-P Prepared by: EINHORN YAFFEE **********************************	ipe Fan Coi PRESCOTT		12-30-94 HAP v3.04 Page 1
1. SPACE SELECTION			
•	Qty	Space Name	Qty
SPACES IN ZONE 1 (Zone 1)	=======		
1. First Floor - North			
SPACES IN ZONE 2 (Zone 2)			
2. First Floor - South	1		
SPACES IN ZONE 3 (Zone 3)			
3. Second Floor - North	1		
SPACES IN ZONE 4 (Zone 4)			
4. Second Floor - South	1	:======================================	

C-326

Name: Fan Coil Units - PLC Type: TERMINAL UNITS - 2-Pi Prepared by: EINHORN YAFFEE **********************************	PRESCOTT		12-30-94 HAP v3.04 Page 1
1. SPACE SELECTION			
Space Name	Qty	Space Name	Qty
SPACES IN ZONE 1 (Zone 1)			
2. First Floor - South	1		
SPACES IN ZONE 2 (Zone 2)			
3. Second Floor - North	1		
SPACES IN ZONE 3 (Zone 3)			
4. Second Floor - South	1		
=======================================	:======	===============	

AII Name: Fan Coil Units (1 North Type: TERMINAL UNITS - 2-Pip Prepared by: EINHORN YAFFEE I	n) - PLC pe Fan Coi PRESCOTT		12-30-94 HAP v3.04 Page 1
1. SPACE SELECTION			
Space Name	Qty	Space Name	Qty
SPACES IN ZONE 1 (Zone 1)			
1. First Floor - North	1		

Name: Fan Coil Units - DDC			12-30-94
Type: TERMINAL UNITS - 2-Pi	ipe Fan Coi	ils	HAP v3.04
Prepared by: EINHORN YAFFEE	PRESCOTT		Page 1
********		******	*****
1. SPACE SELECTION			
Space Name	Qty	Space Name	Qty
=======================================	-=======		========
SPACES IN ZONE 1 (Zone 1)			
2. First Floor - South	1		
=======================================	:=======		=======================================
SPACES IN ZONE 2 (Zone 2)			
3. Second Floor - North			
======================================		===========	
SPACES IN ZONE 3 (Zone 3)			
	1		
4. Second F1001 - South	_		=======================================

Name: Fan Coil Units (1 Nort	ch) - DDC		12-30-94
Type: TERMINAL UNITS - 2-Pi	ipe Fan Coil	.s	HAP v3.04
Prepared by: EINHORN YAFFEE	PRESCOTT		Page 1
*******		*****	******
1. SPACE SELECTION			
	<del></del>		
Space Name	Qty	Space Name	Qty
Space Name		Space Name	
-		-	
=======================================		-	
=======================================		-	

C-336

Plant: Cooling Plant - Prepared By: EINHORN YA	FFEE PRES	COTT	******	******	*****	12-30-94 Page 1 ******
PLANT NAME, CLASSIFICAT		E				
Plant name	: ( : ( : 2 odel: (	Cooling Air-Coo Compute A/C Rec	led Chil r-Genera iprocati	ler ated Ing		
AIR SYSTEM SELECTIONS						
Air System Name			Type	Oua	antity	
1. Fan Coil Units	Baseline		. (2P-F	FC)	1	
Estimated maximum coor Chiller capacity at of Chiller input power a Chiller configuration Is chilled water research to the configuration of the configuration of the configuration is chilled water research to the configuration of the configu	pling load design at design. at used ed	: : : Mu ? ?	NA 40.0 7 1.130 } lt. Comp N N 20.0 9	Fons kW/Ton pressors	/ Ckt.,	
PUMP AND PIPING SYSTEM	DATA			<b></b>		
Piping System	(F) (	Head ft wg)	Mech (%)	Elec (%)	Power (kW)	Piping Gain/Loss (%)
Chilled Water	6.0	75.00	70.0	81.0	3.96	0.0

Plant: Heating Plant - Baseline Prepared By: EINHORN YAFFEE PRES		****	*****	****	12-30-94 Page 1 ******
PLANT NAME, CLASSIFICATION & TYPE	PE				
Plant name: Classification: Type	Heating Remote	Source 1		e	
AIR SYSTEM SELECTIONS					
	Pr	Hea e-Heat	ting Coil Central	Categor Termina	y l Zone
1. Fan Coil Units - Baseline.		-	1	-	-
REMOTE SOURCE HEATING DATA					
Estimated maximum heating load	:		MBH 		
PUMP AND PIPING SYSTEM DATA					
Pump or Delta-T Piping System (F)	Pump Head	Efficio Mech	encies Elec	Pump Power	Piping Gain/Loss
Hot Water 7.0					0.0

Plant: Cooling Plant	- PLC					12-30-94
Prepared By: EINHORN	YAFFEE PRES	SCOTT				Page 1
**************	****	*****	*****	*****	******	*****
PLANT NAME, CLASSIFI	CATION & TY	PE				
Plant name		Cooling	Plant -	PLC		
Classification	<i></i>	Air-Coo	led Chill	er		
Type of simulation	model :	Compute	r-Generat	ed		
Type of chiller		A/C Rec	iprocatin	q		
					<b></b> -	<b></b>
AIR SYSTEM SELECTION	S					
			 Туре			
Air System Name					<i>-</i>	
2. Fan Coil Unit	s - PLC		. (2P-FC	)	1	
3. Fan Coil Unit	s (1 North)	- PLC	. (2P-FC	)	1	
Estimated maximum Chiller capacity a Chiller input powe Chiller configurat Is chilled water r Is hot gas bypass % load for minimum Crankcase heater k	cooling load to design  r at design ion  eset used  unloading.  W	d:: Mu??	lt. Compr N N 20.0 % 0.000 kW	/Ton essors	/ Ckt.,	Unloaded
PUMP AND PIPING SYST	EM DATA					
				cies		Piping
Duma ox	Delta-T	Head	Mech	Elec	Power	Gain/Los
Pump or Piping System	Delta-1 (F)	(ft. wa)	(%)	(왕)	(kW)	(%)
					<b></b>	
Chilled Water	6.0		70.0			

Plant: Heating Plant - Prepared By: EINHORN Y.		SCOTT				12-30-94 Page 1
*************	*****	*****	*****	*****	*****	
PLANT NAME, CLASSIFICA		PE				
Plant name	: : 	Heating Remote	r Source			
AIR SYSTEM SELECTIONS						
Air System Name		Pr	Hea e-Heat	ting Coil Central	Categor Termina	y 1 Zone
2. Fan Coil Units - 3. Fan Coil Units (1	PLC		-	1	-	- - -
REMOTE SOURCE HEATING	DATA					
Estimated maximum he Gross heating capaci			600.0	МВН 	<b></b>	
PUMP AND PIPING SYSTEM	DATA					
	Delta-T	Pump Head	Effici Mech	encies Elec	Pump Power	Piping Gain/Loss (%)
Hot Water	7.0	70.00	70.0	81.0	3.96	0.0

Plant: Cooling Plant	- DDC				12-30-94
Prepared By: EINHORN	YAFFEE PRESCOT	1			Page 1
*******	******	******	******	******	*****
	TON C MIND				
PLANT NAME, CLASSIFIC			<b></b>		
Plant name		ing Plant	- DDC		
Classification	Cool	ing			
Type					
Type of simulation					
Type of chiller					
<u></u>					
AIR SYSTEM SELECTIONS					
Air System Name			e Qu	antity	
AII System Name					
4. Fan Coil Units				1	
5. Fan Coil Units					
AIR-COOLED RECIPROCAT	TING CHILLER DAT	'A			
				<b></b>	
Estimated maximum o			Tong		
Chiller capacity at Chiller input power			kW/Ton		
Chiller configurati	on			/ Ckt.,	Unloaded
Is chilled water re	set used?	N			
Is hot gas bypass u					
% load for minimum					
Crankcase heater kW		0.000			. <b></b> .
PUMP AND PIPING SYSTE	M DATA				
		needad			Dining
Dump or	Delta-T He	mp Effici			
Pump or Piping System	(F) (ft v				
		<b></b>	· <b></b>		. <b></b>
Chilled Water	6.0 75	00 70.0	81.0		

Flanc. Heacing Flance	30-94 ge 1 ****
PLANT NAME, CLASSIFICATION & TYPE	
Plant name: Heating Plant - DDC Classification: Heating Type: Remote Source Heating	
AIR SYSTEM SELECTIONS	
Heating Coil Category	
Air System Name Pre-Heat Central Terminal Zo	ne 
4. Fan Coil Units - DDC 1 - 5. Fan Coil Units (1 North) - DDC 1 -	- - 
REMOTE SOURCE HEATING DATA	
Estimated maximum heating load: NA	
Gross heating capacity 600.0 MBH	
PUMP AND PIPING SYSTEM DATA	
Pump Efficiencies Pump P	iping
Pump or Delta-T Head Mech Elec Power Gain Piping System (F) (ft wg) (%) (%) (kW)	
Hot Water 7.0 70.00 70.0 81.0 3.96	

#### BUILDING INPUT DATA

****	*****	*****	*****	*****	*****	Page :
BUILDING NAME		: Bu	ilding 3136 -	Basel	ine	
PLANT SELECTIO						
Plant Nar	ne			Туре	Quantity	
1. Cooling I	Plant -	Baseli	ne (A/ne (RE	EMOTE H	(TG) 1	
MISCELLANEOUS	ELECTR	IC POWE	R USE			
Reference Name			Max. Powe		Schedule Nam	е
 Empty				0.0	NA	<b></b>
Empty			•	0.0	NA	
Empty Empty				0.0 0.0	NA NA	
	<del>-</del>	<b></b> -				
MISCELLANEOUS	FUEL U	SE 		<b></b>		
Name	Туре	Units	Conversion kBTU/Units	Use	Schedule Nam	e
Empty		THM	100.0000	0.0	NA	
Empty		THM	100.0000 100.0000	0.0		
Empty Empty	NG NG	THM THM	100.0000	0.0		
Fuel Types: N	 G=Nat.G	as FO=	Fuel Oil PR=	Propan	le RH=Rmt Htg	
ELECTRIC RATE	- <b></b>			. <b>-</b>		
Electric rate Average build				voir E	Gquivalent \$/k	Wh
				. <b>- -</b>		
FUEL RATES						
Natural gas. Fuel oil			: None			
Remote source	e heati e cooli	ng ng	: Ft. Bel		oistrict Steam	
MISCELLANEOUS						
			area			

#### BUILDING INPUT DATA

Prepared by: HAP v3.04	*****	*****	*****	****	******	*****	01-06-95 Page 1 ******
BUILDING NAME.					<b></b>		
PLANT SELECTIO	)N <b></b>					<b></b>	
Plant Nam				Туре	. Quant	ity	
3. Cooling F	lant -	PLC	(A/				
MISCELLANEOUS							
			Max. Powe	r Use			
Reference Name				(kW)	Schedule	Name	
Empty	<b></b> _			0.0	NA		
Empty Empty				0.0	NA NA		
Empty				0.0	NA		
	. <b>-</b> <del>-</del> -						
MISCELLANEOUS		SE 					
Reference	Fuel	Fuel	Conversion	Max.	~ 1 1 1 ·	37	
Name	Type	Units	kBTU/Units	Use 	Schedule	Name	
Empty		THM	100.0000	0.0	NA		
Empty	NG		100.0000 100.0000		NA NA		
Empty Empty	NG NG	THM			NA NA		
Fuel Types: NO	 =Nat.G	 as FO=	Fuel Oil PR=	 :Propan	 ie RH=Rmt	<b></b> Htq	
ELECTRIC RATE					~		
Electric rate	ling po	wer fac	: Ft. Bel	voir E	Equivalent	\$/kWh	
FUEL RATES				<b></b>			
Natural gas Fuel oil Propane	heati	 .ng	: None: None: None: Ft. Bel: None				·
MISCELLANEOUS	DATA						
Additional bu	ilding		area		:	1160.0 100.00	_

#### BUILDING INPUT DATA

Prepared by: E HAP v3.04 ************************************	*****	*****	*****		*****	*****	01-06-95 Page 1
	<del>-</del> -						
PLANT SELECTIO							
Plant Nam				Туре	. Quanti	ity	
5. Cooling F	lant -	DDC	(A/	C CHIL	LER) 1	• <del></del> -	
MISCELLANEOUS	ELECTR	IC POWE	R USE				
			Max. Powe	r Use			
Reference Name				(kW)	Schedule	Name	
Empty		- <b></b>		0.0	NA		
Empty				0.0	NA		
Empty				0.0	NA NA		
Empty	. <b></b> -						
MISCELLANEOUS						. <b>.</b> <del>.</del> .	
Name	Туре	Units	Conversion kBTU/Units	Use		Name	
Empty		THM	100.0000	0.0	NA		
Empty		THM	100.0000		NA		
Empty	NG NC	THM THM			NA NA		
Empty	. <b>-</b>						
Fuel Types: NO	=Nat.G	as FO=	Fuel Oil PR=	Propan	ie RH=Rmt	Htg 	
ELECTRIC RATE							
Electric rate	ling po	wer fac			Equivalent		
FUEL RATES							
Natural gas Fuel oil Propane Remote source	heati	 .ng	: None: None: None: Ft. Bel	voir D	District St	team	
MISCELLANEOUS	DATA						
		floor	area		:	1160.0 100.00	<del>-</del>

C-339

# APPENDIX D CARRIER E20-II BUILDING SIMULATION RESULTS

**BUILDING 200** 

#### ANNUAL ENERGY COSTS

#### TABLE 1. COSTS BY ENERGY CATEGORY

Component	Annual Energy			Costs> (\$/sqft)*	
Electric Natural Gas Fuel Oil Propane Remote Heating Remote Cooling	0 0	kWh Therm 1000 lb	5739 17313 0 0 0	0.219 0.659 0.000 0.000 0.000 0.000	55.2 % 0.0 % 0.0 %
>>> HVAC Subtotal			23052	0.878	73.5 %
Electric Natural Gas Fuel Oil Propane Remote Heating	0	kWh Therm	8300 0 0 0	0.316 0.000 0.000 0.000 0.000	0.0 %
>>> Non-HVAC Subtotal			8300	0.316	26.5 %
>>> GRAND TOTAL	======		31351	1.194	100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

#### ENERGY BUDGET BY ENERGY SOURCE

\*\*\*\*\*\*\*\*\*\*\*\*

Building: Building 200 - Baseline
Weather: Washington (Washington TMY)
Prepared by: EINHORN YAFFEE PRESCOTT

08-15-95 HAP v3.04

Page 1 of 1

TABLE 1. ANNUAL COIL LOADS

ŧ

Component	(kBTU)	(kBTU/sqft) *	_
Cooling Loads	1791881	68.247	
Heating Loads	2583650	98.402	

TABLE 2. ENERGY CONSUMPTION BY ENERGY COMPONENT

Component		Energy *> (kBTU/sqft)*		
Electric	994935	37.894	994935	37.894
Natural Gas	2847986	108.470	2847986	108.470
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
Remote Cooling	0	0.000	0	0.000
>>> HVAC Total	3842922	146.364	3842922	146.364
Electric	1438987	54.806	1438987	54.806
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
>>> Non-HVAC Tota	al 1438987	54.806	1438987	54.806
>>> GRAND TOTAL	5281909	201.170	5281909	201.170
	=========		===================================	

<sup>\*</sup> Site Energy is the actual energy consumed.

<sup>\*</sup> Source Energy is the site energy divided by the electric generating efficiency of 100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

#### ANNUAL ENERGY COSTS

Building: Building 200 - PLC

08-15-95

Weather: Washington (Washington TMY)

HAP v3.04

Prepared by: EINHORN YAFFEE PRESCOTT \*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

Page 1 of 1

TABLE 1. COSTS BY ENERGY CATEGORY

Component	Annual Energy		Annual (\$)	Costs> (\$/sqft)*	% of Total
Electric Natural Gas Fuel Oil Propane Remote Heating Remote Cooling	0 0	kWh Therm 1000 lb	4596 12836 0 0 0	0.175 0.489 0.000 0.000 0.000 0.000	17.9 % 49.9 % 0.0 % 0.0 % 0.0 %
>>> HVAC Subtotal			17432	0.664	67.7 %
Electric Natural Gas Fuel Oil Propane Remote Heating	0 0	kWh Therm 1000 lb	8300 0 0 0	0.316 0.000 0.000 0.000 0.000	32.3 % 0.0 % 0.0 % 0.0 % 0.0 %
>>> Non-HVAC Subtotal	======	==========	8300 ===================================	0.980	=======

\* Cost per unit floor area is based on the gross building floor area.

#### ENERGY BUDGET BY ENERGY SOURCE

Building: Building 200 - PLC

08-15-95

Weather: Washington (Washington TMY)

HAP v3.04

Prepared by: EINHORN YAFFEE PRESCOTT

Page 1 of 1

\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

#### TABLE 1. ANNUAL COIL LOADS

Component	(kBTU)	(kBTU/sqft) *	
Cooling Loads	1686259	64.224	
Heating Loads	1662769	63.329	

#### TABLE 2. ENERGY CONSUMPTION BY ENERGY COMPONENT

Component		Energy *> (kBTU/sqft)*		
Electric	796826	30.348	796826	30.348
Natural Gas	2111492	80.419	2111492	80.419
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
Remote Cooling	0	0.000	0	0.000
>>> HVAC Total	2908318	110.768	2908318	110.768
Electric	1438987	54.806	1438987	54.806
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
>>> Non-HVAC Tota	al 1438987	54.806	1438987	54.806
>>> GRAND TOTAL	4347305	165.574	4347305	165.574
=======================================	========	===		

<sup>\*</sup> Site Energy is the actual energy consumed.

<sup>\*</sup> Source Energy is the site energy divided by the electric generating efficiency of 100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

#### ANNUAL ENERGY COSTS

Building: Building 200 - DDC 08-15-95

#### TABLE 1. COSTS BY ENERGY CATEGORY

Component	Annual Energy			Costs> (\$/sqft)*	
Electric Natural Gas Fuel Oil Propane Remote Heating Remote Cooling	0 0	kWh Therm 1000 lb	4067 11192 0 0 0 0	0.155 0.426 0.000 0.000 0.000 0.000	47.5 % 0.0 % 0.0 %
>>> HVAC Subtotal			15259	0.581	64.8 %
Electric Natural Gas Fuel Oil Propane Remote Heating	0 0 0	kWh Therm	8300 0 0 0	0.000 0.000	35.2 % 0.0 % 0.0 % 0.0 % 0.0 %
>>> Non-HVAC Subtotal			8300	0.316	35.2 %
>>> GRAND TOTAL			23559	0.897	100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

#### ENERGY BUDGET BY ENERGY SOURCE

\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

Building: Building 200 - DDC

08-15-95

Weather: Washington (Washington TMY)

HAP v3.04

Prepared by: EINHORN YAFFEE PRESCOTT

Page 1 of 1

TABLE 1. ANNUAL COIL LOADS

Component	(kBTU)	(kBTU/sqft)*
Cooling Loads Heating Loads	1349307 1422854	51.390 54.192

TABLE 2. ENERGY CONSUMPTION BY ENERGY COMPONENT

Component		Energy *> (kBTU/sqft)*	< Source (kBTU)	
Electric	705037	26.852	705037	26.852
Natural Gas	1841126	70.122	1841126	70.122
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
Remote Cooling	0	0.000	0	0.000
>>> HVAC Total	2546163	96.975	2546163	96.975
Electric	1438987	54.806	1438987	54.806
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
>>> Non-HVAC Total	al 1438987	54.806	1438987	54.806
>>> GRAND TOTAL	3985150	151.781	3985150	151.781

<sup>\*</sup> Site Energy is the actual energy consumed.

<sup>\*</sup> Source Energy is the site energy divided by the electric generating efficiency of 100.0 %

 $<sup>\</sup>star$  Cost per unit floor area is based on the gross building floor area.

**BUILDING 219** 

#### ANNUAL ENERGY COSTS

#### TABLE 1. COSTS BY ENERGY CATEGORY

Component	Annual Energy			Costs> (\$/sqft)*	
Electric Natural Gas Fuel Oil	0	kWh Therm	0	0.440 0.000	45.5 % 0.0 %
Propane Remote Heating Remote Cooling	0 0 0		0 0 0	0.000 0.000 0.000	
>>> HVAC Subtotal		. <b></b>	22135	0.672	69.4 %
Electric Natural Gas Fuel Oil Propane Remote Heating	496200 0 0 0 0	kWh Therm	9765 0 0 0 0	0.296 0.000 0.000 0.000 0.000	0.0 % 0.0 %
>>> Non-HVAC Subtotal	L		9765	0.296	30.6 %
>>> GRAND TOTAL	=======	======	31900 	0.969	100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

Gross floor area....: 32937 sqft Conditioned floor area...: 32937 sqft

#### ENERGY BUDGET BY ENERGY SOURCE

#### TABLE 1. ANNUAL COIL LOADS

Component	(kBTU)	(kBTU/sqft) *
Cooling Loads	1571199	47.703
Heating Loads	1338039	40.624

#### TABLE 2. ENERGY CONSUMPTION BY ENERGY COMPONENT

Component		Energy *> (kBTU/sqft)*	< Source (kBTU)	
Electric Natural Gas Fuel Oil Propane Remote Heating Remote Cooling	1323884 2385029 0 0 0	40.194 72.412 0.000 0.000 0.000 0.000	1323884 2385029 0 0 0	40.194 72.412 0.000 0.000 0.000 0.000
>>> HVAC Total	3708913	112.606	3708913	112.606
Electric Natural Gas Fuel Oil Propane Remote Heating	1693033 0 0 0	51.402 0.000 0.000 0.000 0.000	1693033 0 0 0 0	51.402 0.000 0.000 0.000 0.000
>>> Non-HVAC Tota	al 1693033	51.402	1693033	51.402
>>> GRAND TOTAL	5401945	164.008	5401945	164.008 =======

<sup>\*</sup> Site Energy is the actual energy consumed.

<sup>\*</sup> Source Energy is the site energy divided by the electric generating efficiency of 100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

#### ANNUAL ENERGY COSTS

12-30-94

Building: Building 219 - PLC Weather: Washington (Washington TMY)

HAP v3.04 Prepared by: EINHORN YAFFEE PRESCOTT Page 1 of 1

#### TABLE 1. COSTS BY ENERGY CATEGORY

Component	Annual Energy			Costs> (\$/sqft)*	
Electric Natural Gas Fuel Oil Propane Remote Heating Remote Cooling	190811 15490 0 0 0	kWh Therm	3755 9417 0 0 0	0.114 0.286 0.000 0.000 0.000 0.000	41.1 % 0.0 % 0.0 %
>>> HVAC Subtotal			13172	0.400	57.4 %
Electric Natural Gas Fuel Oil Propane Remote Heating	496200 0 0 0	kWh Therm	9765 0 0 0 0	0.296 0.000 0.000 0.000 0.000	0.0 % 0.0 % 0.0 %
>>> Non-HVAC Subtotal			9765	0.296	42.6 %
>>> GRAND TOTAL	=======		22937	0.696	100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

Gross floor area.....: 32937 sqft Conditioned floor area....: 32937 sqft

#### ENERGY BUDGET BY ENERGY SOURCE

Building: Building 219 - PLC 12-30-94 Weather: Washington (Washington TMY) HAP v3.04

Prepared by: EINHORN YAFFEE PRESCOTT Page 1 of 1

#### TABLE 1. ANNUAL COIL LOADS

Component	(kBTU)	(kBTU/sqft)*
Cooling Loads	1261528	38.301
Heating Loads	794141	24.111

#### TABLE 2. ENERGY CONSUMPTION BY ENERGY COMPONENT

Component		Energy *> (kBTU/sqft)*	< Source (kBTU)	
Electric	651047	19.766	651047	19.766
Natural Gas	1549035	47.030	1549035	47.030
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
Remote Cooling	0	0.000	0	0.000
>>> HVAC Total	2200082	66.797	2200082	66.797
Electric	1693033	51.402	1693033	51.402
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	, 0	0.000
>>> Non-HVAC Tota	al 1693033	51.402	1693033	51.402
>>> GRAND TOTAL	3893114	118.199	3893114	118.199
===============	========	==========		

<sup>\*</sup> Site Energy is the actual energy consumed.

<sup>\*</sup> Source Energy is the site energy divided by the electric generating efficiency of 100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

#### ANNUAL ENERGY COSTS

#### TABLE 1. COSTS BY ENERGY CATEGORY

Component	Annual Energy			Costs> (\$/sqft)*	
Electric Natural Gas Fuel Oil Propane Remote Heating Remote Cooling	181447 15490 0 0 0	kWh Therm	3571 9417 0 0 0	0.108 0.286 0.000 0.000 0.000	
>>> HVAC Subtotal			12987	0.394	57.1 %
Electric Natural Gas Fuel Oil Propane Remote Heating	496200 0 0 0 0	kWh Therm	9765 0 0 0 0	0.296 0.000 0.000 0.000 0.000	0.0 % 0.0 %
>>> Non-HVAC Subtotal	1		9765	0.296	42.9 %
>>> GRAND TOTAL	=======================================	======	22753 	0.691	100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

Gross floor area.....: 32937 sqft Conditioned floor area....: 32937 sqft

#### ENERGY BUDGET BY ENERGY SOURCE

12-30-94

HAP v3.04

Building: Building 219 - DDC Weather: Washington (Washington TMY)

TABLE 1. ANNUAL COIL LOADS

Component	(kBTU)	(kBTU/sqft)*	
Cooling Loads	1166556	35.418	
Heating Loads	794157	24.111	

\_\_\_\_\_

### TABLE 2. ENERGY CONSUMPTION BY ENERGY COMPONENT

Component		Energy *> (kBTU/sqft)*		Energy *> (kBTU/sqft)*
Electric	619098	18.796	619098	18.796
Natural Gas	1549036	47.030	1549036	47.030
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
Remote Cooling	0	0.000	0	0.000
>>> HVAC Total	2168134	65.827	2168134	65.827
Electric	1693033	51.402	1693033	51.402
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
>>> Non-HVAC Tota	il 1693033	51.402	1693033	51.402
>>> GRAND TOTAL	3861166	117.229	3861166	117.229
=======================================		=======================================	=======================================	

<sup>\*</sup> Site Energy is the actual energy consumed.

Gross floor area.....: 32937 sqft Conditioned floor area....: 32937 sqft

<sup>\*</sup> Source Energy is the site energy divided by the electric generating efficiency of 100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

**BUILDING 247** 

# TABLE 1. COSTS BY ENERGY CATEGORY

Component	Annual Energy			Costs> (\$/sqft)*	
Electric	592897	kWh	11668	0.079	
Natural Gas	38163	Therm	23199	0.157	36.9 %
Fuel Oil	0		0	0.000	0.0 %
Propane	0		0	0.000	0.0 %
Remote Heating	0		0	0.000	0.0 %
Remote Cooling	0		0	0.000	0.0 %
>>> HVAC Subtotal			34868	0.235	55.5 %
Electric	1422880	kWh	28002	0.189	44.5 %
Natural Gas	0	Therm	0	0.000	0.0 %
Fuel Oil	0		0	0.000	0.0 %
Propane	0		0	0.000	0.0 %
Remote Heating	0		0	0.000	0.0 %
>>> Non-HVAC Subto	tal		28002	0.189	44.5 %
>>> GRAND TOTAL	========	=====	62870	0.425	100.0 %
=======================================	========	=====	=======================================		

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

Gross floor area....: 148067 sqft Conditioned floor area...: 143338 sqft

Building: Building 247 - Baseline 01-05-95
Weather: Washington (Washington TMY) HAP v3.04
Prepared by: EINHORN YAFFEE PRESCOTT Page 1 of 1

\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

TABLE 1. ANNUAL COIL LOADS

Component	(kBTU)	(kBTU/sqft)*
Cooling Loads	4151033	28.035
Heating Loads	1875302	12.665

# TABLE 2. ENERGY CONSUMPTION BY ENERGY COMPONENT

Component		<pre>Energy *&gt;   (kBTU/sqft) *</pre>	< Source (kBTU)	
Electric	2022966	13.663	2022966	13.663
Natural Gas	3816305	25.774	3816305	25.774
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
Remote Cooling	0	0.000	0	0.000
>>> HVAC Total	5839271	39.437	5839271	39.437
Electric	4854866	32.788	4854866	32.788
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
>>> Non-HVAC Tota	al 4854866	32.788	4854866	32.788
>>> GRAND TOTAL	10694136	72.225	10694136	72.225
=======================================	=========		=======================================	=========

<sup>\*</sup> Site Energy is the actual energy consumed.

Gross floor area.....: 148067 sqft Conditioned floor area....: 143338 sqft

<sup>\*</sup> Source Energy is the site energy divided by the electric generating efficiency of 100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

Building: Building 247 - PLC

01-05-95 HAP v3.04

Weather: Washington (Washington TMY) Prepared by: EINHORN YAFFEE PRESCOTT

Page 1 of 1 \*

# TABLE 1. COSTS BY ENERGY CATEGORY

Component	Annual Energy			Costs> (\$/sqft)*	
Electric Natural Gas Fuel Oil Propane Remote Heating Remote Cooling	406978 27010 0 0 0	kWh Therm	8009 16419 0 0 0	0.054 0.111 0.000 0.000 0.000 0.000	31.3 % 0.0 % 0.0 % 0.0 %
>>> HVAC Subtotal			24429	0.165	46.6 %
Electric Natural Gas Fuel Oil Propane Remote Heating	1422880 0 0 0	_	28002 0 0 0 0	0.189 0.000 0.000 0.000 0.000	0.0 % 0.0 %
>>> Non-HVAC Subto	tal		28002	0.189	53.4 %
>>> GRAND TOTAL	=======================================	======	52431 	0.354	========

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

Gross floor area..... 148067 sqft Conditioned floor area..... 143338 sqft

Building: Building 247 - PLC 01-05-95
Weather: Washington (Washington TMY) HAP v3.04
Prepared by: EINHORN YAFFEE PRESCOTT Page 1 of 1

Prepared by: EINHORN YAFFEE PRESCOTT Page 1 of 1

#### TABLE 1. ANNUAL COIL LOADS

·
25.988 8.519

# TABLE 2. ENERGY CONSUMPTION BY ENERGY COMPONENT

Component		Energy *> (kBTU/sqft)*	< Source (kBTU)	
Electric	1388610	9.378	1388610	9.378
Natural Gas	2701007	18.242	2701007	18.242
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	. 0	0.000
Remote Heating	0	0.000	0	0.000
Remote Cooling	0	0.000	0	0.000
>>> HVAC Total	4089617	27.620	4089617	27.620
Electric	4854866	32.788	4854866	32.788
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
>>> Non-HVAC Tota	al 4854866	32.788	4854866	32.788
>>> GRAND TOTAL	8944482	60.408	8944482	60.408
=======================================	=========		========	

<sup>\*</sup> Site Energy is the actual energy consumed.

Gross floor area.....: 148067 sqft
Conditioned floor area....: 143338 sqft

<sup>\*</sup> Source Energy is the site energy divided by the electric generating efficiency of 100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

TABLE 1. COSTS BY ENERGY CATEGORY

Component	Annual Energy			Costs> (\$/sqft)*	
Electric Natural Gas Fuel Oil Propane Remote Heating Remote Cooling	404356 27079 0 0 0	kWh Therm	7958 16462 0 0 0	0.054 0.111 0.000 0.000 0.000 0.000	31.4 % 0.0 % 0.0 %
>>> HVAC Subtotal			24419	0.165	46.6 %
Electric Natural Gas Fuel Oil Propane Remote Heating	1422880 0 0 0 0	kWh Therm	28002 0 0 0 0	0.189 0.000 0.000 0.000 0.000	0.0 %
>>> Non-HVAC Subto	tal		28002	0.189	53.4 %
>>> GRAND TOTAL	= = = = = = = = = = = = = = = = = = = =		52422 	0.354	========

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

Gross floor area....: 148067 sqft Conditioned floor area...: 143338 sqft

Building: Building 247 - DDC

Weather: Washington (Washington TMY)

HAP v3.04

01-05-95

Prepared by: EINHORN YAFFEE PRESCOTT \*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

Page 1 of 1

TABLE 1. ANNUAL COIL LOADS

Component	(kBTU)	(kBTU/sqft)*	
Cooling Loads	3785796	25.568	
Heating Loads	1265145	8.544	

TABLE 2. ENERGY CONSUMPTION BY ENERGY COMPONENT

Component		Energy *> (kBTU/sqft)*	< Source (kBTU)	
Electric	1379663	9.318	1379663	9.318
Natural Gas	2707936	18.289	2707936	18.289
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
Remote Cooling	0	0.000	0	0.000
>>> HVAC Total	4087599	27.606	4087599	27.606
Electric	4854866	32.788	4854866	32.788
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
>>> Non-HVAC Tota	al 4854866	32.788	4854866	32.788
>>> GRAND TOTAL	8942464	60.395	8942464	60.395
=======================================	========			

<sup>\*</sup> Site Energy is the actual energy consumed.

Gross floor area..... 148067 sqft Conditioned floor area....: 143338 sqft

<sup>\*</sup> Source Energy is the site energy divided by the electric generating efficiency of 100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

**BUILDING 1425** 

TABLE 1. COSTS BY ENERGY CATEGORY

Component	Annual Energy		<		Costs> (\$/sqft)*	% of Total
Electric Natural Gas Fuel Oil Propane Remote Heating Remote Cooling	72273 0 0 0 242 0	kWh 1000	lb	1422 0 0 0 0 1934 0	0.092 0.000 0.000 0.000 0.125 0.000	20.1 % 0.0 % 0.0 % 0.0 % 27.3 % 0.0 %
>>> HVAC Subtotal				3356	0.218	47.3 %
Electric Natural Gas Fuel Oil Propane Remote Heating	189882 0 0 0	kWh	lb	3737 0 0 0 0	0.242 0.000 0.000 0.000 0.000	0.0 % 0.0 %
>>> Non-HVAC Subtotal				3737	0.242	52.7 %
>>> GRAND TOTAL	======	=====	======	7093	0.460	100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

Gross floor area.....: 15430 sqft Conditioned floor area....: 13736 sqft

TABLE 1. ANNUAL COIL LOADS

Component	(kBTU)	(kBTU/sqft)*	
Cooling Loads	452461	29.323	
Heating Loads	217148	14.073	

# TABLE 2. ENERGY CONSUMPTION BY ENERGY COMPONENT

Component		Energy *> (kBTU/sqft)*	< Source (kBTU)	
Electric	246594	15.981	246594	15.981
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	242365	15.707	242365	15.707
Remote Cooling	0	0.000	0	0.000
>>> HVAC Total	488959	31.689	488959	31.689
Electric	647876	41.988	647876	41.988
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
>>> Non-HVAC Tota	al 647876	41.988	647876	41.988
>>> GRAND TOTAL	1136836	73.677	1136836	73.677
=============	:========			

<sup>\*</sup> Site Energy is the actual energy consumed.

Gross floor area.....: 15430 sqft Conditioned floor area....: 13736 sqft

<sup>\*</sup> Source Energy is the site energy divided by the electric generating efficiency of 100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

TABLE 1. COSTS BY ENERGY CATEGORY

Component	Annual Energy		<		Costs> (\$/sqft)*	
Electric Natural Gas Fuel Oil Propane Remote Heating Remote Cooling	56679 0 0 0 70	kWh 1000	lb	1115 0 0 0 0 560	0.072 0.000 0.000 0.000 0.036 0.000	0.0 % 0.0 % 0.0 %
>>> HVAC Subtotal				1675	0.109	31.0 %
Electric Natural Gas Fuel Oil Propane Remote Heating	189882 0 0 0	kWh 1000	lb	3737 0 0 0 0	0.242 0.000 0.000 0.000 0.000	0.0 % 0.0 %
>>> Non-HVAC Subtotal				3737	0.242	69.0 %
>>> GRAND TOTAL	======	=====	======	5412 ======	0.351	100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

Gross floor area....: 15430 sqft Conditioned floor area...: 13736 sqft

Building: Building 1425 - PLC

Weather: Washington (Washington TMY)

01-05-95

HAP v3.04

Prepared by: EINHORN YAFFEE PRESCOTT \*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

Page 1 of 1

#### TABLE 1. ANNUAL COIL LOADS

Cooling Loads       395459       25.629         Heating Loads       64983       4.211	Component	(kBTU)	(kBTU/sqft)*
	3		

# TABLE 2. ENERGY CONSUMPTION BY ENERGY COMPONENT

Component		Energy *> (kBTU/sqft)*	< Source (kBTU)	
Electric	193390	12.533	193390	12.533
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	70176	4.548	70176	4.548
Remote Cooling	0	0.000	0	0.000
>>> HVAC Total	263566	17.081	263566	17.081
Electric	647876	41.988	647876	41.988
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
>>> Non-HVAC Tota	al 647876	41.988	647876	41.988
>>> GRAND TOTAL	911442	59.069	911442	59.069
==============				<del></del>

<sup>\*</sup> Site Energy is the actual energy consumed.

Gross floor area..... 15430 sqft Conditioned floor area..... 13736 sqft

<sup>\*</sup> Source Energy is the site energy divided by the electric generating efficiency of 100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

Building: Building 1425 - DDC

01-05-95 HAP v3.04 Weather: Washington (Washington TMY) Page 1 of 1

Prepared by: EINHORN YAFFEE PRESCOTT \*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

## TABLE 1. COSTS BY ENERGY CATEGORY

Component	Annual Energy		: Annual (\$)	Costs> (\$/sqft)*	
Electric	56679	kWh	1115	0.072	20.6 %
Natural Gas	0		0	0.000	0.0 %
Fuel Oil	0		0	0.000	0.0 %
Propane	0		. 0	0.000	0.0 %
Remote Heating	70	1000 lk	560	0.036	10.3 %
Remote Cooling	0		0	0.000	0.0 %
>>> HVAC Subtotal			1675	0.109	31.0 %
Electric	189882	kWh	3737	0.242	69.0 %
Natural Gas	0		0	0.000	0.0 %
Fuel Oil	0		0	0.000	0.0 %
Propane	0		0	0.000	0.0 %
Remote Heating	0	1000 lk	0	0.000	0.0 %
>>> Non-HVAC Subtotal			3737	0.242	69.0 %
>>> GRAND TOTAL	======	=======	5412	0.351	100.0 %
=======================================		======			=========

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

Gross floor area.....: 15430 sqft Conditioned floor area....: 13736 sqft

Building: Building 1425 - DDC

Weather: Washington (Washington TMY)

01-05-95 HAP v3.04

Prepared by: EINHORN YAFFEE PRESCOTT

Page 1 of 1 \*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

TABLE 1. ANNUAL COIL LOADS

Component	(kBTU)	(kBTU/sqft) *	
Cooling Loads	395459	25.629	
Heating Loads	64983	4.211	

# TABLE 2. ENERGY CONSUMPTION BY ENERGY COMPONENT

Component		Energy *> (kBTU/sqft) *	< Source (kBTU)	
Electric	193390	12.533	193390	12.533
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	70176	4.548	70176	4.548
Remote Cooling	0	0.000	0	0.000
>>> HVAC Total	263566	17.081	263566	17.081
Electric	647876	41.988	647876	41.988
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	. 0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
>>> Non-HVAC Tota	al 647876	41.988	647876	41.988
>>> GRAND TOTAL	911442	59.069	911442	59.069
====		<del></del>		

<sup>\*</sup> Site Energy is the actual energy consumed.

Gross floor area..... 15430 sqft Conditioned floor area..... 13736 sqft

<sup>\*</sup> Source Energy is the site energy divided by the electric generating efficiency of 100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

**BUILDING 3136** 

Building: Building 3136 - Baseline 01-05-95
Weather: Washington (Washington TMY) HAP v3.04
Prepared by: EINHORN YAFFEE PRESCOTT Page 1 of 1

## TABLE 1. COSTS BY ENERGY CATEGORY

Component	Annual Energy		<	Annual (\$)	Costs> (\$/sqft)*	% of Total
Electric Natural Gas Fuel Oil Propane Remote Heating Remote Cooling	82975 0 0 0 413 0	kWh	lb	1633 0 0 0 3292 0	0.139 0.000 0.000 0.000 0.280 0.000	16.4 % 0.0 % 0.0 % 0.0 % 33.0 % 0.0 %
>>> HVAC Subtotal				4925	0.419	49.4 %
Electric Natural Gas Fuel Oil Propane Remote Heating	256487 0 0 0 0	kWh 1000	lb	5048 0 0 0 0	0.429 0.000 0.000 0.000 0.000	0.0 왕
>>> Non-HVAC Subtotal				5048	0.429	50.6 %
>>> GRAND TOTAL	======	=====	======	9973 ======	0.848	========

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

Gross floor area....: 11760 sqft Conditioned floor area...: 10600 sqft

## TABLE 1. ANNUAL COIL LOADS

Component	(kBTU)	(kBTU/sqft) *
Cooling Loads	566514	48.173
Heating Loads	360888	30.688

# TABLE 2. ENERGY CONSUMPTION BY ENERGY COMPONENT

Component		Energy *> (kBTU/sqft)*	< Source (kBTU)	
Electric	283111	24.074	283111	24.074
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	412547	35.080	412547	35.080
Remote Cooling	0	0.000	0	0.000
>>> HVAC Total	695657	59.155	695657	59.155
Electric	875133	74.416	875133	74.416
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
>>> Non-HVAC Tota	al 875133	74.416	875133	74.416
>>> GRAND TOTAL	1570791	133.571	1570791	133.571
=======================================	========	==========	:=========	

<sup>\*</sup> Site Energy is the actual energy consumed.

Gross floor area.....: 11760 sqft Conditioned floor area....: 10600 sqft

<sup>\*</sup> Source Energy is the site energy divided by the electric generating efficiency of 100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

TABLE 1. COSTS BY ENERGY CATEGORY

Component	Annual Energy		<		Costs> (\$/sqft)*	
Electric	75724	kWh		1490	0.127	17.8 %
Natural Gas	0			0	0.000	0.0 %
Fuel Oil	0			0	0.000	0.0 %
Propane	0			0	0.000	0.0 %
Remote Heating	228	1000	lb	1818	0.155	21.8 %
Remote Cooling	0			0	0.000	0.0 %
>>> HVAC Subtotal				3308	0.281	39.6 %
Electric	256487	kWh		5048	0.429	60.4 %
Natural Gas	0			0	0.000	0.0 %
Fuel Oil	0			0	0.000	
Propane	0			0	0.000	0.0 왕
Remote Heating	0	1000	lb	0	0.000	0.0 용 
>>> Non-HVAC Subtotal				5048	0.429	60.4 %
>>> GRAND TOTAL	======	====	======	8356	0.711	100.0 %
=======================================	======:	====:	=====	======	======================================	

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

Gross floor area.....: 11760 sqft Conditioned floor area....: 10600 sqft

Building: Building 3136 - PLC 01-05-95
Weather: Washington (Washington TMY) HAP v3.04
Prepared by: EINHORN YAFFEE PRESCOTT Page 1 of 1

# TABLE 1. ANNUAL COIL LOADS

Cooling Loads 499102 42.441	Component	(kBTU)	(kBTU/sqft) *	_
Heating Loads 207526 17.647	Cooling Loads Heating Loads			_

# TABLE 2. ENERGY CONSUMPTION BY ENERGY COMPONENT

Component		Energy *> (kBTU/sqft)*	< Source (kBTU)	
Electric	258369	21.970	258369	21.970
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	227850	19.375	227850	19.375
Remote Cooling	0	0.000	0	0.000
>>> HVAC Total	486219	41.345	486219	41.345
Electric	875133	74.416	875133	74.416
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
>>> Non-HVAC Tota	al 875133	74.416	875133	74.416
>>> GRAND TOTAL	1361352	115.761	1361352	115.761
=======================================	========		<b></b>	

<sup>\*</sup> Site Energy is the actual energy consumed.

Gross floor area....: 11760 sqft Conditioned floor area...: 10600 sqft

<sup>\*</sup> Source Energy is the site energy divided by the electric generating efficiency of 100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

## TABLE 1. COSTS BY ENERGY CATEGORY

Component	Annual Energy		<- <b>-</b>	Annual (\$)	Costs> (\$/sqft)*	% of Total
Electric Natural Gas Fuel Oil Propane Remote Heating Remote Cooling	75724 0 0 0 228 0	kWh	lb	1490 0 0 0 1818 0	0.127 0.000 0.000 0.000 0.155 0.000	0.0 % 0.0 % 0.0 %
>>> HVAC Subtotal				3308	0.281	39.6 %
Electric Natural Gas Fuel Oil Propane Remote Heating	256487 0 0 0	kWh	1b	5048 0 0 0 0	0.429 0.000 0.000 0.000 0.000	0.0 %
>>> Non-HVAC Subtotal				5048	0.429	60.4 %
>>> GRAND TOTAL	:======	====		8356	0.711	=======

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

Gross floor area.....: 11760 sqft Conditioned floor area....: 10600 sqft

Building: Building 3136 - DDC

Weather: Washington (Washington TMY)

HAP v3.04 Page 1 of 1

01-05-95

# TABLE 1. ANNUAL COIL LOADS

Component	(kBTU)	(kBTU/sqft) *
Cooling Loads Heating Loads	499102 207526	42.441 17.647

# TABLE 2. ENERGY CONSUMPTION BY ENERGY COMPONENT

Component		Energy *> (kBTU/sqft)*	< Source (kBTU)	
Electric	258369	21.970	258369	21.970
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	227850	19.375	227850	19.375
Remote Cooling	0	0.000	0	0.000
>>> HVAC Total	486219	41.345	486219	41.345
Electric	875133	74.416	875133	74.416
Natural Gas	0	0.000	0	0.000
Fuel Oil	0	0.000	0	0.000
Propane	0	0.000	0	0.000
Remote Heating	0	0.000	0	0.000
>>> Non-HVAC Tota	al 875133	74.416	875133	74.416
>>> GRAND TOTAL	1361352	115.761	1361352	115.761
=======================================	=========	_======================================	=======================================	

<sup>\*</sup> Site Energy is the actual energy consumed.

<sup>\*</sup> Source Energy is the site energy divided by the electric generating efficiency of 100.0 %

<sup>\*</sup> Cost per unit floor area is based on the gross building floor area.

# APPENDIX E BLCC 4.2 LIFE CYCLE COST ANALYSIS INPUT DATA

**BUILDING 200** 

\*\*\*\*\*\*\*\*\*\*\*\* \* NIST BLCC INPUT DATA LISTING (version 4.20-) \* \*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

FILE NAME: 200-BASE

FILE LAST MODIFIED ON 08-16-1995/12:30:38

PROJECT ALTERNATIVE: BLDG200-BASE

COMMENT: (NONE)

## GENERAL DATA: \_\_\_\_\_\_

ANALYSIS TYPE: Federal Analysis -- Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995

STUDY PERIOD: 10 YEARS, 0 MONTHS SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

# CAPITAL ASSET COST DATA:

\_\_\_\_\_\_ INITIAL COST (BASE YEAR \$) 0 10/0 EXPECTED ASSET LIFE (YRS/MTHS) 0.00% RESALE VALUE FACTOR Ω NUMBER OF REPLACEMENTS

NO REPLACEMENTS

OPERATING, MAINTENANCE, AND REPAIR COST DATA:

\_\_\_\_\_

ANNUAL RECUR OM&R COST (\$): 8495

No non-annually-recurring OM&R costs reported.

#### ENERGY-RELATED DATA:

\_\_\_\_\_

NUMBER OF ENERGY TYPES = 2

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA) DOE rate schedule type: Industrial

Underlying gen. inflation rate used with DOE rates: 0.00%

	TYPE 1	TYPE 2
ENERGY TYPE:	Electricity	Natural Gas
BASE ANNUAL CONSUMPTION:	727922	29904
UNITS:	kWh	Therm
PRICE PER UNIT (\$):	0.020	0.608
ANNUAL DEMAND CHARGE (\$):	1700.00	0.00
ESCALATION RATE METHOD:	DOE rates	DOE rates
1995	0.39	3.38
1996	0.24	1.98
1997	0.38	3.16
1998	0.59	4.11
1999	1.24	4.75
2000	1.12	5.03
2001	0.67	5.22
2002	1.00	5.69
2003	1.09	4.99

2004 0.62 2005 0.00

experience

3.47

FILE NAME: 200-FMR

FILE LAST MODIFIED ON 08-16-1995/12:31:31

PROJECT ALTERNATIVE: BLDG200-FMR

COMMENT: (NONE)

# GENERAL DATA:

ANALYSIS TYPE: Federal Analysis -- Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995

STUDY PERIOD: 10 YEARS, 0 MONTHS

SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

# CAPITAL ASSET COST DATA:

INITIAL COST (BASE YEAR \$) 1115 EXPECTED ASSET LIFE (YRS/MTHS) 10/0 RESALE VALUE FACTOR 0.00% NUMBER OF REPLACEMENTS 0

NO REPLACEMENTS

engare adalescence

OPERATING, MAINTENANCE, AND REPAIR COST DATA:

.....

ANNUAL RECUR OM&R COST (\$): 8495

No non-annually-recurring OM&R costs reported.

#### ENERGY-RELATED DATA:

\_\_\_\_\_

NUMBER OF ENERGY TYPES = 2

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA)
DOE rate schedule type: Industrial

Underlying gen. inflation rate used with DOE rates: 0.00%

TYPE 1 TYPE 2 Electricity Natural Gas ENERGY TYPE: 727922 BASE ANNUAL CONSUMPTION: 29904 Therm kWh UNITS: 0.020 0.608 PRICE PER UNIT (\$): ANNUAL DEMAND CHARGE (\$): 0.00 0.00 ESCALATION RATE METHOD: DOE rates DOE rates 3.38 0.39 1995 1.98 0.24 1996 3.16 0.38 1997 0.59 4.11 1998 4.75 1999 1.24 1.12 5.03 2000 5.22 2001 0.67 5.69 1.00 2002

 2003
 1.09
 4.99

 2004
 0.62
 3.47

 2005
 0.00
 0.00

er e grande hallege, bli

E-5

FILE NAME: 200-PLC

FILE LAST MODIFIED ON 08-16-1995/12:32:22

PROJECT ALTERNATIVE: BLDG200-PLC

COMMENT: (NONE)

# GENERAL DATA:

ANALYSIS TYPE: Federal Analysis -- Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995

STUDY PERIOD: 10 YEARS, 0 MONTHS

SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

# CAPITAL ASSET COST DATA:

\_\_\_\_\_

INITIAL COST (BASE YEAR \$) 12711
EXPECTED ASSET LIFE (YRS/MTHS) 20/0
RESALE VALUE FACTOR 0.00%
NUMBER OF REPLACEMENTS 0

NO REPLACEMENTS

OPERATING, MAINTENANCE, AND REPAIR COST DATA:

\_\_\_\_\_

ANNUAL RECUR OM&R COST (\$): 8495

No non-annually-recurring OM&R costs reported.

# ENERGY-RELATED DATA:

Committee of the state of the s

NUMBER OF ENERGY TYPES = 2

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA)
DOE rate schedule type: Industrial

Underlying gen. inflation rate used with DOE rates: 0.00%

TYPE 2 TYPE 1 ENERGY TYPE: Electricity Natural Gas BASE ANNUAL CONSUMPTION: 666966 22171 kWh Therm UNITS: 0.020 0.608 PRICE PER UNIT (\$): 1700.00 ANNUAL DEMAND CHARGE (\$): 0.00 DOE rates DOE rates ESCALATION RATE METHOD: 1995 0.39 3.38 1.98 1996 0.24 3.16 0.38 1997 4.11 0.59 1998 4.75 1999 1.24 1.12 2000 5.03 0.67 5.22 2001 1.00 5.69 2002

 2003
 1.09
 4.99

 2004
 0.62
 3.47

 2005
 0.00
 0.00

;

E-7

FILE NAME: 200-DDC

FILE LAST MODIFIED ON 08-16-1995/12:33:30

PROJECT ALTERNATIVE: BLDG200-DDC

COMMENT: (NONE)

# GENERAL DATA:

ANALYSIS TYPE: Federal Analysis -- Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995

STUDY PERIOD: 10 YEARS, 0 MONTHS

SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

# CAPITAL ASSET COST DATA:

INITIAL COST (BASE YEAR \$) 78764
EXPECTED ASSET LIFE (YRS/MTHS) 20/0
RESALE VALUE FACTOR 0.00%
NUMBER OF REPLACEMENTS 0

NO REPLACEMENTS

بدائا فالججع بججعات

OPERATING, MAINTENANCE, AND REPAIR COST DATA:

\_\_\_\_\_

ANNUAL RECUR OM&R COST (\$): 2935

No non-annually-recurring OM&R costs reported.

#### ENERGY-RELATED DATA:

\_\_\_\_\_\_

NUMBER OF ENERGY TYPES = 2

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA)
DOE rate schedule type: Industrial

Underlying gen. inflation rate used with DOE rates: 0.00%

	TYPE 1	TYPE 2
ENERGY TYPE:	Electricity	Natural Gas
BASE ANNUAL CONSUMPTION:	628377	18411
UNITS:	kWh	Therm
PRICE PER UNIT (\$):	0.020	0.608
ANNUAL DEMAND CHARGE (\$):	0.00	0.00
ESCALATION RATE METHOD:	DOE rates	DOE rates
1995	0.39	3.38
1996	0.24	1.98
1997	0.38	3.16
1998	0.59	4.11
1999	1.24	4.75
2000	1.12	5.03
2001	0.67	5.22
2002	1.00	5.69

 2003
 1.09
 4.99

 2004
 0.62
 3.47

 2005
 0.00
 0.00

.....

Sample Stick Commission of the Control of the Contr

**BUILDING 219** 

\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\* \* NIST BLCC INPUT DATA LISTING (version 4.20-) \* \*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

FILE NAME: 219-BASE

FILE LAST MODIFIED ON 08-16-1995/12:34:45

PROJECT ALTERNATIVE: BLDG219-BASE

COMMENT: (NONE)

#### GENERAL DATA:

ANALYSIS TYPE: Federal Analysis -- Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995 STUDY PERIOD: 10 YEARS, 0 MONTHS

SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

#### CAPITAL ASSET COST DATA:

\_\_\_\_\_ INITIAL COST (BASE YEAR \$) 10/0 EXPECTED ASSET LIFE (YRS/MTHS) 0.00% RESALE VALUE FACTOR NUMBER OF REPLACEMENTS Ω

NO REPLACEMENTS

and a single

. Walio e e la p

OPERATING, MAINTENANCE, AND REPAIR COST DATA:

\_\_\_\_\_

ANNUAL RECUR OM&R COST (\$): 6090

No non-annually-recurring OM&R costs reported.

# ENERGY-RELATED DATA:

\_\_\_\_\_\_

NUMBER OF ENERGY TYPES = 2

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA) DOE rate schedule type: Industrial

Underlying gen. inflation rate used with DOE rates: 0.00%

TVDE 1

ממעים כ

	TYPE I	TYPE 2
ENERGY TYPE:	Electricity	Natural Gas
BASE ANNUAL CONSUMPTION:	903608	25043
UNITS:	kWh	Therm
PRICE PER UNIT (\$):	0.020	0.608
ANNUAL DEMAND CHARGE (\$):	1708.00	0.00
ESCALATION RATE METHOD:	DOE rates	DOE rates
1995	0.39	3.38
1996	0.24	1.98
1997	0.38	3.16
1998	0.59	4.11
1999	1.24	4.75
2000	1.12	5.03
2001	0.67	5.22
2002	1.00	5.69

 2003
 1.09
 4.99

 2004
 0.62
 3.47

 2005
 0.00
 0.00

એવા જોડા **ફેટ**લ્લા હતા

and the state of the state of the state of the state of the state of the state of the state of the state of the

FILE NAME: 219-FMR

FILE LAST MODIFIED ON 08-16-1995/12:35:26

PROJECT ALTERNATIVE: BLDG219-FMR

COMMENT: (NONE)

#### GENERAL DATA:

ANALYSIS TYPE: Federal Analysis -- Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995

STUDY PERIOD: 10 YEARS, 0 MONTHS

SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

# CAPITAL ASSET COST DATA:

INITIAL COST (BASE YEAR \$) 1673
EXPECTED ASSET LIFE (YRS/MTHS) 10/0
RESALE VALUE FACTOR 0.00%
NUMBER OF REPLACEMENTS 0

NO REPLACEMENTS

A STATE OF STATE OF STATE OF

OPERATING, MAINTENANCE, AND REPAIR COST DATA:

\_\_\_\_\_

ANNUAL RECUR OM&R COST (\$): 6090

No non-annually-recurring OM&R costs reported.

#### ENERGY-RELATED DATA:

\_\_\_\_\_\_

NUMBER OF ENERGY TYPES = 2

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA)

DOE rate schedule type: Industrial

Underlying gen. inflation rate used with DOE rates: 0.00%

	TYPE 1	TYPE 2
ENERGY TYPE:	Electricity	Natural Gas
BASE ANNUAL CONSUMPTION:	903608	25043
UNITS:	kWh	Therm
PRICE PER UNIT (\$):	0.020	0.608
ANNUAL DEMAND CHARGE (\$):	0.00	0.00
ESCALATION RATE METHOD:	DOE rates	DOE rates
1995	0.39	3.38
1996	0.24	1.98
1997	0.38	3.16
1998	0.59	4.11
1999	1.24	4.75
2000	1.12	5.03
2001	0.67	5.22
2002	1.00	5.69

 2003
 1.09
 4.99

 2004
 0.62
 3.47

 2005
 0.00
 0.00

संदर्भतिक्षेत्रः अ

-witherpel

E-14

\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\* \* NIST BLCC INPUT DATA LISTING (version 4.20-) \* \*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

FILE NAME: 219-PLC

FILE LAST MODIFIED ON 08-16-1995/12:36:13

PROJECT ALTERNATIVE: BLDG219-PLC

COMMENT: (NONE)

GENERAL DATA:

ANALYSIS TYPE: Federal Analysis -- Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995

STUDY PERIOD: 10 YEARS, 0 MONTHS

SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

## CAPITAL ASSET COST DATA:

\_\_\_\_\_

12516 INITIAL COST (BASE YEAR \$) EXPECTED ASSET LIFE (YRS/MTHS) 10/0 0.00% RESALE VALUE FACTOR NUMBER OF REPLACEMENTS 0

NO REPLACEMENTS

OPERATING, MAINTENANCE, AND REPAIR COST DATA:

\_\_\_\_\_

ANNUAL RECUR OM&R COST (\$): 6090

No non-annually-recurring OM&R costs reported.

#### ENERGY-RELATED DATA:

\_\_\_\_\_

NUMBER OF ENERGY TYPES = 2

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA)

and the commence of the second

DOE rate schedule type: Industrial

Underlying gen. inflation rate used with DOE rates: 0.00%

3 3 3	(\$):	696551 kWh 0.020 1708.00 DOE rates 0.39 0.24 0.38 0.59 1.24	TYPE 2 Natural Gas 16265 Therm 0.608 0.00 DOE rates 3.38 1.98 3.16 4.11 4.75
_			
-	2000 2001	1.12 0.67	5.03 5.22
	2002	1.00	5.69

 2003
 1.09
 4.99

 2004
 0.62
 3.47

 2005
 0.00
 0.00

e ceret i d

อนุทุนที่เหลา<del>เพียงสมมาก</del> พ.ศ. (1977) (ค.ศ.

E-16

\*\*\*\*\*\*\*\*\*\*\*\*\*\*\* \* NIST BLCC INPUT DATA LISTING (version 4.20-) \* \*\*\*\*\*\*\*\*\*\*\*\*\*\*

FILE NAME: 219-DDC

FILE LAST MODIFIED ON 08-16-1995/12:36:51

PROJECT ALTERNATIVE: BLDG219-DDC

COMMENT: (NONE)

#### GENERAL DATA: \_\_\_\_\_

1

ANALYSIS TYPE: Federal Analysis -- Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995 STUDY PERIOD: 10 YEARS, 0 MONTHS

SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

#### CAPITAL ASSET COST DATA: \_\_\_\_\_\_

72141 INITIAL COST (BASE YEAR \$) 10/0 EXPECTED ASSET LIFE (YRS/MTHS) 0.00% RESALE VALUE FACTOR 0 NUMBER OF REPLACEMENTS

NO REPLACEMENTS

OPERATING, MAINTENANCE, AND REPAIR COST DATA: \_\_\_\_\_\_

ANNUAL RECUR OM&R COST (\$): 2380

No non-annually-recurring OM&R costs reported.

ENERGY-RELATED DATA:

\_\_\_\_\_

NUMBER OF ENERGY TYPES = 2

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA) DOE rate schedule type: Industrial

a plijala propinacija je je je je propinacija propinacija propinacija propinacija propinacija propinacija propi

Underlying gen. inflation rate used with DOE rates: 0.00%

ENERGY TYPE: BASE ANNUAL CONSUMPTION: UNITS: PRICE PER UNIT (\$): ANNUAL DEMAND CHARGE (\$): ESCALATION RATE METHOD:	TYPE 1 Electricity 677647 kWh 0.020 0.00 DOE rates	TYPE 2 Natural Gas 15490 Therm 0.608 0.00 DOE rates
1995	0.39	3.38
1996	0.24	1.98
1997	0.38	3.16
1998	0.59	4.11
1999	1.24	4.75
2000	1.12	5.03
2001	0.67	5.22
2002	1.00	5.69

 2003
 1.09
 4.99

 2004
 0.62
 3.47

 2005
 0.00
 0.00

Server services

**BUILDING 247** 

FILE NAME: 247-BASE

FILE LAST MODIFIED ON 08-16-1995/12:37:40

PROJECT ALTERNATIVE: BLDG247-BASE

COMMENT: (NONE)

# GENERAL DATA:

\*

 $(p_{ijk},p_{ijk})_{ijk}(p_{ijk}) = (-1)$ 

3.3 3件 点

ANALYSIS TYPE: Federal Analysis--Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995

STUDY PERIOD: 10 YEARS, 0 MONTHS

SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

#### CAPITAL ASSET COST DATA:

INITIAL COST (BASE YEAR \$) 0
EXPECTED ASSET LIFE (YRS/MTHS) 10/0
RESALE VALUE FACTOR 0.00%
NUMBER OF REPLACEMENTS 0

NO REPLACEMENTS

OPERATING, MAINTENANCE, AND REPAIR COST DATA:

-----

ANNUAL RECUR OM&R COST (\$): 14815

No non-annually-recurring OM&R costs reported.

## ENERGY-RELATED DATA:

, og er skaper forgrundigt for til en til en til en til en til en til en til en til en til en til en til en ti

\_\_\_\_\_

NUMBER OF ENERGY TYPES = 2

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA)

DOE rate schedule type: Industrial

Underlying gen. inflation rate used with DOE rates: 0.00%

	TYPE 1	TYPE 2
ENERGY TYPE:	Electricity	Natural Gas
BASE ANNUAL CONSUMPTION:	2045422	40071
UNITS:	kWh	Therm
PRICE PER UNIT (\$):	0.020	0.608
ANNUAL DEMAND CHARGE (\$):	3070.00	0.00
ESCALATION RATE METHOD:	DOE rates	DOE rates
1995	0.39	3.38
1996	0.24	1.98
1997	0.38	3.16
1998	0.59	4.11
1999	1.24	4.75
2000	1.12	5.03
2001	0.67	5.22
2002	1.00	5.69

The state of the s

2003	1.09 .	4.99
2004	0.62	3.47
2005	0.00	0.00

性现代的特点。

FILE NAME: 247-FMR

FILE LAST MODIFIED ON 08-16-1995/12:38:24

PROJECT ALTERNATIVE: BLDG247-FMR

COMMENT: (NONE)

#### GENERAL DATA:

ANALYSIS TYPE: Federal Analysis -- Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995

STUDY PERIOD: 10 YEARS, 0 MONTHS

SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

## CAPITAL ASSET COST DATA:

INITIAL COST (BASE YEAR \$) 558
EXPECTED ASSET LIFE (YRS/MTHS) 10/0
RESALE VALUE FACTOR 0.00%
NUMBER OF REPLACEMENTS 0

NO REPLACEMENTS

. Salat i je popija i i i

OPERATING, MAINTENANCE, AND REPAIR COST DATA:

\_\_\_\_\_

ANNUAL RECUR OM&R COST (\$): 14815

No non-annually-recurring OM&R costs reported.

#### ENERGY-RELATED DATA:

\_\_\_\_\_\_

NUMBER OF ENERGY TYPES = 2

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA)

DOE rate schedule type: Industrial

Underlying gen. inflation rate used with DOE rates: 0.00%

ENERGY TYPE: BASE ANNUAL CONSUMPTION: UNITS: PRICE PER UNIT (\$): ANNUAL DEMAND CHARGE (\$): ESCALATION RATE METHOD:	TYPE 1 Electricity 2045422 kWh 0.020 0.00 DOE rates	TYPE 2 Natural Gas 40071 Therm 0.608 0.00 DOE rates
1995 1996 1997 1998 1999	0.39 0.24 0.38 0.59 1.24	3.38 1.98 3.16 4.11 4.75 5.03
2000 2001 2002	1.12 0.67 1.00	5.03 5.22 5.69

2003	1.09	4.99	
2004	0.62	3.47	
2005	0.00	0.00	

STATE OF THE STATE

eg Sad

## \*\*\*\*\*\*\*\*\*\*\*\*\*\*\* \* NIST BLCC INPUT DATA LISTING (version 4.20-) \* \*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

FILE NAME: 247-PLC

FILE LAST MODIFIED ON 08-16-1995/12:39:17

PROJECT ALTERNATIVE: BLDG247-PLC

COMMENT: (NONE)

#### GENERAL DATA: \_\_\_\_\_\_

1

عيانه ايشير بيدونيدي

Afrika, binin

ANALYSIS TYPE: Federal Analysis -- Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995

STUDY PERIOD: 10 YEARS, 0 MONTHS

SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

#### CAPITAL ASSET COST DATA: \_\_\_\_\_\_

14914 INITIAL COST (BASE YEAR \$) 10/0 EXPECTED ASSET LIFE (YRS/MTHS) 0.00% RESALE VALUE FACTOR 0 NUMBER OF REPLACEMENTS

NO REPLACEMENTS

# OPERATING, MAINTENANCE, AND REPAIR COST DATA:

\_\_\_\_\_\_

ANNUAL RECUR OM&R COST (\$): 14815

No non-annually-recurring OM&R costs reported.

#### ENERGY-RELATED DATA:

\_\_\_\_\_

NUMBER OF ENERGY TYPES = 2

and the state of t

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA) DOE rate schedule type: Industrial

Underlying gen. inflation rate used with DOE rates: 0.00%

TYPE 1 TYPE 2 Electricity Natural Gas ENERGY TYPE: BASE ANNUAL CONSUMPTION: 28361 1850207 Therm kWh UNITS: PRICE PER UNIT (\$): 0.020 0.608 ANNUAL DEMAND CHARGE (\$): 0.00 3070.00 DOE rates DOE rates ESCALATION RATE METHOD: 0.39 3.38 1995 0.24 1.98 1996 0.38 3.16 1997 0.59 4.11 1998 4.75 1.24 1999 1.12 5.03 2000 0.67 5.22 2001 5.69 1.00 2002

 2003
 1.09
 4.99

 2004
 0.62
 3.47

 2005
 0.00
 0.00

edianimania di

E-25

FILE NAME: 247-DDC

FILE LAST MODIFIED ON 08-16-1995/12:40:06

PROJECT ALTERNATIVE: BLDG247-DDC

COMMENT: (NONE)

#### GENERAL DATA:

ANALYSIS TYPE: Federal Analysis -- Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995

STUDY PERIOD: 10 YEARS, 0 MONTHS

SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

# CAPITAL ASSET COST DATA:

INITIAL COST (BASE YEAR \$) 87416
EXPECTED ASSET LIFE (YRS/MTHS) 10/0
RESALE VALUE FACTOR 0.00%
NUMBER OF REPLACEMENTS 0

NO REPLACEMENTS

OPERATING, MAINTENANCE, AND REPAIR COST DATA:

-----

ANNUAL RECUR OM&R COST (\$): 12515

No non-annually-recurring OM&R costs reported.

# ENERGY-RELATED DATA:

\_\_\_\_\_\_

كالحراروم وفاعرتهم

NUMBER OF ENERGY TYPES = 2

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA)

DOE rate schedule type: Industrial

Underlying gen. inflation rate used with DOE rates: 0.00%

	TYPE 1	TYPE 2
ENERGY TYPE:	Electricity	Natural Gas
BASE ANNUAL CONSUMPTION:	1827236	27079
UNITS:	kWh	Therm
PRICE PER UNIT (\$):	0.020	0.608
ANNUAL DEMAND CHARGE (\$):	0.00	0.00
ESCALATION RATE METHOD:	DOE rates	DOE rates
1995	0.39	3.38
1996	0.24	1.98
1997	0.38	3.16
1998	0.59	4.11
1999	1.24	4.75
2000	1.12	5.03
2001	0.67	5.22
2002	1.00	5.69

2003	1.09	4.99
2004	0.62	3.47
2005	0.00	0.00

•

द्यानस्थात्रा लेकानस्य

**BUILDING 1425** 

FILE NAME: 1425BASE

FILE LAST MODIFIED ON 08-16-1995/12:41:14

PROJECT ALTERNATIVE: BLDG1425BASE

COMMENT: (NONE)

# GENERAL DATA:

ANALYSIS TYPE: Federal Analysis -- Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995

STUDY PERIOD: 10 YEARS, 0 MONTHS

SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

## CAPITAL ASSET COST DATA:

INITIAL COST (BASE YEAR \$) 0
EXPECTED ASSET LIFE (YRS/MTHS) 10/0
RESALE VALUE FACTOR 0.00%
NUMBER OF REPLACEMENTS 0

NO REPLACEMENTS

وأراوانيان وأبان

OPERATING, MAINTENANCE, AND REPAIR COST DATA:

\_\_\_\_\_

ANNUAL RECUR OM&R COST (\$): 4930

No non-annually-recurring OM&R costs reported.

# ENERGY-RELATED DATA:

NUMBER OF ENERGY TYPES = 2

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA)
DOE rate schedule type: Industrial

Underlying gen. inflation rate used with DOE rates: 0.00%

TYPE 2 TYPE 1 Electricity Central Stea ENERGY TYPE: BASE ANNUAL CONSUMPTION: 265769 254000 kWh Pound UNITS: 0.008 PRICE PER UNIT (\$): 0.020 ANNUAL DEMAND CHARGE (\$): 0.00 456.00 DOE rates ESCALATION RATE METHOD: DOE rates IF DOE ESC, ENERGY TYPE: Electricity Natural Gas 1995 0.39 3.38 0.24 1.98 1996 0.38 3.16 1997 1998 0.59 4.11 1.24 1999 4.75 1.12 5.03 2000 2001 0.67 5.22

2002	1.00	5.69
2003	1.09	4.99
2003	0.62	3.47
2005	0.00	0.00

ages and following

1.10

A Company of the Company

E-30

\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\* \* NIST BLCC INPUT DATA LISTING (version 4.20-) \* \*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

FILE NAME: 1425-FMS

FILE LAST MODIFIED ON 08-16-1995/12:42:35

PROJECT ALTERNATIVE: BLDG1425-FMR

COMMENT: (NONE)

#### GENERAL DATA:

ANALYSIS TYPE: Federal Analysis -- Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995

STUDY PERIOD: 10 YEARS, 0 MONTHS

SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

#### CAPITAL ASSET COST DATA:

\_\_\_\_\_

558 INITIAL COST (BASE YEAR \$) 10/0 EXPECTED ASSET LIFE (YRS/MTHS) 0.00% RESALE VALUE FACTOR 0 NUMBER OF REPLACEMENTS

NO REPLACEMENTS

daga alam d

OPERATING, MAINTENANCE, AND REPAIR COST DATA: \_\_\_\_\_

ANNUAL RECUR OM&R COST (\$): 4930

No non-annually-recurring OM&R costs reported.

#### ENERGY-RELATED DATA:

\_\_\_\_\_\_

NUMBER OF ENERGY TYPES = 2

a Magazales de la grego, le filo de filo de la colonia de la colonia de la colonia de la colonia de la colonia

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA)

DOE rate schedule type: Industrial

Underlying gen. inflation rate used with DOE rates: 0.00%

ENERGY TYPE: BASE ANNUAL CONSUMPTION:	265769	
UNITS:	kWh	Pound
PRICE PER UNIT (\$):	0.020	0.008
ANNUAL DEMAND CHARGE (\$):	0.00	0.00
ESCALATION RATE METHOD:	DOE rates	
IF DOE ESC, ENERGY TYPE:	Electricity	Natural Gas
1995	0.39	3.38
1996	0.24	1.98
<del></del>		3.16
1997	0.38	
1998	0.59	4.11
1999	1.24	4.75
2000	1.12	5.03
2001	0.67	5.22

2002	1.00	5.69
2003	1.09	4.99
2004	0.62	3.47
2005	0 00	0.00

\*\*\*\*\*\*\*\*\*\*\*\*\* \* NIST BLCC INPUT DATA LISTING (version 4.20-) \* \*\*\*\*\*\*\*\*\*\*\*\*\*\*

FILE NAME: 1425-PLC

FILE LAST MODIFIED ON 08-16-1995/12:44:05

PROJECT ALTERNATIVE: BLDG1425-PLC

COMMENT: (NONE)

#### GENERAL DATA:

ANALYSIS TYPE: Federal Analysis -- Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995

STUDY PERIOD: 10 YEARS, 0 MONTHS

SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

#### CAPITAL ASSET COST DATA:

\_\_\_\_\_

INITIAL COST (BASE YEAR \$) 11518 10/0 EXPECTED ASSET LIFE (YRS/MTHS) 0.00% RESALE VALUE FACTOR NUMBER OF REPLACEMENTS Ω

NO REPLACEMENTS

4

OPERATING, MAINTENANCE, AND REPAIR COST DATA:

\_\_\_\_\_\_

ANNUAL RECUR OM&R COST (\$): 4930

No non-annually-recurring OM&R costs reported.

## ENERGY-RELATED DATA:

\_\_\_\_\_\_

NUMBER OF ENERGY TYPES = 2

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA)

DOE rate schedule type: Industrial

Underlying gen. inflation rate used with DOE rates: 0.00%

TVDE 1

	TYPE I	TYPE Z
ENERGY TYPE:	Electricity	Central Stea
BASE ANNUAL CONSUMPTION:	249395	73500
UNITS:	kWh	Pound
PRICE PER UNIT (\$):	0.020	0.008
ANNUAL DEMAND CHARGE (\$):	456.00	0.00
ESCALATION RATE METHOD:		
IF DOE ESC, ENERGY TYPE:	Electricity	Natural Gas
1995	0.39	3.38
1996	0.24	1.98
1997	0.38	3.16
1998	0.59	4.11
1999	1.24	4.75
2000	1.12	5.03
2001	0.67	5.22

rdallainta tetta ka ja jii kaat ta Malalaja ja kirjaanda ka ka ja ja ja ja ja ka ka ka ja ja ja ja ja ja ja ja

ב שמעת

2002	1.00	5.69
2003	1.09	4.99
2004	0.62	3.47
2005	0.00	0.00

our sign

FILE NAME: 1425-DDC

FILE LAST MODIFIED ON 08-16-1995/12:44:58

PROJECT ALTERNATIVE: BLDG1425-DDC

COMMENT: (NONE)

# GENERAL DATA:

ANALYSIS TYPE: Federal Analysis -- Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995

STUDY PERIOD: 10 YEARS, 0 MONTHS

SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

## CAPITAL ASSET COST DATA:

INITIAL COST (BASE YEAR \$)
EXPECTED ASSET LIFE (YRS/MTHS)

48993 10/0 0.00%

RESALE VALUE FACTOR NUMBER OF REPLACEMENTS

0

NO REPLACEMENTS

ومعرف أعاما ويماوي ويجوي

OPERATING, MAINTENANCE, AND REPAIR COST DATA:

-----

ANNUAL RECUR OM&R COST (\$): 3670

No non-annually-recurring OM&R costs reported.

## ENERGY-RELATED DATA:

\_\_\_\_\_\_

NUMBER OF ENERGY TYPES = 2

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA)

DOE rate schedule type: Industrial

Underlying gen. inflation rate used with DOE rates: 0.00%

TYPE 2 TYPE 1 Electricity Central Stea ENERGY TYPE: 246561 70000 BASE ANNUAL CONSUMPTION: Pound kWh UNITS: 0.008 0.020 PRICE PER UNIT (\$): 0.00 0.00 ANNUAL DEMAND CHARGE (\$): DOE rates DOE rates ESCALATION RATE METHOD: Electricity Natural Gas IF DOE ESC, ENERGY TYPE: 3.38 0.39 1995 1.98 0.24 1996 3.16 0.38 1997 4.11 1998 0.59 4.75 1999 1.24 5.03 2000 1.12 5.22 0.67 2001

2002	1.00	5.69
2003	1.09	4.99
2004	0.62	3.47
2005	0.00	0.00

De la companya di mandri d

Anna in

**BUILDING 3136** 

FILE NAME: 3136BASE

FILE LAST MODIFIED ON 08-16-1995/12:45:55

PROJECT ALTERNATIVE: BLDG3136BASE

COMMENT: (NONE)

# GENERAL DATA:

1

ANALYSIS TYPE: Federal Analysis -- Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995

STUDY PERIOD: 10 YEARS, 0 MONTHS

SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

# CAPITAL ASSET COST DATA:

INITIAL COST (BASE YEAR \$) 0
EXPECTED ASSET LIFE (YRS/MTHS) 10/0
RESALE VALUE FACTOR 0.00%
NUMBER OF REPLACEMENTS 0

NO REPLACEMENTS

OPERATING, MAINTENANCE, AND REPAIR COST DATA:

OFFICE TRANSPORTED TO THE PROPERTY OF THE PROP

ANNUAL RECUR OM&R COST (\$): 2345

No non-annually-recurring OM&R costs reported.

#### ENERGY-RELATED DATA:

\_\_\_\_\_

ารระทั่งสามพิษารู (ปฏิธีสุดสาราช 1951 ก.)

NUMBER OF ENERGY TYPES = 2

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA)

DOE rate schedule type: Industrial

Underlying gen. inflation rate used with DOE rates: 0.00%

ENERGY TYPE: BASE ANNUAL CONSUMPTION: UNITS: PRICE PER UNIT (\$): ANNUAL DEMAND CHARGE (\$): ESCALATION RATE METHOD: IF DOE ESC, ENERGY TYPE:	TYPE 1 Electricity 346101 kWh 0.020 456.00 DOE rates Electricity	433650 Pound 0.008 0.00 DOE rates
1995	0.39	3.38
1996	0.24	1.98
1997	0.38	3.16
1998	0.59	4.11
1999	1.24	4.75
2000	1.12	5.03
2001	0.67	5.22

2002	1.00	5.69
2003	1.09	4.99
2004	0.62	3.47
2005	0.00	0.00

*3850 - <mark>186</mark>0- (18*18)

\* \* NIST BLCC INPUT DATA LISTING (version 4.20-) \* \*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

FILE NAME: 3136-FMR

FILE LAST MODIFIED ON 08-16-1995/12:46:31

PROJECT ALTERNATIVE: BLDG3136-FMR

COMMENT: (NONE)

#### GENERAL DATA: \_\_\_\_\_

ANALYSIS TYPE: Federal Analysis--Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995

STUDY PERIOD: 10 YEARS, 0 MONTHS

SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

#### CAPITAL ASSET COST DATA: \_\_\_\_\_\_

INITIAL COST (BASE YEAR \$) 558 10/0 EXPECTED ASSET LIFE (YRS/MTHS) 0.00% RESALE VALUE FACTOR NUMBER OF REPLACEMENTS 0

NO REPLACEMENTS

ووؤفرا المداعر تعكورها

OPERATING, MAINTENANCE, AND REPAIR COST DATA: \_\_\_\_\_\_

ANNUAL RECUR OM&R COST (\$): 2345

No non-annually-recurring OM&R costs reported.

ENERGY-RELATED DATA:

\_\_\_\_\_\_

NUMBER OF ENERGY TYPES = 2

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA)

DOE rate schedule type: Industrial

Underlying gen. inflation rate used with DOE rates: 0.00%

·	TYPE 1	TYPE 2
ENERGY TYPE:	Electricity	Central Stea
BASE ANNUAL CONSUMPTION:	346101	433650
UNITS:	kWh	Pound
PRICE PER UNIT (\$):	0.020	0.008
ANNUAL DEMAND CHARGE (\$):	0.00	0.00
ESCALATION RATE METHOD:	DOE rates	DOE rates
IF DOE ESC, ENERGY TYPE:	Electricity	Natural Gas
1995	0.39	3.38
1996	0.24	1.98
1997	0.38	3.16
1998	0.59	4.11
1999	1.24	4.75
2000	1.12	5.03
2001	0.67	5.22

on <del>National Conservations and the conservation of the conservatio</del>

2002	1.00	5.69
2003	1.09	4.99
2004	0.62	3.47
2005	0.00	0.00

An a graph of

\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\* \* NIST BLCC INPUT DATA LISTING (version 4.20-) \* \*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

FILE NAME: 3136-PLC

FILE LAST MODIFIED ON 08-16-1995/12:47:37

PROJECT ALTERNATIVE: BLDG3136-PLC

COMMENT: (NONE)

#### GENERAL DATA:

ANALYSIS TYPE: Federal Analysis--Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995

STUDY PERIOD: 10 YEARS, 0 MONTHS

SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

#### CAPITAL ASSET COST DATA: \_\_\_\_\_\_

INITIAL COST (BASE YEAR \$) 10646 EXPECTED ASSET LIFE (YRS/MTHS) 10/0 0.00% RESALE VALUE FACTOR 0 NUMBER OF REPLACEMENTS

NO REPLACEMENTS

أأخيا مهيها ورابه بالأوابات

March 1885

หลายีโดยสัมพิธีเลีย หลังครับ มี และ เ

OPERATING, MAINTENANCE, AND REPAIR COST DATA:

\_\_\_\_\_ ANNUAL RECUR OM&R COST (\$): 2345

No non-annually-recurring OM&R costs reported.

#### ENERGY-RELATED DATA:

\_\_\_\_\_\_ NUMBER OF ENERGY TYPES = 2

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA)
DOE rate schedule type: Industrial

Underlying gen. inflation rate used with DOE rates: 0.00%

ENERGY TYPE: BASE ANNUAL CONSUMPTION: UNITS: PRICE PER UNIT (\$): ANNUAL DEMAND CHARGE (\$): ESCALATION RATE METHOD:	335997 kWh 0.020 456.00 DOE rates	
IF DOE ESC, ENERGY TYPE:	Electricity	Natural Gas
1995 1996 1997 1998 1999 2000 2001	0.39 0.24 0.38 0.59 1.24 1.12 0.67	3.38 1.98 3.16 4.11 4.75 5.03 5.22

\* \* NIST BLCC INPUT DATA LISTING (version 4.20-) \* \*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

FILE NAME: 3136-DDC

FILE LAST MODIFIED ON 08-16-1995/12:48:09

PROJECT ALTERNATIVE: BLDG3136-DDC

COMMENT: (NONE)

#### GENERAL DATA:

ANALYSIS TYPE: Federal Analysis -- Energy Conservation Projects

BASE DATE FOR LCC ANALYSIS: JAN 1995

STUDY PERIOD: 10 YEARS, 0 MONTHS

SERVICE DATE: JAN 1995

DISCOUNT AND INTEREST RATES ARE Real (exclusive of general inflation)

DISCOUNT RATE: 3.1%

Escalation rates do not include general inflation

# CAPITAL ASSET COST DATA:

\_\_\_\_\_\_ INITIAL COST (BASE YEAR \$) EXPECTED ASSET LIFE (YRS/MTHS) 0.00% RESALE VALUE FACTOR 0 NUMBER OF REPLACEMENTS

NO REPLACEMENTS

OPERATING, MAINTENANCE, AND REPAIR COST DATA:

\_\_\_\_\_

ANNUAL RECUR OM&R COST (\$): 1265

No non-annually-recurring OM&R costs reported.

#### ENERGY-RELATED DATA:

\_\_\_\_\_

NUMBER OF ENERGY TYPES = 2

And the second second

DOE energy price escalation rates filename: ENCOST94

DOE region (state code): 3 (VA)

DOE rate schedule type: Industrial

Underlying gen. inflation rate used with DOE rates: 0.00%

TVDF 1

TYPE 2

	TIED T	11111 21
ENERGY TYPE:	Electricity	Central Stea
BASE ANNUAL CONSUMPTION:	332211	228000
UNITS:	kWh	Pound
PRICE PER UNIT (\$):	0.020	0.008
ANNUAL DEMAND CHARGE (\$):	0.00	0.00
ESCALATION RATE METHOD:	DOE rates	DOE rates
IF DOE ESC, ENERGY TYPE:	Electricity	Natural Gas
1995	0.39	3.38
1996	0.24	1.98
1997	0.38	3.16
1998	0.59	4.11
1999	1.24	4.75
2000	1.12	5.03
2001	0.67	5.22

2002	1.00	5.69
2003	1.09	4.99
2004	0.62	3.47
2005	0.00	0.00

.

. galace bougt

E-44

# APPENDIX F BLCC 4.2 LIFE CYCLE COST ANALYSIS RESULTS

**BUILDING 200** 

# BLCC SUMMARY FOR BLDG200-BASE

		·
	PRESENT VALUE	ANNUAL VALUE
INITIAL COST (AS OF SERVICE DATE)	\$0	\$0
ANNUALLY RECURRING OM&R COSTS	\$72,096	\$8,495
ENERGY COSTS	\$335,417	\$39,522
LESS: REMAINING VALUE	( \$0)	( \$0)
TOTAL LCC	\$407,513	\$48,017

# BLCC SUMMARY FOR BLDG200-FMR

	PRESENT VALUE	ANNUAL VALUE	;	
INITIAL COST (AS OF SERVICE DATE)	\$1,000	\$118	i	
ANNUALLY RECURRING OM&R COSTS	\$72,096	\$8,495	i	
ENERGY COSTS	\$320,509	\$37,765	i i	
LESS: REMAINING VALUE	( \$0)	( \$0	)	
TOTAL LCC	\$393,604	\$46,378	r	

# BLCC SUMMARY FOR BLDG200-PLC

			<del>-</del>	
	PRESENT VALUE	ANN	JAL VALUE	
INITIAL COST (AS OF SERVICE DATE)	\$11,400		\$1,343	
ANNUALLY RECURRING OM&R COSTS	\$72,096	\$8,495		
ENERGY COSTS	\$275,815		\$32,499	
LESS: REMAINING VALUE	( \$0)	(	\$0)	
TOTAL LCC	\$359,311		\$42,337	

# BLCC SUMMARY FOR BLDG200-DDC

	PRESENT VALUE	ANNUAL VALUE
INITIAL COST (AS OF SERVICE DATE)	\$78,764	\$9,281
ANNUALLY RECURRING OM&R COSTS	\$24,909	\$2,935
ENERGY COSTS	\$226,660	\$26,707
LESS: REMAINING VALUE	( \$0)	( \$0)
TOTAL LCC	\$330,333	\$38,923

BASE CASE: BLDG200-BASE ALTERNATIVE: BLDG200-FMR

# PRINCIPAL STUDY PARAMETERS:

\_\_\_\_\_\_

ANALYSIS TYPE: Federal Analysis--Energy Conservation Projects STUDY PERIOD: 10.00 YEARS (JAN 1995 THROUGH DEC 2004) DISCOUNT RATE: 3.1% Real (exclusive of general inflation)

BASE CASE LCC FILE: 200-BASE.LCC ALTERNATIVE LCC FILE: 200-FMR.LCC

## COMPARISON OF PRESENT-VALUE COSTS

	BASE CASE: BLDG200-BASE	ALTERNATIVE: BLDG200-FMR	SAVINGS FROM ALT.
INITIAL INVESTMENT ITEM(S): CASH REQUIREMENTS AS OF SERVICE DATE	\$0	\$1,115	-\$1,115
SUBTOTAL FUTURE COST ITEMS:	\$0	\$1,115	-\$1,115
ANNUAL AND NON-AN. RECURRING COSTS ENERGY-RELATED COSTS	\$72,096 \$331,719	\$72,096 \$316,810	\$0 \$14,909
SUBTOTAL	\$403,814	\$388,906	\$14,909
TOTAL P.V. LIFE-CYCLE COST	\$403,814	\$390,021	\$13,794

NET SAVINGS FROM ALTERNATIVE BLDG200-FMR COMPARED TO ALTERNATIVE BLDG200-BASE

Net Savings	=	P.V. of non-investment savings	\$14,909
J	_	Increased total investment	\$1,115
		Net Savings:	\$13,794

Note: the SIR and AIRR computations include differential initial costs, capital replacement costs, and resale value (if any) as investment costs, per NIST Handbook 135 (Federal and MILCON analyses only).

SAVINGS-TO-INVESTMENT RATIO (SIR)
FOR ALTERNATIVE BLDG200-FMR COMPARED TO ALTERNATIVE BLDG200-BASE

P.V. of non-investment savings
SIR = ----- = 13.37
Increased total investment

F-6

# ADJUSTED INTERNAL RATE OF RETURN (AIRR) FOR ALTERNATIVE BLDG200-FMR COMPARED TO ALTERNATIVE BLDG200-BASE (Reinvestment rate = 3.10%; Study period = 10 years)

AIRR = 33.62%

## ESTIMATED YEARS TO PAYBACK

Simple Payback occurs in year 1 Discounted Payback occurs in year 1

## ENERGY SAVINGS SUMMARY

Energy	Units	<b></b> Annı	ual Consumption		Life-Cycle
type		Base Case	Alternative	Savings	Savings
Electricity	kWh	727,922	727,922	0	0
Natural Gas	Therm	29,904	29,904	0	0

Energy type	Annual Base Case	Emissions Alternative	Annual Reduction	Life-Cycle Reduction
Electricity:				
CO2 (Mg):	422.8	422.8	0.0	0.0
SOx (Kq):	3,552.7	3,552.7	0.0	0.0
NOx (Kg):	1,813.6	1,813.6	0.0	0.0
Natural Gas:				
CO2 (Mg):	157.9	157.9	0.0	0.0
SOx (Kq):	0.9	0.9	0.0	0.0
NOx (Kg):	119.6	119.6	0.0	0.0
Total:				
CO2 (Mg):	580.8	580.8	0.0	0.0
SOx (Kg):	3,553.6	3,553.6	0.0	0.0
NOx (Kg):	1,933.2	1,933.2	0.0	0.0

BASE CASE: BLDG200-BASE ALTERNATIVE: BLDG200-PLC

#### PRINCIPAL STUDY PARAMETERS:

\_\_\_\_\_\_

ANALYSIS TYPE: Federal Analysis--Energy Conservation Projects STUDY PERIOD: 10.00 YEARS (JAN 1995 THROUGH DEC 2004) DISCOUNT RATE: 3.1% Real (exclusive of general inflation)

BASE CASE LCC FILE: 200-BASE.LCC ALTERNATIVE LCC FILE: 200-PLC.LCC

#### COMPARISON OF PRESENT-VALUE COSTS

•	BASE CASE: BLDG200-BASE	ALTERNATIVE: BLDG200-PLC	SAVINGS FROM ALT.
INITIAL INVESTMENT ITEM(S):		410 811	610 711
CASH REQUIREMENTS AS OF SERVICE DATE	\$0 <b></b>	\$12,711 	-\$12,711 
SUBTOTAL	\$0	\$12,711	-\$12,711
FUTURE COST ITEMS: ANNUAL AND NON-AN. RECURRING COSTS	\$72,096	\$72,096	\$0
ENERGY-RELATED COSTS	\$331,719	\$272,118	\$59,601
SUBTOTAL	\$403,814	\$344,214	\$59,601
TOTAL P.V. LIFE-CYCLE COST	\$403,814	\$356,925	\$46,890

NET SAVINGS FROM ALTERNATIVE BLDG200-PLC COMPARED TO ALTERNATIVE BLDG200-BASE

Net Savings	=	P.V. of non-investment savings	\$59,601
_	-	Increased total investment	\$12,711
		-	
		Net Savings:	\$46,890

Note: the SIR and AIRR computations include differential initial costs, capital replacement costs, and resale value (if any) as investment costs, per NIST Handbook 135 (Federal and MILCON analyses only).

SAVINGS-TO-INVESTMENT RATIO (SIR)
FOR ALTERNATIVE BLDG200-PLC COMPARED TO ALTERNATIVE BLDG200-BASE

P.V. of non-investment savings
SIR = ----- = 4.69
Increased total investment

# ADJUSTED INTERNAL RATE OF RETURN (AIRR) FOR ALTERNATIVE BLDG200-PLC COMPARED TO ALTERNATIVE BLDG200-BASE (Reinvestment rate = 3.10%; Study period = 10 years)

AIRR = 20.33%

## ESTIMATED YEARS TO PAYBACK

Simple Payback occurs in year 3
Discounted Payback occurs in year 3

#### ENERGY SAVINGS SUMMARY

Energy	Units	Ann	Life-Cycle		
type		Base Case	Alternative	Savings	Savings
Electricity	kWh	727,922	666,966	60,956	609,560
Natural Gas	Therm	29,904	22,171	7,733	77,330

Energy type	Annual Base Case	Emissions Alternative	Annual Reduction	Life-Cycle Reduction
Electricity:				
CO2 (Mg):	422.8	387.4	35.4	354.1
SOx (Kg):	3,552.7	3,255.2	297.5	1,856.4
NOx (Kg):	1,813.6	1,661.7	151.9	1,518.7
Natural Gas:				
CO2 (Mg):	157.9	117.1	40.8	408.4
SOx (Kg):	0.9	0.7	0.2	0.0
NOx (Kg):	119.6	88.7	30.9	309.3
Total:				
CO2 (Mg):	580.8	504.5	76.2	762.5
SOx (Kq):	3,553.6	3,255.8	297.7	1,856.4
NOx (Kg):	1,933.2	1,750.4	182.8	1,828.0

BASE CASE: BLDG200-BASE ALTERNATIVE: BLDG200-DDC

### PRINCIPAL STUDY PARAMETERS:

\_\_\_\_\_

ANALYSIS TYPE: Federal Analysis--Energy Conservation Projects STUDY PERIOD: 10.00 YEARS (JAN 1995 THROUGH DEC 2004) DISCOUNT RATE: 3.1% Real (exclusive of general inflation)

BASE CASE LCC FILE: 200-BASE.LCC ALTERNATIVE LCC FILE: 200-DDC.LCC

#### COMPARISON OF PRESENT-VALUE COSTS

	BASE CASE: BLDG200-BASE	ALTERNATIVE: BLDG200-DDC	SAVINGS FROM ALT.
INITIAL INVESTMENT ITEM(S):			
CASH REQUIREMENTS AS OF SERVICE DATE	\$0	\$78,764	-\$78,764
SUBTOTAL	\$0	\$78,764	-\$78,764
FUTURE COST ITEMS:			
ANNUAL AND NON-AN. RECURRING COSTS	\$72,096	\$24,909	\$47,187
ENERGY-RELATED COSTS	\$331,719	\$226,660	\$105,059
SUBTOTAL	\$403,814	\$251,569	\$152,246
TOTAL P.V. LIFE-CYCLE COST	\$403,814	\$330,333	\$73,482

NET SAVINGS FROM ALTERNATIVE BLDG200-DDC COMPARED TO ALTERNATIVE BLDG200-BASE

Net Savings	=	P.V. of non-investment savings	\$152,246
	-	Increased total investment	\$78,764
		-	<del></del>
		Net Savings:	\$73,482

Note: the SIR and AIRR computations include differential initial costs, capital replacement costs, and resale value (if any) as investment costs, per NIST Handbook 135 (Federal and MILCON analyses only).

SAVINGS-TO-INVESTMENT RATIO (SIR)
FOR ALTERNATIVE BLDG200-DDC COMPARED TO ALTERNATIVE BLDG200-BASE

P.V. of non-investment savings
SIR = ----- = 1.93
Increased total investment

F-10

# ADJUSTED INTERNAL RATE OF RETURN (AIRR) FOR ALTERNATIVE BLDG200-DDC COMPARED TO ALTERNATIVE BLDG200-BASE (Reinvestment rate = 3.10%; Study period = 10 years)

AIRR = 10.12%

## ESTIMATED YEARS TO PAYBACK

Simple Payback occurs in year 5 Discounted Payback occurs in year 6

## ENERGY SAVINGS SUMMARY

Energy	Units	<b></b> Ann	ual Consumption	n	Life-Cycle
type		Base Case	Alternative	Savings	Savings
Electricity	kWh	727,922	628,377	99,545	995,450
Natural Gas	Therm	29,904	18,411	11,493	114,930

Energy .type	Annual ! Base Case	Emissions Alternative	Annual Reduction	Life-Cycle Reduction
Electricity:				
CO2 (Mg):	422.8	365.0	57.8	578.2
SOx (Kg):	3,552.7	3,066.8	485.8	3,031.6
NOx (Kg):	1,813.6	1,565.6	248.0	2,480.1
Natural Gas:				
CO2 (Mg):	157.9	97.2	60.7	606.9
SOx (Kg):	0.9	0.6	0.3	0.0
NOx (Kg):	119.6	73.6	46.0	459.7
Total:				
CO2 (Mg):	580.8	462.2	118.5	1,185.2
SOx (Kg):	3,553.6	3,067.4	486.2	3,031.6
NOx (Kg):	1,933.2	1,639.2	294.0	2,939.8

**BUILDING 219** 

## BLCC SUMMARY FOR BLDG219-BASE

	. <b></b>	
	PRESENT VALUE	ANNUAL VALUE
INITIAL COST (AS OF SERVICE DATE)	\$0	\$0
ANNUALLY RECURRING OM&R COSTS	\$51,685	\$6,090
ENERGY COSTS	\$331,859	\$39,103
LESS: REMAINING VALUE	( \$0)	(\$0)
TOTAL LCC	\$383,544	\$45,193

## BLCC SUMMARY FOR BLDG219-FMR

	<b></b>	
	PRESENT VALUE	ANNUAL VALUE
INITIAL COST (AS OF SERVICE DATE)	\$1,673	\$197
ANNUALLY RECURRING OM&R COSTS	\$51,685	\$6,090
ENERGY COSTS	\$316,880	\$37,338
LESS: REMAINING VALUE	( \$0)	( \$0)
TOTAL LCC	\$370,238	\$43,625

## BLCC SUMMARY FOR BLDG219-PLC

	PRESENT VALUE	ANNUAL VALUE	
INITIAL COST (AS OF SERVICE DATE)	\$12,516	\$1,475	
ANNUALLY RECURRING OM&R COSTS	\$51,685	\$6,090	
ENERGY COSTS	\$240,024	\$28,282	
LESS: REMAINING VALUE	( \$0)	( \$0)	
TOTAL LCC	\$304,225	\$35,847	

## BLCC SUMMARY FOR BLDG219-DDC

	PRESENT VALUE	ANNUAL VALUE
INITIAL COST (AS OF SERVICE DATE)	\$72,141	\$8,500
ANNUALLY RECURRING OM&R COSTS	\$20,199	\$2,380
ENERGY COSTS	\$216,827	\$25,549
LESS: REMAINING VALUE	( \$0)	( \$0)
TOTAL LCC	\$309,167	\$36,429

BASE CASE: BLDG219-BASE ALTERNATIVE: BLDG219-FMR

## PRINCIPAL STUDY PARAMETERS:

\_\_\_\_\_\_

ANALYSIS TYPE: Federal Analysis--Energy Conservation Projects STUDY PERIOD: 10.00 YEARS (JAN 1995 THROUGH DEC 2004) DISCOUNT RATE: 3.1% Real (exclusive of general inflation)

BASE CASE LCC FILE: 219-BASE.LCC ALTERNATIVE LCC FILE: 219-FMR.LCC

### COMPARISON OF PRESENT-VALUE COSTS

	BASE CASE: BLDG219-BASE	ALTERNATIVE: BLDG219-FMR	SAVINGS FROM ALT.
INITIAL INVESTMENT ITEM(S):			
CASH REQUIREMENTS AS OF SERVICE DATE	\$0	\$1,673	-\$1,673
		41 672	d1 672
SUBTOTAL	\$0	\$1,673	-\$1,673
FUTURE COST ITEMS:			
ANNUAL AND NON-AN. RECURRING COSTS	\$51,685	\$51,685	\$0
ENERGY-RELATED COSTS	\$331,859	\$316,880	\$14,979
SUBTOTAL	\$383,544	\$368,565	\$14,979
TOTAL P.V. LIFE-CYCLE COST	\$383,544	\$370,238	\$13,306

NET SAVINGS FROM ALTERNATIVE BLDG219-FMR COMPARED TO ALTERNATIVE BLDG219-BASE

Net Sav	ings =	P.V. of	non-inv	estment	savings	\$ \$14,979
	_	Increase	d total	invest	nent	\$1,673
				Net Sav	ings:	\$13,306

Note: the SIR and AIRR computations include differential initial costs, capital replacement costs, and resale value (if any) as investment costs, per NIST Handbook 135 (Federal and MILCON analyses only).

SAVINGS-TO-INVESTMENT RATIO (SIR)
FOR ALTERNATIVE BLDG219-FMR COMPARED TO ALTERNATIVE BLDG219-BASE

P.V. of non-investment savings
SIR = ----- = 8.95
Increased total investment

# ADJUSTED INTERNAL RATE OF RETURN (AIRR) FOR ALTERNATIVE BLDG219-FMR COMPARED TO ALTERNATIVE BLDG219-BASE (Reinvestment rate = 3.10%; Study period = 10 years)

AIRR = 28.37%

## ESTIMATED YEARS TO PAYBACK

Simple Payback occurs in year 1 Discounted Payback occurs in year 2

#### ENERGY SAVINGS SUMMARY

Energy	Units	Anni	ual Consumption	1	Life-Cycle
type		Base Case	Alternative	Savings	Savings
Electricity	kWh	903,608	903,608	0	0
Natural Gas	Therm	25,043	25,043	0	0

Energy type		Emissions Alternative	Annual Reduction	Life-Cycle Reduction
Electricity:				
CO2 (Mg):	524.9	524.9	0.0	0.0
SOx (Kg):	4,410.1	4,410.1	0.0	0.0
NOx (Kg):	2,251.3	2,251.3	0.0	0.0
Natural Gas:				
CO2 (Mg):	132.3	132.3	0.0	0.0
SOx (Kg):	0.8	0.8	0.0	0.0
NOx (Kg):	100.2	100.2	0.0	0.0
Total:				
CO2 (Mg):	657.1	657.1	0.0	0.0
SOx (Kg):	4,410.9	4,410.9	0.0	0.0
NOx (Kg):	2,351.5	2,351.5	0.0	0.0

BASE CASE: BLDG219-BASE ALTERNATIVE: BLDG219-PLC

## PRINCIPAL STUDY PARAMETERS:

\_\_\_\_\_\_

ANALYSIS TYPE: Federal Analysis--Energy Conservation Projects STUDY PERIOD: 10.00 YEARS (JAN 1995 THROUGH DEC 2004) DISCOUNT RATE: 3.1% Real (exclusive of general inflation)

BASE CASE LCC FILE: 219-BASE.LCC ALTERNATIVE LCC FILE: 219-PLC.LCC

#### COMPARISON OF PRESENT-VALUE COSTS

	BASE CASE: BLDG219-BASE	ALTERNATIVE: BLDG219-PLC	SAVINGS FROM ALT.
INITIAL INVESTMENT ITEM(S): CASH REQUIREMENTS AS OF SERVICE DATE	\$0	\$12,516	-\$12,516
CASH REQUIREMENTS AS OF SERVICE DATE			
SUBTOTAL	\$0	\$12,516	-\$12,516
FUTURE COST ITEMS:			
ANNUAL AND NON-AN. RECURRING COSTS	\$51,685	\$51,685	\$0
ENERGY-RELATED COSTS	\$331,859	\$240,024	\$91,836
SUBTOTAL	\$383,544	\$291,709	\$91,836
SUBTUTAL	7505,544	7251,705	
TOTAL P.V. LIFE-CYCLE COST	\$383,544	\$304,225	\$79,320

NET SAVINGS FROM ALTERNATIVE BLDG219-PLC COMPARED TO ALTERNATIVE BLDG219-BASE

Net Savings	=	P.V. of non-investment savings	\$91,836
_	-	Increased total investment	\$12,516
		Net Savings:	\$79,320

Note: the SIR and AIRR computations include differential initial costs, capital replacement costs, and resale value (if any) as investment costs, per NIST Handbook 135 (Federal and MILCON analyses only).

SAVINGS-TO-INVESTMENT RATIO (SIR)
FOR ALTERNATIVE BLDG219-PLC COMPARED TO ALTERNATIVE BLDG219-BASE

P.V. of non-investment savings
SIR = ----- = 7.34
Increased total investment

# ADJUSTED INTERNAL RATE OF RETURN (AIRR) FOR ALTERNATIVE BLDG219-PLC COMPARED TO ALTERNATIVE BLDG219-BASE (Reinvestment rate = 3.10%; Study period = 10 years)

AIRR = 25.84%

## ESTIMATED YEARS TO PAYBACK

Simple Payback occurs in year 2 Discounted Payback occurs in year 2

## ENERGY SAVINGS SUMMARY

Energy	Units	Annı	ual Consumption	1	Life-Cycle
type		Base Case	Alternative	Savings	Savings
Electricity	kWh	903,608	696,551	207,057	2,070,570
Natural Gas	Therm	25,043	16,265	8,778	87,780

Energy type	Annual Base Case	Emissions Alternative	Annual Reduction	Life-Cycle Reduction
Electricity:				
CO2 (Mg):	524.9	404.6	120.3	1,202.8
SOx (Kg):	4,410.1	3,399.5	1,010.6	6,305.8
NOx (Kg):	2,251.3	1,735.4	515.9	5,158.8
Natural Gas:				
CO2 (Mg):	132.3	85.9	46.4	463.6
SOx (Kg):	0.8	0.5	0.3	0.0
NOx (Kg):	100.2	65.1	35.1	351.1
Total:				
CO2 (Mg):	657.1	490.5	166.6	1,666.3
SOx (Kg):	4,410.9	3,400.0	1,010.8	6,305.8
NOx (Kg):	2,351.5	1,800.5	551.0	5,509.9

BASE CASE: BLDG219-BASE ALTERNATIVE: BLDG219-DDC

# PRINCIPAL STUDY PARAMETERS:

-----

ANALYSIS TYPE: Federal Analysis--Energy Conservation Projects STUDY PERIOD: 10.00 YEARS (JAN 1995 THROUGH DEC 2004) DISCOUNT RATE: 3.1% Real (exclusive of general inflation)

BASE CASE LCC FILE: 219-BASE.LCC ALTERNATIVE LCC FILE: 219-DDC.LCC

### COMPARISON OF PRESENT-VALUE COSTS

	BASE CASE: BLDG219-BASE	ALTERNATIVE: BLDG219-DDC	SAVINGS FROM ALT.
INITIAL INVESTMENT ITEM(S): CASH REQUIREMENTS AS OF SERVICE DATE	\$0	\$72,141	-\$72,141
SUBTOTAL FUTURE COST ITEMS:	\$0	\$72,141	-\$72,141
ANNUAL AND NON-AN. RECURRING COSTS ENERGY-RELATED COSTS	\$51,685 \$331,859	\$20,199 \$216,827	\$31,486 \$115,032
SUBTOTAL	\$383,544	\$237,026	\$146,518
TOTAL P.V. LIFE-CYCLE COST	\$383,544	\$309,167	\$74,377

NET SAVINGS FROM ALTERNATIVE BLDG219-DDC COMPARED TO ALTERNATIVE BLDG219-BASE

Net Savings	=	P.V. of non-investme	nt savings	\$146,518
-		Increased total inve		\$72,141
		Net	Savings:	\$74,377

Note: the SIR and AIRR computations include differential initial costs, capital replacement costs, and resale value (if any) as investment costs, per NIST Handbook 135 (Federal and MILCON analyses only).

SAVINGS-TO-INVESTMENT RATIO (SIR)
FOR ALTERNATIVE BLDG219-DDC COMPARED TO ALTERNATIVE BLDG219-BASE

P.V. of non-investment savings
SIR = ----- = 2.03
Increased total investment

# ADJUSTED INTERNAL RATE OF RETURN (AIRR) FOR ALTERNATIVE BLDG219-DDC COMPARED TO ALTERNATIVE BLDG219-BASE (Reinvestment rate = 3.10%; Study period = 10 years)

AIRR = 10.67%

## ESTIMATED YEARS TO PAYBACK

Simple Payback occurs in year 5 Discounted Payback occurs in year 5

### ENERGY SAVINGS SUMMARY

Energy	Units	Anni	ual Consumption	a	Life-Cycle
type		Base Case	Alternative	Savings	Savings
Electricity	kWh	903,608	677,647	225,961	2,259,610
Natural Gas	Therm	25,043	15,490	9,553	95,530

Energy type	Annual Base Case	Emissions Alternative	Annual Reduction	Life-Cycle Reduction
Electricity:				
CO2 (Mg):	524.9	393.6	131.3	1,312.6
SOx (Kg):	4,410.1	3,307.3	1,102.8	6,881.6
NOx (Kg):	2,251.3	1,688.3	563.0	5,629.7
Natural Gas:				
CO2 (Mg):	132.3	81.8	50.4	504.5
SOx (Kg):	0.8	0.5	0.3	0.0
NOx (Kg):	100.2	62.0	38.2	382.1
Total:				
CO2 (Mg):	657.1	475.4	181.7	1,817.1
SOx (Kg):	4,410.9	3,307.8	1,103.1	6,881.6
NOx (Kg):	2,351.5	1,750.3	601.2	6,011.9

**BUILDING 247** 

## BLCC SUMMARY FOR BLDG247-BASE

	PRESENT VALUE	ANNUAL VALUE
INITIAL COST (AS OF SERVICE DATE)	\$0	\$0
ANNUALLY RECURRING OM&R COSTS	\$125,733	\$14,815
ENERGY COSTS	\$639,123	\$75,308
LESS: REMAINING VALUE	( \$0)	( \$0)
	\$764,855	\$90,123
TOTAL LCC	4/04/000	γ20, ±43

## BLCC SUMMARY FOR BLDG247-FMR

	PRESENT VALUE	ANNUAL VALUE	
INITIAL COST (AS OF SERVICE DATE)	\$558	\$66	
ANNUALLY RECURRING OM&R COSTS	\$125,733	\$14,815	
ENERGY COSTS	\$612,199	\$72,135	
LESS: REMAINING VALUE	( \$0)	( \$0)	
TOTAL LCC	\$738,489	\$87,016	

## BLCC SUMMARY FOR BLDG247-PLC

	PRESENT VALUE	ANNUAL VALUE	
INITIAL COST (AS OF SERVICE DATE)	\$14,914	\$1,757	
ANNUALLY RECURRING OM&R COSTS	\$125,733	\$14,815	
ENERGY COSTS	\$530,820	\$62,546	
LESS: REMAINING VALUE	( \$0)	( \$0)	
TOTAL LCC	\$671,467	\$79,119	

## BLCC SUMMARY FOR BLDG247-DDC

	PRESENT VALUE	ANNUAL VALUE
INITIAL COST (AS OF SERVICE DATE)	\$87,416	\$10,300
ANNUALLY RECURRING OM&R COSTS	\$106,213	\$12,515
ENERGY COSTS	\$491,759	\$57,944
LESS: REMAINING VALUE	( \$0)	( \$0)
TOTAL LCC	\$685,388	\$80,759

BASE CASE: BLDG247-BASE ALTERNATIVE: BLDG247-FMR

### PRINCIPAL STUDY PARAMETERS:

\_\_\_\_\_\_

ANALYSIS TYPE: Federal Analysis--Energy Conservation Projects STUDY PERIOD: 10.00 YEARS (JAN 1995 THROUGH DEC 2004) DISCOUNT RATE: 3.1% Real (exclusive of general inflation)

BASE CASE LCC FILE: 247-BASE.LCC ALTERNATIVE LCC FILE: 247-FMR.LCC

#### COMPARISON OF PRESENT-VALUE COSTS

	BASE CASE: BLDG247-BASE	ALTERNATIVE: BLDG247-FMR	SAVINGS FROM ALT.
INITIAL INVESTMENT ITEM(S): CASH REQUIREMENTS AS OF SERVICE DATE	\$0	\$558	-\$558
SUBTOTAL	\$0	\$558	-\$558
FUTURE COST ITEMS:			
ANNUAL AND NON-AN. RECURRING COSTS	\$125,733	\$125,733	\$0
ENERGY-RELATED COSTS	\$639,123	\$612,199	\$26,923
	\$764,855	\$737,932	\$26,923
SUBTOTAL	\$/04,655	ψ/37,932	720,723
TOTAL P.V. LIFE-CYCLE COST	\$764,855	\$738,489	\$26,366

NET SAVINGS FROM ALTERNATIVE BLDG247-FMR COMPARED TO ALTERNATIVE BLDG247-BASE

Net Savings	=	P.V. of non-investment savings	\$26,923
_	-	Increased total investment	\$558
		Net Savings:	\$26,366

Note: the SIR and AIRR computations include differential initial costs, capital replacement costs, and resale value (if any) as investment costs, per NIST Handbook 135 (Federal and MILCON analyses only).

SAVINGS-TO-INVESTMENT RATIO (SIR)
FOR ALTERNATIVE BLDG247-FMR COMPARED TO ALTERNATIVE BLDG247-BASE

P.V. of non-investment savings
SIR = ----- = 48.29
Increased total investment

# ADJUSTED INTERNAL RATE OF RETURN (AIRR) FOR ALTERNATIVE BLDG247-FMR COMPARED TO ALTERNATIVE BLDG247-BASE (Reinvestment rate = 3.10%; Study period = 10 years)

AIRR = 51.93%

### ESTIMATED YEARS TO PAYBACK

Simple Payback occurs in year 1 Discounted Payback occurs in year 1

#### ENERGY SAVINGS SUMMARY

Energy	Units	Ann	ual Consumptio	n	Life-Cycle
type		Base Case	Alternative	Savings	Savings
Electricity	kWh	2,045,422	2,045,422	0	0
Natural Gas	Therm	40,071	40,071	0	0

Energy type	Annual Base Case	Emissions Alternative	Annual Reduction	Life-Cycle Reduction
Electricity:				
CO2 (Mg):	1,188.2	1,188.2	0.0	0.0
SOx (Kg):	9,982.8	9,982.8	0.0	0.0
NOx (Kg):	5,096.1	5,096.1	0.0	0.0
Natural Gas:				
CO2 (Mg):	211.6	211.6	0.0	0.0
SOx (Kq):	1.2	1.2	0.0	0.0
NOx (Kg):	160.3	160.3	0.0	0.0
Total:				
CO2 (Mg):	1,399.8	1,399.8	0.0	0.0
SOx (Kg):	9,984.0	9,984.0	0.0	0.0
NOx (Kg):	5,256.4	5,256.4	0.0	0.0

BASE CASE: BLDG247-BASE ALTERNATIVE: BLDG247-PLC

## PRINCIPAL STUDY PARAMETERS:

\_\_\_\_\_\_

ANALYSIS TYPE: Federal Analysis--Energy Conservation Projects STUDY PERIOD: 10.00 YEARS (JAN 1995 THROUGH DEC 2004) DISCOUNT RATE: 3.1% Real (exclusive of general inflation)

BASE CASE LCC FILE: 247-BASE.LCC ALTERNATIVE LCC FILE: 247-PLC.LCC

### COMPARISON OF PRESENT-VALUE COSTS

	BASE CASE: BLDG247-BASE	ALTERNATIVE: BLDG247-PLC	SAVINGS FROM ALT.
INITIAL INVESTMENT ITEM(S):			
CASH REQUIREMENTS AS OF SERVICE DATE	\$0	\$14,914	-\$14,914
SUBTOTAL	\$0	\$14,914	-\$14,914
FUTURE COST ITEMS:			
ANNUAL AND NON-AN. RECURRING COSTS	\$125,733	\$125,733	\$0
ENERGY-RELATED COSTS	\$639,123	\$530,820	\$108,303
SUBTOTAL	\$764,855	\$656,553	\$108,303
TOTAL P.V. LIFE-CYCLE COST	\$764,855	\$671,467	\$93,389

NET SAVINGS FROM ALTERNATIVE BLDG247-PLC COMPARED TO ALTERNATIVE BLDG247-BASE

Net Savings	=	P.V. of non-investment savings	\$108,303
	-	Increased total investment	\$14,914
		Net Savings:	\$93,389

Note: the SIR and AIRR computations include differential initial costs, capital replacement costs, and resale value (if any) as investment costs, per NIST Handbook 135 (Federal and MILCON analyses only).

SAVINGS-TO-INVESTMENT RATIO (SIR)
FOR ALTERNATIVE BLDG247-PLC COMPARED TO ALTERNATIVE BLDG247-BASE

P.V. of non-investment savings
SIR = ----- = 7.26
Increased total investment

# ADJUSTED INTERNAL RATE OF RETURN (AIRR) FOR ALTERNATIVE BLDG247-PLC COMPARED TO ALTERNATIVE BLDG247-BASE (Reinvestment rate = 3.10%; Study period = 10 years)

AIRR = 25.71%

## ESTIMATED YEARS TO PAYBACK

Simple Payback occurs in year 2 Discounted Payback occurs in year 2

## ENERGY SAVINGS SUMMARY

Energy	Units	Annı	ual Consumption	ı	Life-Cycle
type		Base Case	Alternative	Savings	Savings
Electricity	kWh	2,045,422	1,850,207	195,215	1,952,150
Natural Gas	Therm	40,071	28,361	11,710	117,100

Energy type	Annual Base Case	Emissions Alternative	Annual Reduction	Life-Cycle Reduction
Electricity:				
CO2 (Mg):	1,188.2	1,074.8	113.4	1,134.0
SOx (Kq):	9,982.8	9,030.0	952.8	5,945.2
NOx (Kg):	5,096.1	4,609.7	486.4	4,863.7
Natural Gas:				
CO2 (Mg):	211.6	149.8	61.8	618.4
SOx (Kg):	1.2	0.9	0.4	0.0
NOx (Kg):	160.3	113.4	46.8	468.4
Total:				
CO2 (Mg):	1,399.8	1,224.5	175.2	1,752.4
SOx (Kq):	9,984.0	9,030.9	953.1	5,945.2
NOx (Kg):	5,256.4	4,723.2	533.2	5,332.1

BASE CASE: BLDG247-BASE ALTERNATIVE: BLDG247-DDC

## PRINCIPAL STUDY PARAMETERS:

\_\_\_\_\_

ANALYSIS TYPE: Federal Analysis--Energy Conservation Projects STUDY PERIOD: 10.00 YEARS (JAN 1995 THROUGH DEC 2004) DISCOUNT RATE: 3.1% Real (exclusive of general inflation)

BASE CASE LCC FILE: 247-BASE.LCC ALTERNATIVE LCC FILE: 247-DDC.LCC

#### COMPARISON OF PRESENT-VALUE COSTS

	BASE CASE: BLDG247-BASE	ALTERNATIVE: BLDG247-DDC	SAVINGS FROM ALT.
INITIAL INVESTMENT ITEM(S):			
CASH REQUIREMENTS AS OF SERVICE DATE	\$0	\$87,416	-\$87,416
SUBTOTAL	\$0	\$87,416	-\$87,416
FUTURE COST ITEMS:			
ANNUAL AND NON-AN. RECURRING COSTS	\$125,733	\$106,213	\$19,520
ENERGY-RELATED COSTS	\$639,123	\$491,759	\$147,363
SUBTOTAL	\$764,855	\$597,972	\$166,883
TOTAL P.V. LIFE-CYCLE COST	\$764,855	\$685,388	\$79,467

NET SAVINGS FROM ALTERNATIVE BLDG247-DDC COMPARED TO ALTERNATIVE BLDG247-BASE

Note: the SIR and AIRR computations include differential initial costs, capital replacement costs, and resale value (if any) as investment costs, per NIST Handbook 135 (Federal and MILCON analyses only).

SAVINGS-TO-INVESTMENT RATIO (SIR)
FOR ALTERNATIVE BLDG247-DDC COMPARED TO ALTERNATIVE BLDG247-BASE

P.V. of non-investment savings
SIR = ----- = 1.91
Increased total investment

# ADJUSTED INTERNAL RATE OF RETURN (AIRR) FOR ALTERNATIVE BLDG247-DDC COMPARED TO ALTERNATIVE BLDG247-BASE (Reinvestment rate = 3.10%; Study period = 10 years)

AIRR = 9.99%

### ESTIMATED YEARS TO PAYBACK

Simple Payback occurs in year 5 Discounted Payback occurs in year 6

### ENERGY SAVINGS SUMMARY

Energy	Units	Anni	ual Consumption	n	Life-Cycle
type		Base Case	Alternative	Savings	Savings
Electricity	kWh	2,045,422	1,827,236	218,186	2,181,860
Natural Gas	Therm	40,071	27,079	12,992	129,920

Energy type	Annual Base Case	Emissions Alternative	Annual Reduction	Life-Cycle Reduction
Electricity:				
CO2 (Mg):	1,188.2	1,061.4	126.7	1,267.4
SOx (Kg):	9,982.8	8,917.9	1,064.9	6,644.8
NOx (Kg):	5,096.1	4,552.5	543.6	5,436.0
Natural Gas:				
CO2 (Mg):	211.6	143.0	68.6	686.1
SOx (Kg):	1.2	0.8	0.4	0.0
NOx (Kg):	160.3	108.3	52.0	519.7
Total:				
CO2 (Mg):	1,399.8	1,204.4	195.4	1,953.5
SOx (Kg):	9,984.0	8,918.7	1,065.3	6,644.8
NOx (Kg):	5,256.4	4,660.8	595.6	5,955.7

**BUILDING 1425** 

# BLCC SUMMARY FOR BLDG1425BASE

		- <b></b> -		
	PRESENT VALUE	ANN	UAL VALUE	
INITIAL COST (AS OF SERVICE DATE)	\$0		\$0	
ANNUALLY RECURRING OMER COSTS	\$41,840		\$4,930	
ENERGY COSTS	\$71,752		\$8,455	
LESS: REMAINING VALUE	( \$0)	(	\$0)	
			<b></b>	
TOTAL LCC	\$113,592	•	\$13,385	

## BLCC SUMMARY FOR BLDG1425-FMR

	PRESENT VALUE	ANNUAL VALUE	
INITIAL COST (AS OF SERVICE DATE)	\$558	, \$66	
ANNUALLY RECURRING OM&R COSTS	\$41,840	\$4,930	
ENERGY COSTS	\$67,753	\$7,983	
LESS: REMAINING VALUE	( \$0)	( \$0)	
TOTAL LCC	\$110,151	\$12,979	

## BLCC SUMMARY FOR BLDG1425-PLC

	PRESENT VALUE	ANNUAL VALUE	
INITIAL COST (AS OF SERVICE DATE)	\$11,518	\$1,357	
ANNUALLY RECURRING OM&R COSTS	\$41,840	\$4,930	
ENERGY COSTS	\$53,859	\$6,346	
LESS: REMAINING VALUE	( \$0)	( \$0)	
TOTAL LCC	\$107,21 <b>7</b>	\$12,633	

## BLCC SUMMARY FOR BLDG1425-DDC

				-
	PRESENT VALUE	ANN	UAL VALUE	
INITIAL COST (AS OF SERVICE DATE)	\$48,993		\$5,773	
ANNUALLY RECURRING OM&R COSTS	\$31,147		\$3,670	
ENERGY COSTS	\$49,072		\$5,782	
LESS: REMAINING VALUE	( \$0)	(	\$0)	
				•
TOTAL LCC	\$129,211		\$15,225	

BASE CASE: BLDG1425BASE ALTERNATIVE: BLDG1425-FMR

### PRINCIPAL STUDY PARAMETERS:

\_\_\_\_\_\_

ANALYSIS TYPE: Federal Analysis--Energy Conservation Projects STUDY PERIOD: 10.00 YEARS (JAN 1995 THROUGH DEC 2004) DISCOUNT RATE: 3.1% Real (exclusive of general inflation)

BASE CASE LCC FILE: 1425BASE.LCC ALTERNATIVE LCC FILE: 1425-FMS.LCC

### COMPARISON OF PRESENT-VALUE COSTS

	BASE CASE: BLDG1425BASE	ALTERNATIVE: BLDG1425-FMR	SAVINGS FROM ALT.
INITIAL INVESTMENT ITEM(S):			
CASH REQUIREMENTS AS OF SERVICE DATE	\$0	\$558	-\$558
SUBTOTAL	\$0	\$558	-\$558
FUTURE COST ITEMS:			
ANNUAL AND NON-AN. RECURRING COSTS	\$41,840	\$41,840	\$0
ENERGY-RELATED COSTS	\$71,752	\$67,753	\$3,999
SUBTOTAL	\$113,592	\$109,593	\$3,999
TOTAL P.V. LIFE-CYCLE COST	\$113,592	\$110,151	\$3,442

NET SAVINGS FROM ALTERNATIVE BLDG1425-FMR COMPARED TO ALTERNATIVE BLDG1425BASE

Note: the SIR and AIRR computations include differential initial costs, capital replacement costs, and resale value (if any) as investment costs, per NIST Handbook 135 (Federal and MILCON analyses only).

SAVINGS-TO-INVESTMENT RATIO (SIR)
FOR ALTERNATIVE BLDG1425-FMR COMPARED TO ALTERNATIVE BLDG1425BASE

P.V. of non-investment savings
SIR = ----- = 7.17
Increased total investment

# ADJUSTED INTERNAL RATE OF RETURN (AIRR) FOR ALTERNATIVE BLDG1425-FMR COMPARED TO ALTERNATIVE BLDG1425BASE (Reinvestment rate = 3.10%; Study period = 10 years)

AIRR = 25.55%

## ESTIMATED YEARS TO PAYBACK

Simple Payback occurs in year 2 Discounted Payback occurs in year 2

#### ENERGY SAVINGS SUMMARY

Energy	Units	Annual Consumption			Life-Cycle	
type		Base Case	Alternative	Savings	Savings	
Electricity	kWh	265,769	265,769	0	. 0	
Central Steam	Pound	254,000	254,000	0	0	

Energy type		Emissions Alternative	Annual Reduction	Life-Cycle Reduction
Electricity:				
CO2 (Mg):	154.4	154.4	0.0	0.0
SOx (Kg):	1,297.1	1,297.1	0.0	0.0
NOx (Kg):	662.2	662.2	0.0	0.0
Central Steam:				
CO2 (Kg):	0.0	0.0	0.0	0.0
SOx (Kg):	0.0	0.0	0.0	0.0
NOx (Kg):	0.0	0.0	0.0	0.0
Total:				
CO2 (Mg):	154.4	154.4	0.0	0.0
SOx (Kg):	1,297.1	1,297.1	0.0	0.0
NOx (Kg):	662.2	662.2	0.0	0.0

BASE CASE: BLDG1425BASE ALTERNATIVE: BLDG1425-PLC

## PRINCIPAL STUDY PARAMETERS:

\_\_\_\_\_

ANALYSIS TYPE: Federal Analysis--Energy Conservation Projects STUDY PERIOD: 10.00 YEARS (JAN 1995 THROUGH DEC 2004) DISCOUNT RATE: 3.1% Real (exclusive of general inflation)

BASE CASE LCC FILE: 1425BASE.LCC ALTERNATIVE LCC FILE: 1425-PLC.LCC

#### COMPARISON OF PRESENT-VALUE COSTS

	BASE CASE: BLDG1425BASE	ALTERNATIVE: BLDG1425-PLC	SAVINGS FROM ALT.
INITIAL INVESTMENT ITEM(S):			
CASH REQUIREMENTS AS OF SERVICE DATE	\$0	\$11,518	-\$11,518
SUBTOTAL	\$0	\$11,518	-\$11,518
FUTURE COST ITEMS:			
ANNUAL AND NON-AN. RECURRING COSTS	\$41,840	\$41,840	\$0
ENERGY-RELATED COSTS	\$71,752	\$53,859	\$17,893
SUBTOTAL	\$113,592	\$95,699	\$17,893
TOTAL P.V. LIFE-CYCLE COST	\$113,592	\$107,217	\$6,375

NET SAVINGS FROM ALTERNATIVE BLDG1425-PLC COMPARED TO ALTERNATIVE BLDG1425BASE

Net Savings	=	P.V. of non-investment saving	s \$17,893
•	-	Increased total investment	\$11,518
		Net Savings:	\$6,375

Note: the SIR and AIRR computations include differential initial costs, capital replacement costs, and resale value (if any) as investment costs, per NIST Handbook 135 (Federal and MILCON analyses only).

SAVINGS-TO-INVESTMENT RATIO (SIR)
FOR ALTERNATIVE BLDG1425-PLC COMPARED TO ALTERNATIVE BLDG1425BASE

P.V. of non-investment savings
SIR = ----- = 1.55
Increased total investment

# ADJUSTED INTERNAL RATE OF RETURN (AIRR) FOR ALTERNATIVE BLDG1425-PLC COMPARED TO ALTERNATIVE BLDG1425BASE (Reinvestment rate = 3.10%; Study period = 10 years)

AIRR = 7.74%

#### ESTIMATED YEARS TO PAYBACK

Simple Payback occurs in year 6 Discounted Payback occurs in year 7

#### ENERGY SAVINGS SUMMARY

Energy	Units	Ann	ual Consumption	n	Life-Cycle
type		Base Case	Alternative	Savings	Savings
Electricity	kWh	265,769	249,395	16,374	163,740
Central Steam	Pound	254,000	73,500	180,500	1,805,000

#### EMISSIONS REDUCTION SUMMARY

Energy type		Emissions Alternative	Annual Reduction	Life-Cycle Reduction
Electricity:				
CO2 (Mg):	154.4	144.9	9.5	95.1
SOx (Kq):	1,297.1	1,217.2	79.9	498.7
NOx (Kg):	662.2	621.4	40.8	408.0
Central Steam:				
CO2 (Kg):	0.0	0.0	0.0	0.0
SOx (Kq):	0.0	0.0	0.0	0.0
NOx (Kg):	0.0	0.0	0.0	0.0
Total:				
CO2 (Mg):	154.4	144.9	9.5	95.1
SOx (Kq):	1,297.1	1,217.2	79.9	498.7
NOx (Kg):	662.2	621.4	40.8	408.0

NIST BLCC: COMPARATIVE ECONOMIC ANALYSIS (version 4.20-95)

BASE CASE: BLDG1425BASE ALTERNATIVE: BLDG1425-DDC

#### PRINCIPAL STUDY PARAMETERS:

\_\_\_\_\_\_

ANALYSIS TYPE: Federal Analysis--Energy Conservation Projects STUDY PERIOD: 10.00 YEARS (JAN 1995 THROUGH DEC 2004) DISCOUNT RATE: 3.1% Real (exclusive of general inflation)

BASE CASE LCC FILE: 1425BASE.LCC ALTERNATIVE LCC FILE: 1425-DDC.LCC

#### COMPARISON OF PRESENT-VALUE COSTS

·	BASE CASE: BLDG1425BASE	ALTERNATIVE: BLDG1425-DDC	SAVINGS FROM ALT.
INITIAL INVESTMENT ITEM(S): CASH REQUIREMENTS AS OF SERVICE DATE	\$0	\$48,993	-\$48,993
SUBTOTAL FUTURE COST ITEMS:	\$0	\$48,993	-\$48,993
ANNUAL AND NON-AN. RECURRING COSTS	\$41,840	\$31,147	\$10,693
ENERGY-RELATED COSTS	\$71,752	\$49,072	\$22,681
SUBTOTAL	\$113,592	\$80,218	\$33,374
TOTAL P.V. LIFE-CYCLE COST	\$113,592	\$129,211	-\$15,619

NET SAVINGS FROM ALTERNATIVE BLDG1425-DDC COMPARED TO ALTERNATIVE BLDG1425BASE

Net Savings	=	P.V. of non-investment savings	\$33,374
3		Increased total investment	\$48,993
		Net Savings:	-\$15,619

Note: the SIR and AIRR computations include differential initial costs, capital replacement costs, and resale value (if any) as investment costs, per NIST Handbook 135 (Federal and MILCON analyses only).

SAVINGS-TO-INVESTMENT RATIO (SIR)
FOR ALTERNATIVE BLDG1425-DDC COMPARED TO ALTERNATIVE BLDG1425BASE

P.V. of non-investment savings
SIR = ----- = 0.68
Increased total investment

# ADJUSTED INTERNAL RATE OF RETURN (AIRR) FOR ALTERNATIVE BLDG1425-DDC COMPARED TO ALTERNATIVE BLDG1425BASE (Reinvestment rate = 3.10%; Study period = 10 years)

AIRR = -0.78%

#### ESTIMATED YEARS TO PAYBACK

Simple Payback never reached during study period Discounted Payback never reached during study period

#### ENERGY SAVINGS SUMMARY

Energy	Units	Annı	ual Consumption	ı	Life-Cycle
type		Base Case	Alternative	Savings	Savings
Electricity	kWh	265,769	246,561	19,208	192,080
Central Steam	Pound	254,000	70,000	184,000	1,840,000

#### EMISSIONS REDUCTION SUMMARY

Energ typ	<b>-</b>		Emissions Alternative	Annual Reduction	Life-Cycle Reduction
	<b></b>				
Elect	ricity:				
CO2	(Mg):	154.4	143.2	11.2	111.6
sox	(Kg):	1,297.1	1,203.4	93.7	585.0
NOx	(Kg):	662.2	614.3	47.9	478.6
Centra	al Steam:				
CO2	(Kg):	0.0	0.0	0.0	0.0
sox	(Kg):	0.0	0.0	0.0	0.0
NOx	(Kg):	0.0	0.0	0.0	0.0
Total	:				
CO2	(Mg):	154.4	143.2	11.2	111.6
sox	(Kg):	1,297.1	1,203.4	93.7	585.0
NOx	(Kg):	662.2	614.3	47.9	478.6

#### BLCC SUMMARY FOR BLDG3136BASE

	PRESENT VALUE	ANNUAL VALUE	
INITIAL COST (AS OF SERVICE DATE)	\$0	\$0	
ANNUALLY RECURRING OM&R COSTS	\$19,902 ·	\$2,345	
ENERGY COSTS	\$100,793	\$11,876	
LESS: REMAINING VALUE	( \$0)	( \$0)	
TOTAL LCC	\$120,694	\$14,221	

#### BLCC SUMMARY FOR BLDG3136-FMR

	·	
	PRESENT VALUE	ANNUAL VALUE
INITIAL COST (AS OF SERVICE DATE)	\$558	\$66
ANNUALLY RECURRING OM&R COSTS	\$19,902	\$2,345
ENERGY COSTS	\$96,794	\$11,405
LESS: REMAINING VALUE	( \$0)	( \$0)
TOTAL LCC	\$117,253	\$13,816

#### BLCC SUMMARY FOR BLDG3136-PLC

			•
	PRESENT VALUE	ANNUAL VALUE	
INITIAL COST (AS OF SERVICE DATE)	\$10,646	\$1,254	
ANNUALLY RECURRING OM&R COSTS	\$19,902	\$2,345	
ENERGY COSTS	\$82,855	\$9,763	
LESS: REMAINING VALUE	( \$0)	( \$0)	
TOTAL LCC	\$113,403	\$13,362	

#### BLCC SUMMARY FOR BLDG3136-DDC

			-
	PRESENT VALUE	ANNUAL VALUE	
INITIAL COST (AS OF SERVICE DATE)	\$48,614	\$5,728	
ANNUALLY RECURRING OM&R COSTS	\$10,736	\$1,265	
ENERGY COSTS	\$77,243	\$9,102	
LESS: REMAINING VALUE	( \$0)	( \$0)	
			-
TOTAL LCC	\$136,593	\$16,095	

NIST BLCC: COMPARATIVE ECONOMIC ANALYSIS (version 4.20-95)

BASE CASE: BLDG3136BASE ALTERNATIVE: BLDG3136-FMR

#### PRINCIPAL STUDY PARAMETERS:

\_\_\_\_\_\_

ANALYSIS TYPE: Federal Analysis--Energy Conservation Projects STUDY PERIOD: 10.00 YEARS (JAN 1995 THROUGH DEC 2004) DISCOUNT RATE: 3.1% Real (exclusive of general inflation)

BASE CASE LCC FILE: 3136BASE.LCC ALTERNATIVE LCC FILE: 3136-FMR.LCC

#### COMPARISON OF PRESENT-VALUE COSTS

	BASE CASE: BLDG3136BASE	ALTERNATIVE: BLDG3136-FMR	SAVINGS FROM ALT.
INITIAL INVESTMENT ITEM(S):			
CASH REQUIREMENTS AS OF SERVICE DATE	\$0	\$558	-\$558
SUBTOTAL	\$0	\$558	-\$558
FUTURE COST ITEMS:			
ANNUAL AND NON-AN. RECURRING COSTS	\$19,902	\$19,902	\$0
ENERGY-RELATED COSTS	\$100,793	\$96,794	\$3,999
SUBTOTAL	\$120,694	\$116,695	\$3,999
TOTAL P.V. LIFE-CYCLE COST	\$120,694	\$117,253	\$3,442

NET SAVINGS FROM ALTERNATIVE BLDG3136-FMR COMPARED TO ALTERNATIVE BLDG3136BASE

Note: the SIR and AIRR computations include differential initial costs, capital replacement costs, and resale value (if any) as investment costs, per NIST Handbook 135 (Federal and MILCON analyses only).

SAVINGS-TO-INVESTMENT RATIO (SIR)
FOR ALTERNATIVE BLDG3136-FMR COMPARED TO ALTERNATIVE BLDG3136BASE

P.V. of non-investment savings
SIR = ----- = 7.17
Increased total investment

# ADJUSTED INTERNAL RATE OF RETURN (AIRR) FOR ALTERNATIVE BLDG3136-FMR COMPARED TO ALTERNATIVE BLDG3136BASE (Reinvestment rate = 3.10%; Study period = 10 years)

AIRR = 25.55%

#### ESTIMATED YEARS TO PAYBACK

Simple Payback occurs in year 2 Discounted Payback occurs in year 2

#### ENERGY SAVINGS SUMMARY

Energy	Units	Ann	ual Consumption	n	Life-Cycle
type		Base Case	Alternative	Savings	Savings
Electricity	kWh	346,101	346,101	0	0
Central Steam	Pound	433,650	433,650	0	0

#### EMISSIONS REDUCTION SUMMARY

Energy type		Emissions Alternative	Annual Reduction	Life-Cycle Reduction
Electricity:	•			
CO2 (Mg):	201.0	201.0	0.0	0.0
SOx (Kq):	1,689.2	1,689.2	0.0	0.0
NOx (Kq):	862.3	862.3	0.0	0.0
Central Steam:				
CO2 (Kg):	0.0	0.0	0.0	0.0
SOx (Kg):	0.0	0.0	0.0	0.0
NOx (Kg):	0.0	0.0	0.0	0.0
Total:				
CO2 (Mg):	201.0	201.0	0.0	0.0
SOx (Kq):	1,689.2	1,689.2	. 0.0	0.0
NOx (Kg):	862.3	862.3	0.0	0.0

NIST BLCC: COMPARATIVE ECONOMIC ANALYSIS (version 4.20-95)

BASE CASE: BLDG3136BASE ALTERNATIVE: BLDG3136-PLC

#### PRINCIPAL STUDY PARAMETERS:

\_\_\_\_\_\_

ANALYSIS TYPE: Federal Analysis--Energy Conservation Projects STUDY PERIOD: 10.00 YEARS (JAN 1995 THROUGH DEC 2004) DISCOUNT RATE: 3.1% Real (exclusive of general inflation)

BASE CASE LCC FILE: 3136BASE.LCC ALTERNATIVE LCC FILE: 3136-PLC.LCC

#### COMPARISON OF PRESENT-VALUE COSTS

	BASE CASE: BLDG3136BASE	ALTERNATIVE: BLDG3136-PLC	SAVINGS FROM ALT.
INITIAL INVESTMENT ITEM(S):			
CASH REQUIREMENTS AS OF SERVICE DATE	\$0	\$10,646	-\$10,646
SUBTOTAL	\$0	\$10,646	-\$10,646
FUTURE COST ITEMS:			
ANNUAL AND NON-AN. RECURRING COSTS	\$19,902	\$19,902	\$0
ENERGY-RELATED COSTS	\$100,793	\$82,855	\$17,938
SUBTOTAL	\$120,694	\$102,757	\$17,938
TOTAL P.V. LIFE-CYCLE COST	\$120,694	\$113,403	\$7,292

NET SAVINGS FROM ALTERNATIVE BLDG3136-PLC COMPARED TO ALTERNATIVE BLDG3136BASE

Net Saving	gs =	P.V. of	non-inve	estment	savings	\$17,938
	_	Increase	ed total	invest	ment	\$10,646
				Net Sav	rings:	\$7,292

Note: the SIR and AIRR computations include differential initial costs, capital replacement costs, and resale value (if any) as investment costs, per NIST Handbook 135 (Federal and MILCON analyses only).

SAVINGS-TO-INVESTMENT RATIO (SIR)
FOR ALTERNATIVE BLDG3136-PLC COMPARED TO ALTERNATIVE BLDG3136BASE

P.V. of non-investment savings
SIR = ----- = 1.68
Increased total investment

F-52

# ADJUSTED INTERNAL RATE OF RETURN (AIRR) FOR ALTERNATIVE BLDG3136-PLC COMPARED TO ALTERNATIVE BLDG3136BASE (Reinvestment rate = 3.10%; Study period = 10 years)

AIRR = 8.62%

#### ESTIMATED YEARS TO PAYBACK

Simple Payback occurs in year 6
Discounted Payback occurs in year 7

#### ENERGY SAVINGS SUMMARY

Energy	Units	Ann	ual Consumption	1	Life-Cycle
type		Base Case	Alternative	Savings	Savings
Electricity	kWh	346,101	335,997	10,104	101,040
Central Steam	Pound	433,650	239,400	194,250	1,942,500

#### EMISSIONS REDUCTION SUMMARY

Energy type	Annual Base Case	Emissions Alternative	Annual Reduction	Life-Cycle Reduction
Electricity:				
CO2 (Mg):	201.0	195.2	5.9	58.7
SOx (Kg):	1,689.2	1,639.8	49.3	307.7
NOx (Kg):	862.3	837.1	25.2	251.7
Central Steam:				
CO2 (Kg):	0.0	0.0	0.0	0.0
SOx (Kg):	0.0	0.0	0.0	0.0
NOx (Kg):	0.0	0.0	0.0	0.0
Total:				
CO2 (Mg):	201.0	195.2	5.9	58.7
SOx (Kg):	1,689.2	1,639.8	49.3	307.7
NOx (Kg):	862.3	837.1	25.2	251.7

NIST BLCC: COMPARATIVE ECONOMIC ANALYSIS (version 4.20-95)

BASE CASE: BLDG3136BASE ALTERNATIVE: BLDG3136-DDC

#### PRINCIPAL STUDY PARAMETERS:

\_\_\_\_\_\_

ANALYSIS TYPE: Federal Analysis--Energy Conservation Projects STUDY PERIOD: 10.00 YEARS (JAN 1995 THROUGH DEC 2004) DISCOUNT RATE: 3.1% Real (exclusive of general inflation)

BASE CASE LCC FILE: 3136BASE.LCC ALTERNATIVE LCC FILE: 3136-DDC.LCC

#### COMPARISON OF PRESENT-VALUE COSTS

	BASE CASE: BLDG3136BASE	ALTERNATIVE: BLDG3136-DDC	SAVINGS FROM ALT.
INITIAL INVESTMENT ITEM(S):			
CASH REQUIREMENTS AS OF SERVICE DATE	\$0	\$48,614	-\$48,614
SUBTOTAL	\$0	\$48,614	-\$48,614
FUTURE COST ITEMS:			
ANNUAL AND NON-AN. RECURRING COSTS	\$19,902	\$10,736	\$9,166
ENERGY-RELATED COSTS	\$100,793	\$77,243	\$23,550
SUBTOTAL	\$120,694	\$87,979	\$32,715
TOTAL P.V. LIFE-CYCLE COST	\$120,694	\$136,593	-\$15,899

NET SAVINGS FROM ALTERNATIVE BLDG3136-DDC COMPARED TO ALTERNATIVE BLDG3136BASE

Net Savings = P.V. of non-investment savings \$32,715 - Increased total investment \$48,614 Net Savings: -\$15,899

Note: the SIR and AIRR computations include differential initial costs, capital replacement costs, and resale value (if any) as investment costs, per NIST Handbook 135 (Federal and MILCON analyses only).

SAVINGS-TO-INVESTMENT RATIO (SIR)
FOR ALTERNATIVE BLDG3136-DDC COMPARED TO ALTERNATIVE BLDG3136BASE

P.V. of non-investment savings
SIR = ----- = 0.67
Increased total investment

## ADJUSTED INTERNAL RATE OF RETURN (AIRR) FOR ALTERNATIVE BLDG3136-DDC COMPARED TO ALTERNATIVE BLDG3136BASE (Reinvestment rate = 3.10%; Study period = 10 years)

AIRR = -0.90%

#### ESTIMATED YEARS TO PAYBACK

Simple Payback never reached during study period Discounted Payback never reached during study period

#### ENERGY SAVINGS SUMMARY

Energy	Units	Annı	ual Consumption		Life-Cycle
type		Base Case	Alternative	Savings	Savings
Electricity	kWh	346,101	332,211	13,890	138,900
Central Steam	Pound	433,650	228,000	205,650	2,056,500

#### EMISSIONS REDUCTION SUMMARY

Energy type	•	Emissions Alternative	Annual Reduction	Life-Cycle Reduction
Electricity:				
CO2 (Mg):	201.0	193.0	8.1	80.7
SOx (Kq):	1,689.2	1,621.4	67.8	423.0
NOx (Kg):	862.3	827.7	34.6	346.1
Central Steam:				
CO2 (Kg):	0.0	0.0	0.0	0.0
SOx (Kg):	0.0	0.0	0.0	0.0
NOx (Kg):	0.0	0.0	0.0	0.0
Total:				
CO2 (Mg):	201.0	193.0	8.1	80.7
SOx (Kq):	1,689.2	1,621.4	67.8	423.0
NOx (Kg):	862.3	827.7	34.6	346.1

# APPENDIX G COST DATA

## PRICING FOR FMR

			Design 5.5%	•	SIOH 6.0%		Total Cost
BUILDING 200	2  POINTS  x \$500 = \$1,000	+	\$55	+	\$60	=	\$1115
BUILDING 219	$3 \text{ POINTS } \times \$500 = \$1,500$	+	\$82.5	+	\$90	=	\$1673
BUILDING 247	1  POINT x  \$500 = \$500	+	\$27.5	+	\$30	=	\$557.5
BUILDING 1425	1  POINT  x \$500 = \$500	+	\$27.5	+	\$30	=	\$557.5
BUILDING 3136	1  POINT  x \$500 = \$500	+	\$27.5	+	\$30	=	\$557.5

#### PRICING FOR PLC

#### **BUILDING 200**

Advanced Control Technologies

**TMS** 

\$12,500 \$10,300

 $22,800 \div 2 = 11,400 \text{ Average}$ 

\$627 (Design 5.5%) \$684 (SIOH 6.0%)

\$12,711 Total

#### **BUILDING 219**

Advanced Control Technologies

TMS

\$11,500 \$10,950

 $\$22,450 \div 2 = \$11,225 \text{ Average}$ 

\$617 (Design 5.5%)

\$674 (SIOH 6.0%)

\$12,516 Total

#### **BUILDING 247**

Advanced Control Technologies

**TMS** 

\$13,000 \$13,750

 $$26750 \div 2 = $13,375 \text{ Average}$ 

\$736 (Design 5.5%) \$803 (SIOH 6.0%)

\$14,914 Total

#### **BUILDING 1425**

Advanced Control Technologies

**TMS** 

\$10,400 \$10,260

 $\frac{1}{20,660} \div 2 = 10,330 \text{ Average}$ 

\$568 (Design 5.5%) \$620 (SIOH 6.0%)

\$11,518 Total

#### **BUILDING 3136**

Advanced Control Technologies

**TMS** 

\$9,100

<u>\$9,995</u>

 $$19,095 \div 2 = $9,548 \text{ Average}$ 

\$525 (Design)

<u>\$573</u> (SIOH)

\$10,646 Total

### Ft. Belvoir EMS Study EMS Cost Estimate - Advanced Control Technologies

BUILDING 200	25 POINTS x \$500	\$12,500
BUILDING 219	23 POINTS x \$500	\$11,500
BUILDING 247	36 POINTS x \$500	\$13,000
BUILDING 1425	16 POINTS x \$500	\$10,400
BUILDING 3136	14 POINTS x \$500	\$9,100



### POWER DYNAMICS CORPORATION

LARGO PARK SUITE 152
1300 MERCANTILE LANE LANDOVER, MD 20785
(301) 773-0500 FAX (301) 380-2040

January 13, 1995

Mr. Dave Smith Einhorn, Yaffee, Prescott The Flour Mill 1000 Potomac Street, NW Washington, DC 20007-3238

Re: Fort Belvoir, Virginia Energy Management Study

WY BACK-

Dear Mr. Smith:

Thank you for your recent interest in our products and services. Please find enclosed a general proposal overview that can be used for each of the five (5) buildings. We have also enclosed budgeting for each building based on the information you provided us.

Please review and respond with any questions you may have. We hope all the information provided will be of benefit. We have represented the TMS/Facilitec Equipment for over seven (7) years and have been in the EMS business since 1976.

Regards,

Donald G. Bacon

DGB/slp Enclosure(s)



#### POWER DYNAMICS CORPORATION

LARGU PAKK SUITE 152 1300 MERCANTILE LANE LANDOVER, MD 20785 (301) 773-0500 FAX (301) 386-2646

January 13, 1995

TO: Mr. Dave Smith

Einhorn, Yaffee, Prescott

RE: Fort Belvoir, Virginia / EMS Study Proposal Overview

The following is a description of what each building proposal will include.

- A. One (1) TMS 500 programmable stand alone DDC controller with LCD screen display, PC Type keyboard, flash ram back-up card and telephone communication 9600 Baud Data Modom.
- B. X # of RTU-1000 Unitary Input/Output point controllers. Each RTU has six (6) point capability.
- C. Connection of the RTU-1000 Digital outputs to the carrier current command module (supplied by others) input terminals. <u>Note</u>: Pricing is based on wire to carrier current device located within 20 feet of the RTU 1000 mounting location and being in the same physical room.
- D. Programming of the TMS 500 for scheduled control of the DDC outputs to the carrier current device.
- E. One (1) year full labor and parts warranty on all equipment provided by PDC from start-up.
- F. Initial check-out, system start-up and training for all PDC supplied equipment.

#### Notes:

- 1. All needed dedicated phone line(s) for remote communications to be provided by others.
- 2. All pricing shown is for budgeting purposes only, and is based on information provided and similar type application history. We will provide concise pricing per request, and only after individual building walk-through.



## POWER DYNAMICS CORPORATION

LARCO PARK SUITE 152 1300 MERCANTILE LANE LANDOVER, MU 20785 (301) 773-0500 FAX (301) 386-2646

January 13, 1995

TO: Mr. David Smith

Einhorn, Yaffee, Prescott

RE: Fort Belvoir, Virginia / EMS Study

Individual Building Budgeting

1. Building 200

\$ 10.300.00

Three (3) RTU -1000's Seventeen (17) points

2. Building 219

\$ 10.950.00

Four (4) RTU-1000's Twenty-three (23) points

3. Building 247

\$ 13,740.00

Seven (7) RTU-1000's Thirty-eight (38) points

4. Building 1425

3 10,260.00

Three (3) RTU - 1000's Sixteen (16) points

5. Building (No #)

\$ 9,995.00

Three (3) RTU - 1000's Fourteen (14) points

#### Notes:

- All buildings looked at separately regarding carrier current.
- 2. Each building will have basic programmable control.
- 3. We have combined four (4) fan coil units to one (1) point.
- 4. Fach building has separate control capabilities via provided TMS-500.
- 5. More detail, building by building, provided per request.
- 6. If all buildings are done at once, please allow 4 to 6% discount for budgeting purposes.
- 7. Utility usage reduction / savings analysis available per request.
- 8. All information provided for budgeting purposes only.

#### PRICING FOR DDC

**BUILDING 200** 

 Johnson Controls
 \$60,000

 Honeyewell
 \$89,600

 Andover
 \$62,320

 $$211,920 \div 3 = $70,640 \text{ Average}$ 

\$3,885 (Design 5.5%) \$4,238 (SIOH 6.0%)

\$78,76# Total

**BUILDING 219** 

 Johnson Controls
 \$64,000

 Honeywell
 \$65,400

 Andover
 \$113,980\*

 $129,400 \div 2 = 64,700 \text{ Average}$ 

\$3,559 (Design 5.5%) \$3,882 (SIOH 6.0%)

\$72,141Total

**BUILDING 247** 

 Johnson Controls
 \$79,800

 Honeywell
 \$77,000

 Andover
 \$329,940\*

 $$156,800 \div 2 = $78,400 \text{ Average}$ 

\$4,312 (Design 5.5%) \$4,704 (SIOH 6.0%)

\$87,416 Total

**BUILDING 1425** 

 Johnson Controls
 \$48,280

 Honeywell
 \$39,600

 Andover
 \$99,200\*

 $\$87,880 \div 2 = \$43,940 \text{ Average}$ 

\$2,417 (Design 5.5%) \$2,636 (SIOH 6.0%)

\$48,993 Total

**BUILDING 3136** 

 Johnson Controls
 \$46,100

 Honeywell
 \$34,700

 Andover
 \$50,000

 $$130,800 \div 3 = $43,600 \text{ Average}$ 

\$2,398 (Design 5.5%) \$2,616 (SIOH 6.0%)

\$48,614 Total

<sup>\*</sup> value not used in averaging because of excessive disparity from other values

# ESTIMATED ANNUAL MAINTENANCE COSTS FOR EXISTING PNEUMATIC SYSTEMS

#### **BUILDING 200**

	<u>Material</u>	<u>Labor</u>	
3 - Constant Volume Single Zone AHUs	\$1,500	\$1,560	
2 - Constant Volume Multi-Zone AHUs	\$1,300	\$1,560	
1 - 100% Outside AHU	\$200	\$260	
1 - Chiller	\$200	\$260	
5 - Pumps	\$250	\$325	
1 - ATC Compressor	\$200	\$520	
1 - Refrigerated Air Dryer	<u>\$100</u>	<u>\$260</u>	
	\$3,750 +	\$4,745 = <b>\$8,4</b>	95 Total

#### **BUILDING 219**

	<u>Material</u>		<u>Labor</u>
1 - Constant Volume Single Zone AHU	\$500		\$520
2 - Constant Volume Built-Up AHU	\$700		\$1,040
1 - Hot Water Convertor	\$300		\$520
1 - Change-Over System	\$100		\$65
3 - Pumps	\$150		\$195
2 - Chillers	\$400		\$520
1 - ATC Compressor	\$200		\$520
1 - Refrigerated Air Dryer	\$100		<u>\$260</u>
	\$2,450	+	\$3,640 = <b>\$6,090 Total</b>

1 - Built-Up Penthouse AHUs       \$500       \$1,040         20-Constant Volume AHUs       \$5,000       \$5,200         1 - Centrifugal Chiller and Tower       \$700       \$260         9 - Pumps       \$450       \$585	
20-Constant Volume AHUs \$5,000 \$5,200 1 - Centrifugal Chiller and Tower \$700 \$260	
ALSO ASOS	
Φ.4.7.0 Φ.7.0.7.	
9 - Pumps \$450 \$585	
1 - ATC Compressor \$200 \$520	
1 - Refrigerated Air Dryer \$100 \$260	
\$6,950 + \$7,865 = <b>\$14,815</b>	Total

#### **BUILDING 1425**

711 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1			
	<u>Material</u>	<u>Labor</u>	
52-Fan Coil Units	\$780	\$1,690	
1 - Hot Water Convertor	\$150	\$260	
1 - Chiller	\$200	\$260	
1 - Changer-Over System	\$100	\$65	
3 - Pumps	\$150	\$195	
1 - ATC Compressor	\$200	\$520	
1 - Refrigerated Air Dryer	<u>\$100</u>	<u>\$260</u>	
Ç ,	\$1,680 +	- \$3,250 = \$	4,930 Total

	<u>Material</u>	<u>Labor</u>	
1 - Hot Water Convertor	\$150	\$260	
1 - Chiller	\$200	\$260	
1 - Changer-Over System	\$100	\$65	
2 - Pumps	\$100	\$130	
1 - ATC Compressor	\$200	\$520	
1 - Refrigerated Air Dryer	<u>\$100</u>	<u>\$260</u>	
	\$850	+ \$1,495 = \$2,3	345 Total

# ESTIMATED ANNUAL MAINTENANCE COSTS FOR NEW DDC SYSTEMS

#### **BUILDING 200**

		_
	<u>Material</u>	<u>Labor</u>
3 - Constant Volume Single Zone AHUs	\$300	\$780
2 - Constant Volume Multi-Zone AHUs	\$300	\$520
1 - 100% Outside AHU	\$100	\$130
1 - Chiller	\$100	\$130
5 - Pumps	<u>\$250</u>	<u>\$325</u>
•	\$1.050 +	\$1,885 = \$2,935  Total

#### **BUILDING 219**

	<u>Material</u>	<u>Labor</u>
1 - Constant Volume Single Zone AHU	\$100	\$260
2 - Constant Volume Built-Up AHU	\$200	\$390
1 - Hot Water Convertor	\$300	\$390
1 - Change-Over System	\$100	\$65
3 - Pumps	\$150	\$195
2 - Chillers	<b>\$100</b>	<u>\$130</u>
	\$950	\$1,430 = \$2,380  Total

	<u>Material</u>	<u>Labor</u>
1 - Built-Up Penthouse AHUs	\$300	\$520
20-Constant Volume AHUs	\$5,000	\$5,200
1 - Centrifugal Chiller and Tower	\$200	\$260
9 - Pumps	<u>\$450</u>	<u>\$585</u>
•	\$5,950 +	\$6,565 = \$12,515  Total

#### **BUILDING 1425**

	<u>Material</u>	<u>Labor</u>
52-Fan Coil Units	\$780	\$1,690
1 - Hot Water Convertor	\$150	\$260
1 - Chiller	\$150	\$130
1 - Changer-Over System	\$100	\$65
3 - Pumps	<u>\$150</u>	<u>\$195</u>
•	\$1,330 +	\$2,340 = \$3,670  Total

	<u>Iviaici iai</u>	Lauul	
1 - Hot Water Convertor	\$150	\$260	
1 - Chiller	\$200	\$260	
1 - Changer-Over System	\$100	\$65	
2 - Pumps	<u>\$100</u>	<u>\$130</u>	
•	\$550	+ \$715 = 3	\$1,265 Total

Johnson Controls, Inc. Systems and Services Division 5740 General Washington Drive Post Office Box 11248 Alexandria, VA 22312 Tel. 703/750 3250



**EYP** 

Attn: Mr. Dave Smith 1000 Potomac St. L1 NW Washington, DC 20007

December 17, 1993

Ref: Fort Belvoir Building Automation

Dear Dave:

This letter is in reference to the pricing information that you requested for buildings 200, 219, 247, 1425 and 3136 at Fort Belvoir.

After our site visit on 12/10/93, Julio and I created the following unit pricing scenario to assist you in writing your final study for the Baltimore Corp. of Engineers. The pricing was broken out by systems which were surveyed along with the necessary components to connect each building into one network. The pricing breakouts are as follows:

<u>System</u>	<u>Price</u>
Boiler Control	\$ 4,600.00
Chiller Control	\$ 5,200.00
Air Handling Unit	\$ 5,900.00

#### Additional Components

Network Control Unit (1 slot)	\$10,000.00
Ethernet Router	\$ 6,000.00
Operator Workstation	\$25,000.00

Please refer to the attached point schedules to see the system points.

Please feel free to contact me at any time with any questions that you may have pertaining to this project.

Sincerely,

Johnson Controls, Inc.

Thomas J. George Account Manager

G-12

Air States Name: AHU Control  It inchaste  Air States  Air States  Air States  Supply Air Temperature  States Air Temperature  States Air Temperature  Air Temperature  Air Temperature  Air States  Outdoor Air Temperature  Air T		Johnson Controls METASYS Fa	Facilities Mar	es	Ma	E	ment	ent	Sys	ster	n P	oin	System Point Schedule	hec	lule	(2)		
Point Description   Poin	•		tem	Lype	: AI		ontr	oller			Da	te: 1	2/17	/93				
Noting the conference of the control	1		Hard	vare		Ont	put Fe	atures			Softwa	ire Fe	tures	1	1			
ARIU StartStop ARIU StartStop ARIU StartStop ARIU StartStop ARIU StartStop ARIU StartStop ARIU StartStop ARIU StartStort ARIGOR ARIU ARIU Temperature ARIGOR ARIU ARIU Temperature ARIGOR ARIU ARIU Temperature ARIGOR ARIU ARIU ARIU ARIU ARIU ARIU ARIU ARI	Point Number		luqul goisnA	łuqłuO golanA						Pneumatic Output	Time Scheduling	Point Graphic	(erd 62) YootsiH golanA	Binary History (10 Changes of State)	PID Loop Control	string letoT		Comments:
Act   Same   Supply At   Temperature	1 -	AHII Start/Stop	1	$\vdash$	ľ	╁╾		L	×	Γ	×	×	-	×	$\vdash$	Н		
Supply Air Temperature	4 4		<del> -</del>		┝	H						×	Н	×		$\Box$		
Return Air Temperature	1 60		×	┝	_							×	×	-	$\dashv$	$\dashv$		
Miced Aid Temperature	4	Return Air Temperature	×	_								×	×	-	-	$\dashv$		
Outdoor Air Temperature  Substance Air Temperature  Outdoor Air Temperature  Outdoor Air Temperature  Outdoor Air Temperature  Outdoor Air Temperature  Outdoor Air Temperature  Outdoor Air Demperature  Outdoor Air Tempera	1 4	Mixed Air Temperature	×	H								×	×		-	$\dashv$		
Outdoor Air Damper Control  Childed Water Valve Control  Hot Water Valv	1 9	Outdoor Air Temperature	×	_								×	×	-	-	-		
Note   Water Valve Control	10	Outdoor Air Damper Control		×						7		×	×		_	$\dashv$		
Hot Water Valve Control  Hot Water Valve Contr	1 00	Chilled Water Valve Control		×	_							×	×	-	×	$\dashv$		
Number of Points 14 2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	10	Hot Water Valve Control		×						·		×	×		_	$\dashv$		
Number of Points 4 3 1 1 1	10			$\vdash$								7	1	$\dashv$	$\dashv$	-		
Number of Points 4 3 1 1 1	i = ]		-	$\dashv$	$\dashv$	-	4					1	1	+	$\dashv$	+	1	
Number of Points 4 3 1 1	7		+	-	-	_	_			T	T	1	+	$\dashv$	+	+	_	
Number of Points 4 3 1 1 1	3		1	$\dashv$	-	-	_						$\dashv$	+	+	+	_	
Number of Points 4 3 1 1 1	4			$\dashv$	$\dashv$	$\dashv$	-				7		$\dashv$	+	$\dashv$	+		
Number of Points 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 40				-	_	_							1	$\dashv$	$\dashv$	_	
Number of Points  4 3 1 1 1	1 9				_										_	$\dashv$		
Number of Points 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	10			-	-	_												
Number of Points 4 3 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 00		-	-	_	_	_	_										
Number of Points 4 3 1 1 1	10			_	_	L	_	_							_			
Number of Points 4 3 1 1 1	1 0		<del> </del>	$\vdash$	_	L	_											
Number of Points 4 3 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 -			-	-	_	_	L										
Number of Points 4 3 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 4				_	_												
Number of Points 4 3 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 (2)			$\vdash$	-	_	_							-				
Number of Points 4 3 1 1 1	1 4			-	-	_	_	_						-	_			
Number of Points  4 3 1 1 1	1 0			_	_	_	_				Γ							
Number of Points 4 3 1 1 1	19			-		_												
Number of Points 4 3 1 1 1	15			-		_											-	
Number of Points 4 3 1 1 1	1 00														-	$\dashv$		
Number of Points 4 3 1 1 1	I 🌣															-		
Number of Points 4 3 1 1	18												$\dashv$	-	-	$\dashv$		
Number of Points 4 3 1 1	1 2			-	-	_					1		$\dashv$	-	$\dashv$	$\dashv$		
4 3 1 1	32			$\dashv$	$\dashv$	4	_					1	1	$\dashv$	┪	+	4	
		Number of Points	4	3							٦	٦	1	┪	$\dashv$	$\ddot{\parallel}$		

٤

			Comments:																																
			sinio¶ fatoT								-							П			7			$\dashv$	_	1	7	7	1	7			$\forall$	1	<b>®</b>
ונ							٦											$\exists$			7		$\dashv$	1		1	$\forall$	7	$\dashv$	1			$\dashv$	1	
nne	33		PID Loop Control	_		×	×	×	×												7	_	7	1	7	1	7	1	+	7	7	7	$\forall$	1	┪
חשור ארוובחחוב	Date: 12/17/93		Binary History (10 Changes of State)	×	×					×	×						_	Н			7			1	7	┪	$\exists$	7	$\dashv$	7	_	7	7	1	1
נו	:: 12	atures	(214 h2) yroteiH golanA			×	×	×	×												1		7		┪	$\exists$			7	1	1	1	┪	1	┪
	Date	re Fe	Point Graphic	×	×	×	×	×	×	×	×							$\Box$		1	1	_	1		7			1	1	1	1	1	寸		ᅦ
11 A		Software Features	Time Scheduling	×						×		$\dashv$						H			7		1		1	7			1	$\dashv$	1	7	十	1	1
CHICALL DYSICAN			Pneumatic Output																		٦		┪			1			1	+		1	寸	1	┪
J,	<u>.</u>		B.O. Override Status	×						×											1			7	٦	7	1			1	$\dashv$	7	$\dashv$	1	┪
111.	Controller	ures	A.O. Override Status							1	_												1	+	1	$\dashv$		$\dashv$	1	1	1	7	7	1	$\dashv$
7111	onti	Jutput Features	A.O. Manual Override												-						$\dashv$	7		1	7	$\dashv$	1	1	7	1		1	$\forall$	1	┨
		~utbu	B.O. On/Off/Auto Switch	×	_					×											_	7	1		7	$\dashv$			1	1	+	7	$\forall$	1	1
3		٦	Binary Output	×			×			×	_										7			1	$\exists$	$\dashv$	7	7	1	7		7	$\forall$		2
TATE	Type: I		Binary Input		×						×										7		1		7	1			1	1	1	1	7	1	7
71	em ]	Hardware	juqjuO golanA																	┪	1			1	1	_	1	1		7			$\dashv$	1	1
acatataco.	System	Har	Juqul ZolanA			×	×	×	×		•										7		1		7		1	1	7	1	1		十	1	4
UVIIIIOUM CUMINUM HALLALADAUAU A'O	em Name: Chiller Control		Point Description	Chiller Start/Stop	Chiller Status	4 Chilled Water Supply Temperature	S Chilled Water Return Temperature	S Condenser Water Supply Temperature	Condenser Water Return Temperature	8 Chiller Pump Start/Stop	9 Chiller Pump Status																								Number of Points
			тэфти УпіоЧ	_	2	4	S	9	7	8	6	10	11	12	13	14	15	16	17	18	19	2	21	77	23	24	25	79	27	82	8	2	3	32	1

ment System Point Schedule
Controller Date: 12/17/93 ystem Name: Boiler Control System Type: L

				ľ	ļ	1	ŀ	Ì									
_	ystem Name: Boiler Control	yster	n J	System Type: L		Cont	Controller			Da	te:	Date: 12/17/93	7/93				
		Har	Hardware		익	Output Features	eatures			Software Features	re Fea	tures					
Toint Number	Point Description	JuquI golsnA	tuqtuO golanA	Binary Input	JudjuO Yrknið	B.O. On/Off/Auto Switch	A.O. Manual Override	B.O. Override Status	Pneumatic Output	gailubədə2 əmiT	Point Graphic	(2714 42) Y1012iII golknA	Binary History (10 Changes of State)	PID Loop Control	stnioA ledoT	Comments:	
1	1 Boiler Start/Stop			_	×	×		×		×	×	-	×				
7	2 Boiler Status			×	_						×	$\vdash$	×		_		
3	3 Flame Failure	×									×		×		L		
4	4 Hot Water Supply Temperature	×			-						×	×	×				
S	5 Hot Water Return Temperature			<u> </u>	×					_	×	×	×	_			
9	6 Boiler Pump Start/Stop			×	×	,		×		×	×	H	×	_			
7	7 Boiler Pump Status		-	-							×	-	×	_	L		
8													_				
6															_		
2					_												
11				-	_						_						
12				$\dashv$		-							-				
13		1	$\dashv$	$\dashv$	4	_							_				
14			1	$\dashv$	-												
15			$\dashv$	$\dashv$	_	_				_							
16				-	_						-		_				
1																	
8					_												
6			-														
20		_		_								_					
21												$\vdash$	_	L	_		
22											$\vdash$	_	L	_			
23					_				_		-	-	_				
24		_	-							-	-	H	_	L			
25			H	_	H							_	_	_			
92			-								-	_	-				
27				$\sqcup$								_	_	_	L		
78					-						_	-		_	_		
29													_				
8		1									_	_	_	_			
= :		$\dashv$	$\dashv$	$\dashv$	$\dashv$	$\sqcup$		П		H	$\vdash$	$\vdash$	$\mathbb{H}$				
32		1	$\dashv$	$\dashv$	4	4			$\exists$		$\dashv$	$\dashv$	$\dashv$				
1	Number of Points	.2	$\dashv$	3 2		Ц			Н		-	Н	Н	Ц	7		
			ĺ			l	l	l	İ	l		l	l	l			

## **Facsimile Cover Sheet**

To: DAVID L SMITH PE

Company: EINHORN YAFFEE PRESCOTT

Phone: 202/471-5082 Fax: 202/471-5050

From: RICHARD N. PRIDGEON

Company: HONEYWELL, INC.

Phone: (703)749-2072 Fax: (703)749-2093

Date: 07/07/94

Pages including this

cover page: 4

#### Comments:

DAVID,

SORRY FOR THE DELAY IN GETTING THIS INFORMATION TO YOU. PLEASE CALL WITH ANY QUESTIONS. I WILL FOLLOW UP WITH INFO ON ESUSA AND LON WORKS

THANK YOU

**RNP** 

Honeywell Inc. 1766 Old Meadow Ln McLean VA 22102-4387

July 7, 1994

Mr. David L. Smith, P.E. Einhorn Yaffee Prescott The Flour Mill 1000 Potomac Street, NW Washington, DC 20007

Ref.: Fort Belvior

Energy Management System - Budget Pricing

Dear David:

As requested, attached please find a detailed budget cost breakdown for providing and installing a Direct Digital Control Energy Management System per your control points list for the following buildings located at Fort Belvior, Virginia:

-BLDG. 200

-BLDG. 219

•BLDG. 247

-BLDG. 1425

-BLDG. 3136

These cost figures are based on a turnkey installation of a state of the art Direct Digital Control System consisting of the following qualifications:

• All major pieces of mechanical equipment (i.e. AHU, Chillers, Boilers, Hot Water Converters etc.) will be controlled by a stand alone master DDC panel with a real time clock, non-volatile memory, communication hardware/software and the ability to operate all energy management routines and control loop logic without any additional panels or Host processors.

-All unitary or terminal mechanical equipment(Fan Coil Units) will be controlled by stand alone slave DDC panels which require communication with a master DDC panel for real time clock functions but can function in a "degraded" mode upon loss of communication with the master.

-The cost of a Graphic Operators Workstation(location to be determined) including all data file generation, parameters and graphic creation has been included

-All electrical work will be performed per the National Electric Code with all work in mechanical rooms (low and line voltage) to be installed in EMT conduit as a minimum.

Mr. David L. Smith, P.E. July 7, 1994
Page - 2

-All pneumatic tubing will be hard copper if exposed and soft copper if concealed yet accessible if part of a smoke control system. All other exposed pneumatic tubing will be plastic run in EMT conduit.

-The attached cost figures include complete AUTO CAD REV 12 submittal drawings with the following:

- -Riser diagrams
- -Flow diagrams
- Point to point wiring diagrams with wire lists
- -Software logic ladder diagrams
- -Installation details
- -As-built drawings

-Also included in these costs are O&M Manuals, Programmers Manuals,

-Four(4) training sessions (on site) at eight(8) hours each are included for classes up to six operators.

-All work and material installed will be guaranteed to operate as designed for a period of one(1) year after owner acceptance.

I hope this information is sufficient for your needs, if you have any questions please feel free to contact me at 703/749-2072.

Sincerely,

RICHARD N. PRIDGEON, JR.

SENIOR SALES ENGINEER

Operators Guide etc.

703/749-2072

# FORT BELVIOR ENERGY MANAGEMENT SYSTEM BUDGETARY PRICING - JULY 1994

BUILDING BLDG, 200	MECHANICAL EQUIPMENT	COST/EA.	QTY	TOTAL		
	SINGLE ZONE AHU	11 200 00	•			
	MULTIZONE AHU(3 ZONES)	11,200.00	3	33,600.00		
	MULTIZONE AHU(7 ZONES)	15,200.00	1	15,200.00		
	SINGLE ZONE- 100% OA	18,400.00	1	18,400.00		
	CHILLER(2 STAGE)	8,000.00	1	8,000.00		
	BOILER	6,400.00	1	6,400.00		
		8,000.00	1	8,000,00		
BLDG. 219		SUBTOTAL			89,600.00	)
	AHU 1B	10 400 00				
	AHU 1A	10,400.00	1	10,400.00		
	FAN COIL UNITS	11,200.00	1	11,200.00		
	BOILERS	500.00	38	19,000,00		
	HOT WATER CONVERTOR	3,200.00	2	6,400.00		
	PAKAGED CHILLER	4,000.00	2	8,000.00		
	SPLIT AIR COOLED CHILLER	3,200.00	1	3,200.00		
	DUAL TEMP WATER LOOP	3,200.00	1	3,200.00		
	SOAL TEMP WATER LOOP	4,000.00	1	4,000,00		
BLDG. 247		SUBTOTAL			65,400.00	
	CONSTANT-VOLUME-AHU-					
	AUDITORIUM AHU	8,000.00	20	-160 <del>,</del> 000 <del>.00</del> -	DELET	E
	FAN COIL UNITS	8,800.00	1	8,800.00		
	BOILERS	500.00	93	46,500.00		
	CHILLER(CENTRIFICAL)	4,800.00	2	9,600.00		
	OMELER(CENTRIFICAL)	12,800.00	1	12,800,00		
BLDG. 1425		SUBTOTAL		· <del>2</del> :	37,700.00	77,700
	FAN COIL UNITS	-				,
	CHILLER	500,00	52	26,000.00		
	HOT WATER CONVERTOR	3,200.00	1	3,200.00		
	DUAL TEMP WATER LOOP	4,000.00	I	4,000.00		
	DOAL TEMP WATER LOOP	6,400.00	1	6,400,00		
BLDG. 3136		SUBTOTAL		3	39,600.00	
== =: 5.50	FAN COIL UNIT			23500,00		•
		500.00	47	12,500:00-	MATH	error
	HOT WATER CONVERTOR CHILLER	3,200.00	l	3,200.00		
		3,200.00	1	3,200.00		
	DUAL TEMP. WATER LOOP	4,800.00	i	4,800.00		
		SUBTOTAL		2	3,700.00	
				3	4,700,00	

GRAND TOTAL

456,700.00



#### FAX TRANSMISSION

ATTENTION: David Smith.	
FIRM: Einhorn Yaffee Prescott	
FAX NUMBER: (202) 471-5050	
NAME: Jim Wilson	
PHONE NUMBER: (703)354-333/	
DATE: 7/12/94	
TIME: 2:44	
SUBJECT: Ft. Belw. EMS	
pages being sent : 2  g this cover sheet)	
to follow in mail: Yes No	
	FIRM: Einhorn Yaffee Prescott  FAX NUMBER: (202) 471-5050  NAME: Jim Wilson  PHONE NUMBER: (703)354-3331  DATE: 7/12/94  TIME: 2:44  SUBJECT: Ft. Belwin EMS  pages being sent: 2  g this cover sheet)  to follow in mail: Yes No

Washington Gas Energy Systems, Inc. 5500 Cherokee Avenue, Suite 310, Alexandria, VA 22312 • (703) 354-3331 • fax (703) 941-8969

G-20



July 12, 1994

Mr. David Smith Einhorn Yaffee Prescott The Flour Mill 1000 Potomac Street NW Washington, DC 20007-3238

RE: Ft. Belvoir Energy Management - Project No. 60692.80

Dear Mr. Smith:

Washington Gas Energy Systems, Inc. is pleased to provide budget pricing on providing an Andover System for the following buildings located at Fort Belvoir, Virginia, per your points list dated 12/20/93:

Building	200	\$ 62,320.00
Building	219	\$113,980.00
Building	1425	\$ 99,220.00
Building	3136	\$ 50,020.00
Building	247	\$329,940.00

If you should have any questions regarding the above pricing, please do not hesitate to contact me at (703) 354-3331.

Sincerely,

WASHINGTON GAS ENERGY SYSTEMS, INC.

James C. Wilson

Automation Specialist

JCW/as

Ft. Belvoir EMS Study EMS Cost Estimates - Johnson Controls

Bldg 200

Component	Units	Quantity	Unit Cost	Extended Cost
Building EMS Controller	Each	1	\$10,000	\$10,000
Multizone Air Handling Units	Each	2	\$6,500	\$13,000
Single Zone Air Handling Units	Each	4	\$5,900	\$23,600
Fan Coil Units	Each	0	\$560	\$0
Exhaust Fans	Each	4	\$560	\$2,240
Boilers	Each	1	\$5,200	\$5,200
Chillers	Each	1	\$4,600	\$4,600
Hot Water Convertors	Each	0	\$4,000	\$0
			Total	\$58,640

### Bidg 219

Component	Units	Quantity	Unit Cost	Extended Cost
Building EMS Controller	Each	1	\$10,000	\$10,000
Multizone Air Handling Units	Each	0	\$6,500	\$0
Single Zone Air Handling Units	Each	2	\$5,900	\$11,800
Fan Coil Units	Each	38	\$560	\$21,280
Exhaust Fans	Each	2	\$560	\$1,120
Boilers	Each	2	\$5,200	\$10,400
Chillers	Each	2	\$4,600	\$9,200
Hot Water Convertors	Each	0	\$4,000	\$0
			Total	\$63,800

G-22

В	lda	24	7

Component	Units	Quantity	Unit Cost	Extended Cost
Building EMS Controller	Each	1	\$10,000	\$10,000
Multizone Air Handling Units	Each	0	\$6,500	\$0
Fan Coil Units	Each	93	\$560	\$52,080
Exhaust Fans	Each	5	\$560	\$2,800
Boilers	Each	2	\$5,200	\$10,400
Chillers	Each	1	\$4,600	\$4,600
Hot Water Convertors	Each	0	\$4,000	\$0
			Total	\$79,880

### Bldg 1425


Component	Units	Quantity	Unit Cost	Extended Cost
Building EMS Controller	Each	1	\$10,000	\$10,000
Multizone Air Handling Units	Each	0	\$6,500	\$0
Single Zone Air Handling Units	Each	0	\$5,900	\$0
Fan Coil Units	Each	52	\$560	\$29,120
Exhaust Fans	Each	1	\$560	\$560
Boilers	Each	0	\$5,200	\$0
Chillers	Each	1	\$4,600	\$4,600
Hot Water Convertors	Each	1	\$4,000	\$4,000
			Total	\$48,280

Bldg 3136

Component	Units	Quantity	Unit Cost	Extended Cost
Building EMS Controller	Each	1	\$10,000	\$10,000
Multizone Air Handling Units	Each	0	\$6,500	\$0
Single Zone Air Handling Units	Each	0	\$5,900	\$0
Fan Coil Units	Each	47	\$560	\$26,320
Exhaust Fans	Each	2	\$560	\$1,120
Boilers	Each	0	\$5,200	\$0
Chillers	Each	1	\$4,600	\$4,600
Hot Water Convertors	Each	1	\$4,000	\$4,000
			Total	\$46,040

# APPENDIX H EQUIPMENT CUT SHEETS

**FMS** 



### Scientific Atlanta

# Load management: a profitable proposition.

Load management is an effective means of improving your utility's operating efficiency and reducing utility operating costs by controlling deferrable loads with radio.

Control of deferrable loads such as air conditioners, water heaters, heat pumps and irrigation pumps is the first tool to implement in a demand side management program. Whether you are a reseller of electric power or a power generating utility, demand side management offers a number of advantages to you and your customers.

### Advantages For Power Generators

- · Lowers capacity requirements, including transmission and substation needs
- Relieve regulatory and societal pressures caused by new power plant construction
- Provides another option in economic dispatch decision
- Improves customer relations

### Advantages For Power Buyers

- Reduces demand charges or cost of power
- Improves load factor
- Lowers substation and distribution capacity requirements
- Improves customer relations

### The Load Management System


Scientific-Atlanta's Load Management System consists of:

Radio controlled switches to control the deferrable loads at residences and businesses.

Communications which include the standard VHF transmitters and interface devices.

The Master Controller where the control strategies are defined and commands are issued to the radio transmitter.

Test equipment to verify system operation.



### **Radio Controlled Switches**

The on-premise switch is the most important part of the load management system. Signals transmitted by the radio under the direction of the system Master Controller are received by the switch. The received signal causes the switch to disconnect one or more high consumption, deferrable loads. Typical loads include air conditioners and hot water heaters. Load disconnect is accomplished by relays inside the switch. Scientific-Atlanta offers switches for Scientific-Atlanta, Motorola Golay 23, 12 (Digital), and General Electric 100, 101, 102 and S-A 105 coding formats.

Each switch can have up to four relays and/or relay drivers depending on the coding format. These are available in certain combinations of 5 or 30 amp capacity. The relays respond individually to transmitted digital codes—allowing separate control strategies for each load connected to the switch.

#### LOAD SHEDDING


The load shed sequence starts when the system Master Controller sends a digitally coded signal to the remote transmitter controller and the radio transmitter. The digital coding allows the system to activate specific groups of switches. Transmitting different digital codes activates different groups of switches.

When the switch receives the coded signal, it compares it to the address programmed into its memory. If the code is correct for one of the switch's relays, the appropriate relay will open, dropping the connected load from the utility system.

### RESTORING THE LOAD

When the relay in the switch opens, shedding the load, the microprocessor in the switch starts a timer. The timer can be programmed for time-outs of 7.5, 15, 30 or 60 minutes. The actual time-out of the switch varies by plus or minus 1.5 minutes, assuring that not all the disconnected appliances will come back on-line at the same time. The time-out variable for each switch changes each time it is disconnected. This means that, on average, no one consumer is disconnected longer than another. At the end of the time-out period, the relay closes and the load is restored.

If a longer switch time-out is desired, a "refresh" message can be sent to those switches which have their relays open. This "refresh" message resets the timer to zero and starts the countdown again. This enables the utility to keep a switch with a 7.5 minute time-out off for several hours, if desired. Air conditioners are typically controlled 7.5 minutes out of every 30 minutes during the time of expected peak. Water heaters can be turned off entirely for 2 to 4 hours during the peak.



#### AFTER A POWER OUTAGE

Each switch also has the ability to disconnect its load immediately after a power outage. This "cold load pick-up" feature is selectable to aid the system when it has been down for an extended period and the system has lost its natural diversity. If the "cold load pick-up" feature is selected, the switch will be off for one time-out period (7.5, 15, 30, or 60 minutes) following the power restoration.

### TESTING THE SYSTEM


The switch also has the capability of storing a record of the activity in memory. It logs the number of activations of each relay, the number of test messages received, and the period of time since the counters were reset. This information is recalled from the microprocessor memory by using a Portable Counter Display (PCD). The PCD uses an internally generated radio transmission

and optical coupling to access the stored information, eliminating the need to open the enclosure. Comparing the number of activations read from the switch to the control system history verifies that the system is operating correctly.

### IN CASE OF EMERGENCY


The switch also has the ability to disconnect all of its loads when a special "SCRAM" code is received. All Scientific-Atlanta switches have the capability to respond to one emergency code. The number of "SCRAM" codes available varies with the switch format.

### Radio Controlled Switch Features.



H-1

tribution automation control



### **Master Controller**


Scientific-Atlanta's load management controllers are microprocessor based computers which provide centralized control of a utility's load management system. The controllers are used to implement strategies which allow a utility to accomplish its load management goals.

The load management controller contains operating programs which monitor the system load, calculate load shedding schedules, and send out digital messages to cause the desired load shed to take place. Configuration information, which defines the utility's system, is typed into the computer. This information includes characteristics or data coming from a substation or SCADA system, load control receiver grouping information, control strategies, and receiver addresses.

Once the configuration data is entered, the master controller processes it in accordance with built-in programs that instruct the computer on how to do its job. These built-in programs are stored in Read Only Memory which is permanent and not lost if power is removed.


After digesting the configuration data, the master controller will know what messages it must provide and when to schedule messages.

### Model LMC-1041



### **Typical Load Management Program**

This screen was "built" by the user from standard information to display the most important information on a real-time basis.



### VHF Radio Communications

### Licensing


The licensing process for a load management transmitter is the same for a utility as it is for a land mobile transmitter.

An application is made to the Utilities Telecommunication Council (UTC) for a frequency. After a study of surrounding users, the UTC then issues an authorization for the designated load management frequency of 154.46375 Megahertz or one in the 173.XXX MHz range.

Next, the utility prepares an application to the Federal Communications Commission for a license to operate. Since coordination with other users has been done by the UTC, the FCC approves these applications with little trouble.


After obtaining the license, the utility then can install and operate its transmitters.

### VHF Radio Equipment



### Propagation Studies.


A propagation study is conducted by Scientific-Atlanta to ensure proper coverage of the service territory.



### Radio System Maintenance

The radio transmitters used in a Scientific-Atlanta load management system are the same VHF/FM transmitters that a utility uses for its two-way mobile communications. The use of a standard transmitter provides the utility with the benefit of being able to install, test, align and maintain the load management transmitters in the same manner as they manage their land mobile network.

### **Consumer Promotions**



### LMC-1041 Load Management Controller and Data Acquisition System



The LMC-1041 is a programmable PC compatible based controller running on MS-DOS with extensive provisions for automatically gathering substation data and controlling load management functions, capacitor switching, voltage regulator control and/or other remote switching functions. The software design of the LMC-1041 allows it to act as a separate data acquisition system, as a separate load management controller, or both.

Manual or automatic operation is permitted for each separate control group. Any number of addresses can be assigned to each group.


The user can control points with different strategies, by time- of-day and/or by set points using and/or conditionals. The information from contact closures (status), pulse or analog inputs can be used to calculate values. These values and groups of values are then used in the decision making process.

The LMC-1041 interfaces with Scientific-Atlanta's Remote Transmitter Controllers and Store-and-Forward repeaters to control the transmitter network required to cover the utility's service area.

#### Features:

- User friendly software, but flexible and large enough to fit all load control needs.
- Any number of addresses, control groups, strategies allowed. Limited only by memory.
- Combines data acquisition and load control into one machine.
- Operating characteristics can be modified while program runs.

### MGU-1008 Mini-Message Generator Unit



The MGU-1008 is a programmable microprocessor based controller with extensive provisions for automatically controlling load management functions. Manual or automatic operation is permitted for each of up to 5 separate control groups. Each control group can be scheduled as a function of percent load shed, time-of-day, day-of-week, holiday, external sensing, or

manual control via keyboard control. The program may be easily changed with inputs via a CRT and keypad. Status monitoring during operation is provided as a real time display on the CRT.

#### Features:

- Individual control of up to 5 control groups (i.e., water heaters, air conditioners, etc.).
- Cycles of each control group in 5% increments from 0 to 100%.
- Load management may be initiated by: time-of-day, contact from SCADA system or manual control.
- Memory has battery backup to retain program.
- Load management schedules originated or modified easily by menu selections and operator prompts.
- CRT provides summary report of activity.

### RTC-1032 Remote Transmitter Controller



The Remote Transmitter Controller (RTC) is a microprocessorbased unit that provides a reliable method of activating remote radio transmitters used in energy management systems. The RTC contains the necessary functions to key up the transmitter, to provide status and control functions, and to modulate the audio signals to load control units installed at customer's facilities. The Master Controller communicates to the RTC a message which tells it the transmitter identification, frequency, type of message, and the Scientific-Atlanta digital message content. The RTC keys the transmitter and generates signals over a 427.5 Hz to 1146.5 Hz frequency range.

#### Features:

- Audio generation of Scientific-Atlanta's digital signal and single and dual tone formats.
- Control of up to six transmitters.
- Eliminates telephone line distortion when located remotely.
- Message buffering and listen-before-transmit.

10

H-12

### PTU-1084 Portable Test Unit



The PTU-1084 Portable Test Unit provides fast, on-site testing, troubleshooting, and checkout of radio controlled switches used in Scientific-Atlanta's load management products. The Portable Test Unit allows manual selection of digital radio signals for transmission to test for proper operation of switches. The

economy and portability of the PTU-1084 makes it practical for each switch to be tested as it is installed.


Digital coding is selected via incremental push-toselect switches on the front panel. Message transmission is achieved by depressing the TRANSMIT control.

The PTU-1084 is available in Scientific-Atlanta or GE REMS digital AFSK format, or Golay digital FSK format.

#### Features:

- Rugged, portable, hand-held test unit.
- Disposable 9V battery with low battery indicator.
- Operator selected digital coding.
- Internal antenna.
- All major manufacturers' code formats available.

### TMS-1003B Transmission Monitoring System



The Transmission Monitoring System monitors the load management radio frequency and provides a permanent record of each message received, including the date and time of transmission. This provides complete documentation for analysis of overall system effectiveness.

An LCD on the face of the TMS continuously displays the date and time until a message is received. At that time, a "carrier detect" LED lights and, if the message is valid, a "message received" LED lights and the printer prints the date, and message(s).

#### Features:

- Monitors radio transmissions of load management commands to provide permanent record of control activity.
- Provides immediate confirmation that all components of communications channels are functioning.
- Provides complete documentation of all messages sent for use in evaluation and analysis of load management activity.
- Operates unattended.
- Battery backed-up operation.

### PCD-1089 Portable Counter Display



The Portable Counter Display<sup>TM</sup> is a hand held, battery operated survey instrument which permits gathering of accurate data concerning the performance of a load management system. Designed for use in conjunction with PCD compatible Scientific-Atlanta Digital Control Units, (DCU's), the PCD-1089 uses a low power rf transmitter and an optical receiver to interrogate the DCU's internal memory.

The PCD displays the following critical load management system operation data:

- · Number of times each DCU relay has operated
- Number of test messages received by the DCU
- Elapsed time since the counter was reset or frozen
- Switch address
- · Whether cold load pick-up is enabled or disabled
- Relay timeout (Scientific-Atlanta and Golay formatted switches only).

#### Features:

- Provides means for field survey of load management activity.
- · Displays switch activity.
- Easy to use.
- Operates from standard 9V battery.
- Available in several manufacturers' formats.

### Scientific-Atlanta Digital Control Units



The Digital Control Unit (DCU) is a radio controlled switch designed to switch remote loads on and off in response to commands from a central control, such as Scientific-Atlanta's Load Management Controllers.

The DCU's advanced microprocessor-based design includes both "watchdog" and unique fail-safe driver circuits. The "watchdog" continuously monitors the microprocessor and automatically reinitializes its program should it be disrupted by a lightning surge or other line disturbance. The fail-safe relay driver circuit

ensures that output relays are closed in the event of an electronics failure.

#### Features:

#### General:

- Reliable microprocessor-based design which can retain record of control activity for use with PCD-1089.
- Simple field programming.
- High performance dual conversion FM receiver with superior sensitivity and selectivity.
- Electronics mounted in removable door for easy field maintenance.
- Cold load start-up disconnects loads when service is restored after an outage.
- Fail-safe timer reconnects load if signal is not received within a field selectable 7.5, 15, 30, or 60 minute time period.
- Fail-safe relay driver circuits reconnect load if electronics fail.
- Weatherproof enclosure of high-impact polycarbonate.

### DCU-1170A Series (Scientific-Atlanta Format)

The series DCU-1170 switch responds to messages sent via radio in the Scientific-Atlanta format. This format uses audio frequency shift keying of mark and space tones to represent 256 digital addresses per set of tones.

The DCU-1170A series switch is available in single or dual function configurations with two separate SCRAM codes available.

#### Features:

- One or two 5 amp and/or 30 amp relays.
- 64 mark and space tones allow coordination between utilities.
- Cold load cancel permits reconnection of load before time-out.

### DCU-M1180A Series (Golay Compatible Format)

The DCU-M1180A series switch responds to the Golay 23,12 code. Available in one, two, three and four function configurations, the DCU-M1180A series switch is field programmable with any of the standard Golay 23, 12 addresses.

#### Features:

- One, two, three or four function.
- Available with up to three 5 amp 120V form C relays, up to two 30 amp 240V Form B relays and/or external relay drivers.
- 8,192 distinct addresses available plus separate function codes.
- Frequency shift keying format.

### DCU-G1530 Series (REMS™ Compatible Format)

The DCU-G1530 series switch responds to the audio frequency shift keying signaling known as the "GE REMS 100, 101, 102, and SA-105 Formats." The 100 format uses 1200 Hz and 1000 Hz to control the switches, which then time-out. The 101, 102, and SA-105 formats use a "distributed intelligence" technique in which one message from the controller can cause the switch to cycle at a designated rate for up to 8 hours.

The DCU-G1530 switch contains the ability to do all four formats in the same switch. The message received instructs the switch on how to respond.

#### Features:

- One, two, three or four function.
- Available with up to three 5 amp 120V form C relays and/or up to two 30 amp 240V form B relays and/or external relay drivers.
- 4,096 distinct addresses available plus separate functions codes.
- SA-105 message allows the switch to randomly start (turn off the load) over a period of up to 60 minutes.

### Capacitor Control DCU



Scientific-Atlanta's Capacitor Control DCU uses the standard DCU enclosure and adds a "Meter Socket Adapter" and other components to provide capacitor control. This permits existing radio load management systems to add system wide control of capacitor banks to their distribution automation program.

#### Features:

- Any format DCU can be used
- · Local on/off/bypass control
- Extra surge protection
- 120 volt power supply

### Hybrid System™ Control Units



Scientific-Atlanta's Hybrid System<sup>TM</sup> offers a unique signalling technique for the Scientific-Atlanta format. This Hybrid System uses a combination of radio and low voltage (240V) power line carrier signalling to control loads. The Hybrid System uses three components to accomplish load control.

### RCX-1026

The RCX-1026 is a radio receiver and power line carrier transmitter. Its function is to receive the radio messages, convert the messages to a power line car-

rier signal and inject the signal onto the secondary side of a distribution transformer.

### PLC-1022

The PLC-1022 with a 5 amp relay is mounted near the load to be controlled and receives and decodes the power line carrier message.

#### PLC-1023

The PLC-1023 functions in the same manner as the PLC-1022 but contains a 30 amp relay.

#### Features

- Any number of PLCs on the same secondary can be operated by one RCX.
- The RCX can be installed at the most convenient location on the secondary or high on the utility pole for optimum radio reception.
- Hybrid System can be mixed with Scientific-Atlanta format Digital Control Units in order to most effectively cover a utility's service territory.

H-15

# Why Purchase a Scientific-Atlanta Load Management System?

#### TECHNICAL EXPERTISE

- Offers a broad range of technical capabilities in communications systems.
- Offers a microprocessor-based central controller developed from over ten years of utility control experience.
- Offers efficient use of radio spectra.
- Offers a substantial variety of load control strategies and products.
- Offers radio propagation studies to ensure adequate coverage of service territory.

#### FLEXIBILITY

- Handles a variety of energy management techniques including load control, customer voltage reduction, and other distribution automation functions—all with standard products currently being manufactured.
- Meets existing requirements while providing considerable expansion for future applications.

#### **GROWTH CAPABILITY**

- Accommodates new technology, expanding applications and changes in requirements.
- Automated manufacturing facilities in Atlanta with large capacity and potential for expansion.

### **ECONOMY**

Offers economical installation, operation, system expansion, and change.

#### RELIABILITY AND SERVICEABILITY

- Offers a practical test and replacement program.
- Services and repairs all equipment.
- Offers manufacturing and support from a United States location.

#### TRAINING

- Provides on-site training for operation and maintenance of system, including classroom and hands-on training.
- Trains personnel on proper installation of control units.

#### **DELIVERY**

- Utilizes high volume production techniques for consistent quality and timely delivery.
- Offers rapid availability of all system equipment.

#### WARRANTY

 Guarantees all equipment supplied to be free from defects in design, workmanship, and materials for one year from date of installation or 18 months from date of shipment, whichever comes first.


#### OTHER SERVICES

- Provides proven customer communications package for promotion of load management to utility's consumers.
- Provides detailed instructions manuals.
- Provides ongoing technical assistance for systemrelated problems.
- Provides installation supervision of central equipment.
- Provides assistance in radio coordination and licensing process.

HILDENBRAND COMPANY INC.

F.O. Box 3420 ALEXANDRIA, VIRGINIA 22302 TEL (703) 998-0445 FAX (703) 998-6734

### Scientific-Atlanta, Inc.




### Features

- Combines data acquisition and load control into one machine operating on MS-DOS
- Manual or automatic initiation of load control
- Several load control algorithms are available to the user
- Generates messages in several formats of radio controlled switches
- Program is simple, yet flexible
- Controls air conditioners, water heaters, irrigation pumps, and capacitor banks
- User can define the control "steps" that the program uses
- All programming is done with pop-up menus and operator prompts with on-screen helps
- User defines the number of addresses, number of control groups and strategies he wants and the LMC creates file space to accommodate, limited only by available memory
- Operating characteristics can be modified while the program is running
- Special screens can easily be designed and implemented by the user
- Software supports an optional color monitor


- All software is stored on a hard disk
- Lotus®- compatible historical data files allow easy processing of accumulated data
- Printer can be programmed to automatically print reports
- System automatically restarts in case of power outage
- Interfaces to Scientific-Atlanta's Remote Transmitter Controllers RTC-1032 or RCCA-1002A
- Optional WWV interface ensures accurate timekeeping
- Software supports bar chart and line graphics

Scientific Atlanta

**Control Systems Division** 



LMC 1041+, Load Management Controller



RTC-1032, Remote Transmitter Controller

### **Description**

The LMC-1041+ is a personal computer based load management controller and data acquisition system. Automatic or manual control commands are initiated by the LMC-1041+ to remotely installed radio receivers. The receivers control loads such as air conditioners, water heaters, pool pumps, irrigation pumps, etc. Power factor control is also possible by remotely controlling distribution feeder capacitor banks.

Data acquisition capabilities of the LMC-1041+ permit monitoring of substation data for display and/or initiation of automatic control functions. Automatic control can be done using kW or kVAR inputs, status point closures, and/or time-of-day and day-of-week schedules.

Capable of outputting all standard Scientific-Atlanta code formats as well as a number of others, the LMC-1041+'s flexible software permits the user to easily configure the system by selecting the options he wants from the pop-up menus, lists of valid entries, and notes which briefly explain what each entry does.

An unlimited number of load groups as well as multiple load control algorithms, time-of-day schedules and control strategies provide ultimate flexibility. The user can even modify existing displays or create new displays to meet his needs using the LMC-1041+ display editor. With this capability he can display the most important "real-time" and explanatory information.

The LMC-1041+ places no limit on the number of strategies, load groups, or switch addresses the utility may use. The user tells the LMC what he wants to do and the LMC creates file space to meet the user's needs. The only limit is the amount of memory available.

The LMC-1041+ program is organized by strategies, setpoints, status points and time-of-day schedules. The user can then apply these characteristics to increase or decrease the amount and type of load to be shed and restored to meet changing control requirements. The user can call for load control algorithms such as cycling at a designated percentage, on/off control, various dis-

tributed intelligence strategies, nicking or SCRAM. These can be used in virtually any combination to meet the user's control needs.

The LMC-1041+ also has several features which support the user in operating the system and reporting what has happened. All information can be formatted into a Lotus® compatible file and stored on the hard disk. The printer can be programmed to print out any or all events such as alarms or the automatic initiation of load control.

The LMC-1041+ also uses Scientific-Atlanta's Remote Transmitter Controller (RTC-1032) in this system. An RTC-1032 is located at each transmitter site, connected to the LMC through 1200 baud modems. The RTC-1032 (formerly the RCCA-1002A) receives the messages to be broadcast from the LMC, stores those messages until its proper time slot, keys the transmitter, then generates the proper modulation (tones or shifting frequency) to represent the message.

The RTC can generate most of the formats used in load control today. These include single tone, two tone, Scientific-Atlanta's digital, 100, 102, and SA-105 AFSK formats, and the Golay 23, 12 FSK format.

The RTC can control up to six groups of transmitters (for time slot coordination with other utilities). If a carrier-operated relay is in the transmitter, the RTC can also wait until the air clears before broadcasting.

The LMC-1041+ is typically quoted with the standard hardware shown in the specifications section. The RTC's and modems are quoted separately because each system may require different numbers of transmitters.

Scientific Atlanta

**Control Systems Division** 

### **Specifications**

### LMC-1041+ Hardware

- Personal computer running on MS-DOS operating system with enhanced keyboard and 640K of RAM
- 13" Monochrome CRT
- 3 1/2" 720K floppy disk drive
- 20 MB hard disk
- Dot matrix printer
- Serial port
- Parallel port
- Data acquisition board and connector panel with 8 analog inputs, 8 status inputs, and 8 contacts out
- All interfaces and cables required
- Hardware Options:
  - 1. Color monitor
  - 2. Up to 24 analog inputs, 24 status inputs, and 24 contacts out

### LMC-1041+ Software

#### Load control

### 1. Strategies

- a. Any number allowed
- b. One or more running at the same time
- c. Any number of load control steps per strategy
- d. Direction of the steps can be changed whether in shed or restore mode
- e. Strategies can be tied to any combination of four status points, analog demands, or time-of-day schedules for automatic initiation of load control
- f. And/or conditionals enhance initiation factors
- g. Strategy activation can be automatic (tied to activation parameters), continuous (constantly active), or in SCRAM mode (to select 100% shed of all points)

#### 2. Steps

- a. Three types of steps (activation of switch groups, closing control points, or resetting strategy activation level to a new point)
- b. Automatic, continuous, or SCRAM activation of any step
- Steps can be linked to make them happen at the same time in either the shed or restore direction.
- Information going to the historical data files can be turned on and off

### 3. Switch Group Steps

- a. Switch control algorithms
  - Sequential step (on/off in the same order each time)
  - Rotational step (on/off in rotating order)
  - Gradual time cycle (achieve designated % over one time-out period)

- Fast time cycle (achieve designated % in one burst of messages)
- Target % load shed (responds to changes in demand level)
- Nicking (for testing the effectiveness of load control)
- 102 commands (repeating direct load control)
- SA-105 commands (distributed intelligence control)
- b. Maximum load shed % for this switch group
- Maximum duration of load control for the switch group
- Time that the appliance must remain on after reaching its maximum duration before it can be controlled again
- Time-out, cycle time and number of repetitions selections in the 102 and SA-105 format switches.

#### 4. Switch Groups

- a. 1000 addresses per group
- b. Group assigned to a single or all transmitters
- c. Repeat number of messages sent each time (1 or more)
- d. Minimum, nominal, and virtual time-outs

#### 5. Addresses

- Individual addresses can be enabled or disabled
- b. Messages sent can be recorded in a data file
- c. Eight different formats are supported (SA timeout, SA set/reset, single tone, Motorola two tone, Golay, 100, 102 and SA-105)

### 6. Time-of-Day Schedules

- a. Schedule name
- b. Programmed for seven days plus holidays
- c. 4 start/stop intervals per day

#### 7. Holiday Lists

- a. Multiple holiday lists
- b. 20 days per list

#### 8. Transmit Schedule and System Options

- Enable or disable transmissions during each minute of the hour (for coordination with other utilities)
- Time slotting for 1 to 6 transmitter groups (divides the minute into 10 to 60 second time slots)
- c. Carrier busy "listen-before-talk"
- d. Password security
- e. WWV time synchronization

### Specifications (Cont.)

### Data Acquisition

### 1. Remote Terminals

- a. Individually addressable
- b. Polling can be enabled or disabled
- c. Polling interval in one minute increments
- d. Up to 24 status points
- e. Up to 24 analog-in points

### 2. Telemetry (analog inputs)

- a Default values can be assigned in case of communication failures
- b. Scaling mulitipliers are used
- c. Offsets establish starting points
- d. High and low limits establish use of defaults

#### 3. Calculate

- a. Analog values used to calculate demands
- b. Unlimited number of calculations available
- c. 30 different operators can be used

#### 4. Demands

- a. Names
- b. Unlimited number
- c. Combines analog inputs in any manner
- d. Demand interval set from 1 to 60 minutes

#### 5. Setpoints

- a. User designated initiation factors (kW, kVAR, kVA, temperature, etc.)
- b. User sets shed and restore values
- c. User decides the relationship of the shed and restore values

#### 6. Control Points

- a. Name
- b. Up to 24 contacts-out (external)
- c. Unlimited number of internal control points

### Reporting

### 1. Printer

- a. Automatic printing of events (alarms and actions)
- Automatic printout of special screens at designated times

### 2. Display building program

a. Used to develop special, custom-built screens

#### 3. Historical Data Files


- a. Name
- b. Captures designated display numbers
- c. Establish interval between captures
- d. Establish file sizes
- e. Reset data by day of the month

#### 4. Graphics

- a. Explanatory including lines and boxes
- b. Real time bar and line graphs
- c. User choice of colors, intensity, axes and offsets

### 5. Transmitter Check-Back

 a. Error indications from the transmitter sites can alarm at the LMC



### **Specifications (Cont.)**

### Miscellaneous

- 1. Pop-up bar type menus
- 2. On-screen programmable helps (lists options at each choice)
- 3. Programming is done by filling in the blanks
- 4. Function keys (F1 F12) are user programmed to enact control or call up screens
- 5. A majority of programming characteristics can be changed while the program is running
- 6. Copy configurations to floppy disk
- 7. Automatic testing for illegal parameters and relationships
- Redundant hardware configuration allows automatic transfer between machines in case of failure


### Options

 Communications package to allow a remote computer to query, modify the program, or enact control


### **RTC-1032 Remote Transmitter Controller**

- Input 120V ac, 60 Hz
- Power Consumption 30 watts
- Operating temperature 0°C +50°C
- Control Output 6 SPST contacts, 250V ac, 3A
- Communications Modem 1200 baud, bell 212
- Listen-before-talk contact closure from carrier operated relay in the transmitter with LBT override (if the channel stays busy)
- Status Input two contact closures


### **Component Outline Dimensions**



**Master Station** 




### **Remote Transmitter Controller**



**Printer** 

### **Typical Load Management Program**




HILDENBRAND COMPANY INC.
P.O. Box 3420
ALEXANDRIA, YIRGINIA 22302
TEL (703) 998-0445

FAX (703) 998-6734

H-22

### **Digital Control Unit DCU-1170A Series**



### **Description**

The Digital Control Unit (DCU) is a radio controlled switch designed to switch remote loads on and off in response to commands from a central control such as Scientific-Atlanta's Message Generator Units. Available in single and dual function configurations, the DCU is field programmable with any of 256 individual addresses. In addition, each DCU has two individual SCRAM codes for greater flexibility.

Cold load start up, a feature which disconnects loads when power is restored after an outage, is field selectable. When used, power is restored to disconnected loads on a randomized basis within one timeout period. A special code may be used to cancel cold load start-up and restore loads immediately.

The DCU's advanced microprocessor-based design includes both "watchdog" and unique fail-safe driver circuits. The "watchdog" continuously monitors the mircoprocessor and automatically reinitializes its program should it be disrupted by a lightning surge or other line disturbance. The fail-safe relay driver circuit insures that output relays are closed in the event of an electronics failure.

The DCU-1170A Series is available with an optional electronic multi-function event counter which records and stores the following data:

- Number of activations of each function
- · Number of "test" messages received
- Time elapsed in hours since the memory was reset (up to 9 months)
- Cold load pickup status
- Switch address
- SCRAM code

The counter can be read without opening the switch enclosure with a Scientific-Atlanta, hand-held Portable Counter Display, (PCD) Model PCD-1089.


### Features

- · Reliable microprocessor-based design
- Single or dual function
- · Simple field programming
- High performance dual conversion FM receiver with superior sensitivity and selectivity
- Electronics mounted in removable door for easy field maintenance
- Two SCRAM codes
- Cold load start-up disconnects loads when service is restored after an outage
- Fail-safe timer reconnects load if signal is not received within a field selectable 7.5, 15, 30 or 60 minute time period
- Optional set-reset operation causes each function to cancel the other when it activates
- Fail-safe relay driver circuits reconnect load if microprocessor fails
- · Weatherproof NEMA 4 enclosure of high-impact plastic

### **Optional Features**

- Selection of 5 amp/24V ac or 30 amp 240V ac relay contacts
- External antenna connector
- · Alternate operating voltages
- Self testing electronics with ROM/RAM diagnostics
- Test LED to indicate test code received (no relay operation). Separate test codes may cause lamp to either light or blink.
- LED indicator to show relay(s) energized
- Cold load delay causes cold load pickup feature to ignore power outages of up to 30 seconds
- Address coding by upright pins and jumper caps allows easy field reprogramming of the switch without soldering





All electronics are conveniently located in a removable door for ease of maintenance and service.

Optional features include a test LED which indicates reception and decoding of a Scientific-Atlanta digital message. This indicator allows verification of proper system operation after installation without activating the control relay. Separate test codes transmitted to the DCU may cause the LED to either light or blink. In addition, the same LED is used to indicate the results of the DCU's microprocessor self testing diagnostic routine. When the DCU is energized, or a special test code is received, a complete self-test of both the ROM and RAM is performed and the LED will blink to indicate test results. This feature provides verification of the electronics integrity at the time of installation.

Other optional LED's are available to show control relays are energized.


Typical applications are:

Residential direct load control Power factor capacitor switching Voltage regulation control Water pumping control Implementation of interruptible rates Traffic signal control Sprinkler system control

### Operation

ne DCU is a radio switch that responds to digitally-encoded RF signals. The unit is not sensitive to mechanical vibrations since solid state components are used throughout.


The digitally encoded message which controls the DCU utilizes two-frequency pulse width modulation



Electronics are mounted in removable door for easy field maintenance.

(PWM) in frequency shift keying (FSK) format. The high performance, dual conversion radio receiver in the DCU detects the RF signal and demodulates the carrier, recovering the FSK tones. An FSK decoder derives a serial pulse train. By precisely timing the pulse widths, the digital decoder recovers an 8 bit code and compares it to a programmed code. If the codes agree, the control relay is activated and a timer is initiated. If the correct code is not received again within the programmed timeout period, the control relay is deactivated. Retransmitting the correct code extends the control time an additional period from the time it is received.

#### Digital Control Unit DCU-1170A Series



### **Specifications**

#### General

Input Voltage

240V ac ±15%, 60 Hz (Standard)

120V ac  $\pm$ 15%, 60 Hz (Optional)

24V ac ±15%, 60 Hz (Optional)

240/480V ac ±15%, 60 Hz (Optional)

Power Consumption

5 watts maximum

Operating Temperature

-30°C to +60°C

Humidity

0% to 100%, non-condensing

Transient Voltage Protection

Exceeds ANSI C37-90A-1974

Weight

2.2 lbs.

Shipping Weight

2.7 lbs.

**Enclosure** 

Injection molded, high impact strength plastic

Electronics mounted in removable door

Dimensions

9.7"H x 7.1"W x 3.0"D

#### Receiver

Type

Narrowband FM, dual conversion, crystal controlled Sensitivity

Typically 20  $\mu$  V per meter

Frequency

154.46375 MHz (other frequencies available on special order)

Frequency Stability

.002% over operating temperature range

Image Rejection

40 dB

Selectivity

50 dB minimum ±20 kHz; 100 dB minimum ±30 kHz

Certification

FCC and UL

#### **Decoder/Controller**

Microprocessor

8 bit with self-test diagnostics

Code Transmission Format

Two frequency pulse-width modulation (FSK)

Fail-Safe Timer

75, 15, 30 or 60 minutes, ±1.5 minutes randomization

Output Relays

5 amps resistive @24V ac, Form B (SPST) or 30 amps resistive @240V ac, Form B (SPST) contacts

Fail-safe relay drivers close relay contacts in event of microprocessor failure.

Watchdog circuit monitors microprocessor for correct operation.

User Programmable Functions:

256 address codes

Enable or disable SCRAM

Select between two (2) independent SCRAM codes

Enable or disable cold load pickup

Select 7.5, 15, 30 or 60 minute timout

Select set/reset operation (either function

cancels the other)

Test Functions

Microprocessor self-test on energization

Special Codes:

1) Turn test LED on

2) Turn test LED off

3) Cause test LED to blink

LED Indicators (optional)

One (1) for each output relay to show contact position

One (1) for test codes and signal reception indicator Other Functions

Cancel cold load pickup before timeout

### **Optional Features**

Electronic Event Counter

External relay driver

External antenna connection

Address coding by upright pins and jumper caps

CATV System Interface

Rear entrance elbow (see outline drawing)

Test LED to indicate test code received and the results of ROM/RAM tests

LED to indicate control relay(s) energized


Operating Voltage a) 24V ac

- b) 120V ac
- c) 240/480V ac
- d) 120/240V ac

Three wire connection (single function unit only)

Cold load delay (cold load pickup ignores power outages of





### Control Unit Relay Options and Model Number

Function 1

Model	Contact Rating, Wire Size & Color
DCU-1170A	5 Amp, 24V ac, 2 Blue No. 18
DCU-1171A	30 Amp, 240V ac, 2 Blue No. 10
DCU-1172A	5 Amp, 24V ac, 2 Blue No. 18
DCU-1173A	5 Amp, 24V ac, 2 Blue No. 18
	Function 2
Model	Contact Rating, Wire Size & Color
DCU-1170A	N/A
DCU-1171A	N/A
DCU-1172A	30 Amp, 240V ac, 2 Yellow No. 10
DCU-1173A	5 Amp, 24V ac, 2 Yellow No. 18

Above models rated for 240V ac operation. Power wires; 1 Black, 1 Red, No. 12.


Optional operating voltages shown below.

Suffix	Operating	Power Wire Size	
Desig.	Voltage	and Color	
-1	24V ac	1 Blk, 1 Red, No. 18	
-2	120V ac	1 Blk, 1 Red, No. 12	
-3	240/480V ac	1 Blk, 1 Red, 1 Violet, No. 12	
-4	120/240V ac	1 Blk, 1 Red, 1 Violet, No. 12	

All wires are 18" in length, insulated to 600V at 105°C.

### HILDENBRAND COMPANY INC.

P.O. Box 3420 ALEXANDRIA, VIRGINIA 22302 TEL (703) 998-0445



### Scientific-Atlanta, Inc.

United States: 4300 Northeast Expressway, Box 105038, Atlanta, GA 30348; Telephone 404-441-4112; TWX 810-766-4912; Telex 0542898 Europe: Home Park Estate, King Cangley, Herts WD4 8LZ, England; Telephone 09.277-66133; Telex 912044 Australia: 220 Pacific Highway, Suite 501, Crows Nest, N.S.W. 2065, Australia; Telephone 61-2-957-2599: Telex AA 177418

**PLC** 

### PCC TRANSMISSION THEORY


### INTRODUCTION

Powerline Control Components (PCC) are electronic wiring devices designed for industrial and commercial installations. These components provide centralized, remote and local control of electrical loads by superimposing a 120 KHz carrier signal upon the existing power conductors supplying the loads. The devices can control up to 256 separate addresses; each address can switch up to 50 receivers and their respective loads as a group. Programmable controllers, personal computer and other interfaces are available which can automatically actuate commands for all addresses. Override can be exercised using wall-mounted, push button, dry-contact or table top manual controllers.

Powerline Control Components consist of three types: transmitters, receivers and coupling devices and are compatible with common distribution voltages, both single and three phase. The theory of operation is the same for all devices regardless of the input voltage. Transmitters send coded signals via coupled AC power circuits to PCC receivers which control loads connected to them. Coupling equipment is necessary to enhance signal transmission, couple phases and compensate for phase shifts encountered in multi-voltage/multi-transformer installations.


### Transmission Synchronized to Zero Crossing


PCC transmitters are powered by either 120 V or 277 V standard AC power and transmit digitally encoded 120 KHz signal bursts onto the existing electrical wiring. These signals are synchronized to the zero crossing of the power to which the transmitter is connected. Transmission at this point has the advantage of avoiding noise spikes generated by other equipment which generally do not cause noise near the zero crossing. The signal is transmitted three times at 0, 60 and 120 degrees referenced to the zero crossing to which the device draws its power, this coincides with the phase to neutral zero crossing points of all phases of a three phase system. Figure 1 shows the timing relationship of these bursts to the zero crossing. A binary 1 is represented by a 1 millisecond burst of 120 KHz. at the three zero crossing points and a binary zero by the absence of the burst. The signals in Fig. 1 are shown as they would be seen through a high pass filter. The 60 Hz. waveform is only shown for reference. In reality, the signals are actually superimposed on the 60 Hz. waveform and look similar to that shown in Fig. 2.



### **Code Structure**


A complete code transmission encompasses eleven cycles of the power line. The first two cycles represent the Start Code (always 1110). The next four cycles represent the Letter Code (A thru P) and the last five cycles represent either a Number Code (1 thru 16) or a Function Code (On, Off, Bright, Dim, All Lights On, All Units Off).





These codes are transmitted twice making the total length twenty-two cycles.

The codes are transmitted in blocks consisting of the two groups of 22 cycles separated by 3 cycles.



The 3 cycles between each pair of code transmissions is a "silence" and is required by the receiver module's circuitry. Bright and dim commands are exceptions to the 3 cycle rule and can be transmitted continuously with no gaps between the same codes, (dim and dim). The three cycle gap however is necessary between different codes, (i.e. between bright and dim or on and off commands).

Within each block of data the code is transmitted in both true and complement form on altewrnate half cycles of the power line, i.e. if a burst of signal is transmitted on one half cycle (a binary 1) then no signal is transmitted on the next half cycle, (binary 0). See Fig. 4 below. This complement form applies to the data portion of the block only. The start code is 1110 and is always transmitted on the first 2 cycles of the block.




Fig. 4

The following table shows the binary representation of each code used.

A 0110	1 01100
B 1110	2 11100
C 0010	3 00100
D 1010	4 10100
E 0001	5 00010
F 1001	6 10010
G 0101	7 01010
H 1101	8 11010
I 0111	9 01110
J 1111	10 11110
K 0011	11 00110
L 1011	12 10110
M 0000	13 00000
N 1000	14 10000
O 0100	15 01000
P 1100	16 11000
All Off 00001	All Lights On 00011
On 00101	Off 00111
Bright 01011	Dim 01001


### Repeated Signal

Coupler-repeaters are used to maintain signal integrity and allow signals to be seen in distributions which are out of phase with the transmitter supplying the original signal. The transmitters signal (approximately 3V) attenuate as distance from the transmitter increases. Since signals of at least 100mV at the proper zero crossing are required at the receiver for proper operation, a means of regenerating and shifting the signal is necessary. The coupler-repeaters perform this task by monitoring the power lines for valid signals. It then amplifies them at the original zero crossing and repeats the amplified signal with a 30 degree shift. This happens on each phase so that all six possible zero crossings have signal available. The coupler-repeater uses the codes' redundant transmission to accomplish this function. As original signal is transmitted, the coupler-repeater reads the first transmission of the code and amplifies it at exactly the same time as the second transmission occurs, as depicted in the diagram below.


START	LETTER	NUMBER	START	டிராக	NUMBER
ccc∈	<b>∞</b> ∞€	∞∞€	ccc∈	Œ	∞∞€

START	LETTER	FUNCTION	START	டிராக	FUNCTION
Œ	∞∞ <b>∈</b>	CODE	∞∞€	∞∞ <b>∈</b>	<b>∞</b> ∞€

START	reller.	NUMBER
ccc∈	CODE	cco∈




It then transmits a new amplified 30 degree shifted signal for use by recievers in other distributions or otherwise referenced to a 30 degree shifted zero crossing.



The amplification allows signals to travel much further than they normally would to reach distant receivers with sufficient signal strength. The repeating function allows the use of receivers referenced to zero crossings other than that of the original transmitter, i.e. receivers connected to 120V distributions can receive signals created by a transmitter located in a 277V distribution provided the proper PCC devices were provided to couple the transformers between the distributions. The PCC Source Book or Specifier Manual provides specific information on all coupling devices available. For more information call the PCC Techline at 1-800-886-2281.

## SECTION C



POWERLINE CARRIER SYSTEM FLOW DIAGRAM






PCC 125 VAC Single Pole Feed-Thru Switch

To make connections to RS128/RS121: loosen screw clamps on side of module, seat screw to expose clamp, strip wire & insert into appropriate socket on back of module then retighten screw clamps.

To set address codes: insert small screwdriver into slot on code dials and turn until arrow points to desired letter and number code. Remount switch plate by gently pushing it back into position.



#### **BEFORE YOU BEGIN...**

#### **READ ALL INSTRUCTIONS**

Make sure your installation will conform to all applicable codes and requirements.

#### TEST FOR SIGNAL STRENGTH AND NOISE...

using the AR300 and AT300. It is necessary to test the installation in the actual operating environment. The amount and types of line loads may reduce the strength of the transmitted signal and/or electrical noise may cause interference with the transmitted signal. Proper installation may require additional couplers, filters or repeaters. Special coupling devices are required to allow signal to be distributed to all phases and zero-crossings in multi-phase and multi-transformer distributions.

#### IF YOU HAVE ANY QUESTIONS...

Consult your nearest Engineered System Center (ESC) for additional information.

There are no field repairable assemblies on this unit. It is covered by a two year limited warranty. If service is needed, the unit must be returned to the ESC where purchased. Contact your ESC for return details.

#### INSTALLATION

**CAUTION!** Make all connections with the POWER OFF to avoid injury to the installer or damage to the device.

NOTE! This switch is not intended as an exact replacement for standard wall switches. The Neutral terminal MUST be connected to a Neutral (not simply a white lead used as a traveler fo a load).

ADVANCED CONTROL TECHNOLOGIES, INC.

RS120 Installation Instructio

Indianapolis, Indiana 46241 (800) 886-2281

Rev A P/D 089

- 1. Using the STRIP GAUGE on the back of the module, strip insulation from the ends of the conductors. Loosen the appropriate screw clamp on the side of the module. Push the screw against its seat to expose the clamp, insert the wire and retighten the screw clamp. Make connections as shown in the Wiring Diagram. The connection to the neutral terminal of the module does not have to be the neutral of the load.
- 2. Check connections to be sure they are tight and no bare conductors are exposed.

NOTE! Tighten all screw clamps securely.

- 3. Make sure the load or installation does not exceed the device rating.
- 4. Install into a standard single or multi-gang electrical wall box. Use a deep box to avoid interference with box fittings and allow room for wiring connections.

Mount the device in the wallbox and install the cover plate/trim ring (Decora TM or compatible style available through electrical supply vendors).

#### **CHECKOUT**

- Restore the power.
- 2. Set the address:

Up to 256 addresses can be selected from the module. The address consists of a Letter Code (A through P) and a Number Code (1 through 16) for Unit address. Set the address code dials as shown in the Wiring Diagram.


3. Test Local Operation:

Depress the switch plate several times to ensure the module turns the controlled load on and off in response to manual control.

4. Test Remote Operation:

Using a controller, transmit "OFF", "ON", "ALL OFF" and "ALL LIGHTS ON" commands to ensure the device turns the controlled load on and off in response to remote control.

Test for Signal Strength and Noise once again using the AR300 and AT300.





20 Amps

125 VAC (+/-10%) 60 Hz


#### DIMENSIONS:

- A: 41 in (104mm)
- B: 2.75 in. (70mm)
- C. 2.6 in (66.5mm)
- D: 1.3 in. (33mm)
- E: 1.7 in. (43mm)
- F: 1.55 in. (39.4mm)
- G: 1.85 in. (46.5mm)










See TK Series Keypad installation instructions for proper checkout procedures when using the TB Series Transmitter Bases.

To set address codes: insert small screwdriver into slot on address code dials and turn until arrow points to desired letter and number code.



#### **BEFORE YOU BEGIN...**

#### **READ ALL INSTRUCTIONS**

Make sure your installation will conform to all applicable codes and requirements.

#### TEST FOR SIGNAL STRENGTH AND NOISE...

using the AR300 and AT300. It is necessary to test the installation in the actual operating environment. The amount and types of line loads may reduce the strength of the transmitted signal and/or electrical noise may cause interference with the transmitted signal. Proper installation may require additional couplers, filters or repeaters. Special coupling devices are required to allow signal to be distributed to all phases and zero-crossings in multi-phase and multi-transformer distributions.

#### IF YOU HAVE ANY QUESTIONS...

Consult your nearest Engineered System Center (ESC) for additional information.

There are no field repairable assemblies on this unit. It is covered by a two year limited warranty. If service is needed, the unit must be returned to the ESC where purchased. Contact your ESC for return details.



ADYANCED CONTROL TECHNOLOGIES, INC.

TB100 Instruction Shee

**CAUTION!** Make all connections with the POWER OFF to avoid injury to the installer or damage to the device.

**NOTE!** This transmitter is not intended as an exact replacement for standard wall switches. The white lead MUST be connected to a Neutral (not a white lead used as a line voltage "feeder" to a load).

- 1. Strip 3/4" of insulation from the ends of the conductors and make connections as shown in the Wiring Diagram.
- 2. Check connections to be sure they are tight and no bare conductors are exposed.
- 3. Make sure the load or installation does not exceed the device rating.
- 4. Set the address:

Up to 256 addresses can be selected from the module. The address consists of a Letter Code (A through P) and a Number Code (1 through 16) for Unit address. Set the address code dials as shown in the Wiring Diagram.

- 5. Install the appropriate TK Series Keypad as shown in the wiring diagram.
- 6. Install into a standard single or multi-gang electrical wall box. Use a deep box to avoid interference with box fittings and allow room for wiring connections.

Mount the device in the wallbox and install the cover plate/trim ring (Decora <sup>™</sup> or compatible style available through electrical supply vendors).

#### CHECKOUT


- 1. Restore the power.
- 2. Test Local Operation (TK Series Keypads Only):

Refer to the installation instructions for the TK Series Keypads for additional information. Push the rocker switches several times to ensure the module controls the load in response to manual control.

4. Test Remote Operation:

Using a controller, transmit "OFF", "ON", "ALL OFF", "ALL LIGHTS ON", "DIM" and "BRIGHT" commands (as appropriate for the Keypad used) to ensure the device turns the controlled load on and off in response to remote control.


5. Test for Signal Strength and Noise once again using the AR300 and AT300.



# **TK SERIES**



PCC Keypads for TB Series Transmitters



#### **BEFORE YOU BEGIN...**

#### READ ALL INSTRUCTIONS

Make sure your installation will conform to all applicable codes and requirements.

#### TEST FOR SIGNAL STRENGTH AND NOISE...

using the AR300 and the AT300. It is necessary to test the installation in the actual operating environment. The amount and types of line loads may reduce the strength of the transmitted signal and/or electrical noise may cause interference with the transmitted signal. Proper installation may require additional couplers, filters or repeaters. Special coupling devices are required to allow signal to be distributed to all phases and zero-crossings in multi-phase and multi-transformer distributions.

#### IF YOU HAVE ANY QUESTIONS...

Consult your nearest Engineered System Center (ESC) for additional information.

There are no field repairable assemblies on this unit. It is covered by a two year limited warranty. If service is needed, the unit must be returned to the ESC where purchased. Contact your ESC for return details.

#### INSTALLATION



**CAUTION!** Make all connections with the POWER OFF to avoid injury to the installer or damage to the device.

L

#### 1. Set the address:

Up to 256 addresses can be selected from the TB Series Transmitter. The address consists of a Letter Code (A through P) and a Number Code (1 through 16) for Unit address. Set the address code dials as shown in the Wiring Diagram for the TB Series Transmitters.

- 2. Slip the top of the TK Series Keypad into the notch at the top of the TB Series Transmitter. Align the pins on the TK Keypad with the sockets on the TB Transmitter and push in place.
- 3. Make sure the load or installation does not exceed the device rating.
- 4. Install the cover plate/trim ring (Decora TM or compatible style available through electrical supply vendors).

#### CHECKOUT

- 1. Restore the power.
- 2. Test Local Operation:

TK000/TK001 - One Button Keypad - One ON/OFF Command:

The ON/OFF rocker switch controls all loads (either On or Off) controlled by R Series Receivers that are set for the same complete address code as the TB Transmitter.

Depress the rocker switch several times to ensure the module properly controls the load in response to manual control.

TKO10 - One Button Keypad - One ALL ON/ALL OFF Command:

The ALL ON/ALL OFF rocker switch controls loads (either On or Off) controlled by R Series Receivers. The ALL ON command controls all RD, RF and RS Series Receivers (except those RS Receivers that do not respond to the "All Lights On" command) that are set for the SAME LETTER code as the TB Transmitter. The ALL OFF command controls ALL R Series Receivers that are set for the SAME LETTER code as the TB Transmitter.

Depress the rocker switch several times to ensure the module properly controls the load in response to manual control.

TK020/FK021 - Two Button Keypad - One ON/OFF Command, One DIM Command:

The ON/OFF rocker switch controls all loads (either On or Off) controlled by R Series Receivers that are set for the same complete address code as the TB Transmitter.

The  $\Lambda/V$  rocker switch Brightens ( $\Lambda$ ) or Dims (V) ALL loads controlled by TD Series Dimmers that are set at the SAME Letter code as the TB Transmitter.

Depress each rocker switch several times to ensure the module properly controls the load in response to manual control.

TK030/TK031 - Two Button Keypad - Two Sequenced ON/OFF Commands:

Each ON/OFF rocker switch sequentially controls all loads (either On or Off) controlled by R Series Receivers that are set for the same complete address codes (beginning and in sequence with) the address code set on the TB Transmitter.

Example: if the TB Transmitter is set on B1, the top rocker switch will control all loads set at B1 and the next rocker switch will control all loads set at B2.

Depress the rocker switch several times to ensure the module properly controls the load in response to manual control.

TK040/TK041 - Four Button Keypad - Three Sequenced ON/OFF Commands, One ALL ON/ALL OFF Command:

Each ON/OFF rocker switch sequentially controls all loads (either On or Off) controlled by R Series Receivers that are set for the same complete address codes (beginning and in sequence with) the address code set on the TB Transmitter.

Example: if the TB Transmitter is set on B1, the top rocker switch will control all loads set at B1, the second rocker switch will control all loads set at B2 and the third rocker switch will control all loads set at B3.

The ALL ON/ALL OFF (fourth) rocker switch controls loads (either On or Off) controlled by R Series Receivers. The ALL ON command controls ALL RD, RF and RS Series Receivers (except those RS Receivers that do not respond to the "All Lights On" command) that are set for the SAME LETTER code as the TB Transmitter. The ALL OFF command controls all R Series Receivers that are set for the SAME LETTER code as the TB Transmitter.

Depress the rocker switch several times to ensure the module properly controls the load in response to mapual control.

TK050/FK051 - Four Button Keypad - Three Sequenced ON/OFF Commands, One DIM Command:

Each ON/OFF rocker switch sequentially controls all loads (either On or Off) controlled by R Series Receivers that are set for the same complete address codes (beginning and in sequence with) the address code set on the TB Transmitter.

Example: if the TB Transmitter is set on B1, the top rocker switch will control all loads set at B1, the second rocker switch will control all loads set at B2 and the third rocker switch will control all loads set at B3.

The A/V rocker switch Brightens (A) or Dims (V) ALL loads controlled by TD Series Dimmers that are set at the SAME Letter code as the TB Transmitter.

Depress the rocker switch several times to ensure the module properly controls the load in response to manual control.

TK060/TK061 - Four Button Keypad - Four Sequenced ON/OFF Commands:

Each ON/OFF rocker switch sequentially controls all loads (either On or Off) controlled by R Series Receivers that are set for the same complete address codes (beginning and in sequence with) the address code set on the TB Transmitter.

Example: If the TB Transmitter is set on B1, the top rocker switch will control all loads set at B1, the second rocker switch will control all loads set at B2, the third rocker switch will control all loads set at B3 and the fourth rocker switch will control all loads set at B4.

4. Test for Signal Strength and Noise once again using the AR300 and AT300.





The ACT TU100 provides the user with a versatile, powerful transmitter that "stands alone" in performance. Versatile because it can be set up to handle load switching in many different ways. Powerful in that it can carry out an entire year of schedules unattended. Once programmed, it can stand alone and function detached from the user's computer.

The TU100 has an on-board microprocessor which functions independently after schedules have been entered. The clock/calendar allows a scheduling for time-of-day, day-ofweek and month/date. Memory is protected from power failures for up to ten years by a lithium energy source. The memory accommodates up to a year's worth of scheduling.

The TU100 accommodates switching schedules for sixteen letter codes (A-P) each of which has sixteen number codes (1-16). The PCC receivers can use any of these 256 unique codes alone or with multiple receivers set on the same code.

Features:

- 100 groups with corresponding schedules
- 4 holidays per group future release of software will have 12.
- ularly occurring ON/OFF events each day of the week. Each Group Schedule can control from 1 to 256 point addresses. Holidays provide alternate schedules for one to sixteen days.
- Auto-Adjust Mode \*

If selected, on return from a power interruption, the TU100 automatically reconciles all schedules to the current time and then carries out a "Refresh" sequence.

Overrides

Each point address may be overridden indefinately to a particular time or for a specified period.

- 50/60 Hz selectability.
- P1 Test

On command, "P1 Test" transmits continuous P1 ON and P1 OFF signals for testing signal strength with the AR300 PCC Signal Strength Indicator.

Three LED's indicate if the TU100 is powered, and whether it is sending or receiving signals.

Computer Connection

The TU100 communicates with an external computer through its RS232 connector. Using your software or ours, you have all the power of your computer to set up, retrieve and print your schedules. Once programmed, the TU100 need not be connected to the external computer.

Peripheral Connection

An RS485 connection is provided for input from ACT peripheral devices.

Modem Connection

The TU100 can be connected directly to computers by a cable of up to fifty feet in length. For longer distances, the TU100 can be connected to an auto-answer telephone modem. When used with another modem at the computer end, communication with the TU100 can be accomplished anywhere there is a telephone outlet-around the block or around the world. The TU100 communicates at 2400 baud.



#### "User Friendly" Software

ACT provides software to communicate with the TU100 from an IBM PC or PC compatible computer. It supports the set-up of all desired schedule data and can control all functions of the TU100. It enables the user to write data to the TU100 memory or read it back, store and retrieve the data on the computer's floppy disc or provide bard copy from a printer. In addition, TU100 software supports modem operation, including phone number lists for auto-dial modems. Our software adjusts as the user's level of expertise increases. For beginners, everything is completely menu-driven. As operators become more experienced, the software supports direct typing of data without walking through the menus.

The ACT TU100 Operator's Manual comes with a complete description of the user interface and applications guidelines. A technical reference manual is available for those who choose to write their own software.

#### **Applications**

#### Dedicated Control

Since the TU100 can be commanded to transmit and receive PCC signals directly, it may be permanently connected to a PC computer or mainframe and work with the computer in real time. It may also be uploaded with schedules for a day, week, month or season at a time, and left connected but "off-line" for instant "on-line" communication at any time.

#### Set It and Forget It

Because the TU100 does not need an external computer for operation, it can be programmed for up to a year (longer if no data-dependent overrides are used or yearly repeating of overrides are used or yearly repeating of overrides is desired), then disconnected from the computer and installed at any 120 volt outlet that is on its own separate circuit or that has been examined and suitably coupled, if necessary, by the installer. Its small

size allows it to fit under a counter or on a bookshelf. For reprogramming, just unplug the unit (the battery backup keeps the schedules "alive") and bring it back to the computer.

#### Distributed Control

If the PCC installation has areas of electrical isolation from the PCC signal (which may occur if the building has several electrical feeds), more than one TU100 can be used. Each isolated area can then have 256 points of control and reduce the need for signal boosting and coupling services.

#### Remote Communication

The TU100 can be outfitted with an auto-answer modem. It merely requires a nearby telephone outlet jack for the modem. In fact, if several TU100s are in use, in one facility or across an entire chain of facilities, it is possible to communicate with all of them (one at a time) from a single central computer. When an installation is dialed up, the modem answers the phone and makes available the same power and versatility of a TU100 connected directly to the computer.

The following are some suggestions of how a dealer or service operator might use the TU100 as part of a package.

#### Programming Services

Since you can program the TU100 at the computer before installation, the dealer might rent use of his computer to a customer who has none or might sell the unit to the customer pre-programmed. The customer or the dealer would then install it.

#### Remote Operation

The dealer could control the operation of one or several installations. Using a customer-or dealer-owned TU100, the dealer can monitor each installation from his central computer. In this application, it would be possible to download schedule changes as necessary. In addition, troubleshooting of the system can be accomplished over the phone line.

Versatility: The ACT TU100, when integrated with proven PCC components, offers the building operator an unmatched level of cost-effectiveness and versatility. The adaptability of the TU100 combined with the wide diversity of available PCC components, lets managers expand or upgrade facility management capabilities easily, rapidly and inexpensively.

DDC

635

# -METASYS-


# Network Control Unit, Network Expansion Unit

The Network Control Unit (NCU) is a modular, intelligent panel that is the heart of the Metasys<sup>TM</sup> Network. Use an NCU where complex, high-performance control is demanded, such as central plant heating, ventilating, and air-conditioning. The NCU also coordinates independent Application Specific Controllers (ASCs) over a communications network.

In a design breakthrough, the NCU integrates auxiliary electronic hardware into a family of modules that plug into a base frame chassis. Instead of piecing together diverse products on site, the auxiliary components are built-in at the factory. Result: lower total installation costs, greatly improved performance and efficiency, and simplified use.

The base frame also allows you to configure the panel from a selection of compatible modules. You can tailor a system precisely to the immediate application, while leaving options for easy expansion or retrofits in the future.

A companion product, the Network Expansion Unit (NEU), allows you to expand the I/O point and control loop capacity of the NCU. The NEU is a remote panel that communicates with the NCU over simple telephone wires.



Features and Benefits					
۵	Modular Design	Family of modules for economical installation, service, and future expansion.			
۵	Molded, Hardened Packaging	Meets the structural and safety standards set by metal, but vastly reduces labor costs.			
ם	Integrated Auxiliary Gear	Assembles field interfaces (pneumatic and electric) and electronic components into an integrated package for "single panel" installation savings and system reliability.			
۵	Continuously Self-Tuning Proportional-Integral-Derivative Control Algorithm	Dynamically fine tunes—or changes—control strategy to improve performance and energy efficiency. Makes managing your facility simple.			
۵	Manual Overrides / Status LED indicators	Local operator monitoring and control makes the system easy to use.			
٥	Distributed Architecture	Multiple processor and power supply architecture shares and accelerates control processing ability, dispensing with a headend and improving the system reliability.			




Figure 1: System With Two Network Control Units and One Network Expansion Unit

# Modularity for Multiple Applications

The NCU is a high-performance field panel configured from a family of compatible electronic, electrical, and pneumatic modules. This modularity allows the NCU to handle a wide array of control duties.

In small facility applications, an NCU serves as the main control panel. Its flexibility in connecting I/O points makes it the perfect controller for setting up and running all control applications. Using a combination of resident applications and custom user-written programs, the NCU operates equipment at peak efficiency while maintaining optimum occupant comfort. The NCU communicates to the building manager through local override controls, an easy to use Network Terminal, and local or remote graphic Operator Workstations and printers.

Medium and large facilities can use several NCUs, each of them controlling a portion of the facility. NCUs network together via the N1 LAN to share their information. Unlike other systems, this sharing is unlimited and allows any NCU access to any information available to any other NCU. More than just "peer-to-peer," the ease with which the N1 LAN allows complete information sharing is called Dynamic Data Access™. This is a breakthrough in Facility Management Systems, making practical the ability to totally integrate every facet of a building's operation on a single network.

By sharing all information with each other over the network, the NCUs are able to take advantage of sophisticated control algorithms to provide facilitywide optimization. Together, the NCUs make thousands of calculations—instantly—to determine the most efficient operations of such things as the chillers under the control of one NCU with the systems under the control of another.

The NCU can serve still another function: as the network operator interface. The NCU organizes information for operator reports and responds to that operator's commands and program changes. Since each NCU has total access to all NCU data on the N1 LAN, operator access through one NCU is the same as access to all NCUs.

The NCU also coordinates a local network of Application Specific Controllers (ASCs) as they perform HVAC, lighting, fire, and access control functions. In this application, the NCU provides alarm monitoring and integrated control functions for the standalone controllers.

Carrying out even one of these many functions would be a major accomplishment for many controllers, but the Metasys NCU handles them all with ease.

# Simple, Versatile System Access

The building operator has access to the entire Metasys Network through a family of operator interface devices attached to the NCU. Three ports are available for use by operator devices. One port is a standard RS-232 connection to which either an Operator Workstation or output printer may connect.

The second is dedicated to the Network Terminal—a portable or panel mounted input/output device. Like the Operator Workstation, the Network Terminal has access to all parts of the network. It is used for point monitoring, overrides, setpoint adjustments, schedule changes, and parameter modifications.

The third port houses either a dial-up modem module, or a standard RS-232 module that connects to an external modem. The modem module is a 1200 baud Hayes™-compatible autoanswer modem. This provides access to the entire network via remote monitoring by either an Operator Workstation or an output printer.

The NCU supports a multi-user environment, which means that any number of operators can be accessing information in the NCU at the same time.




Figure 2: Multi-User Environment Options

# $oldsymbol{\mathcal{A}}$ ffordable Expansion—The NEU

The flexibility and modularity of Metasys enables facility managers to choose only the equipment they need to operate their buildings.

A good example of how this modularity saves money is the Network Expansion Unit (NEU). The NEU is a panel that, in appearance and I/O functions, is identical to the NCU. It differs only in that it lacks the NCU's main processor, the Network Control Module (NCM).

The NEU is an intelligent remote panel used to expand the point I/O and control loop capacity of the NCU. It is connected to the NCU over a simple 3-wire communication trunk, the N2

Bus. Installing an NEU is often more economical—and efficient—than hardwiring dozens of points from an equipment room back to the NCU in another part of the building.

This flexibility is one reason why Metasys is the preferred FMS solution for existing facilities looking for ways to modernize and optimize their operation. It also makes Metasys the perfect choice for new construction, since the system can be precisely tailored for the immediate application while still providing easy system expansion in the future.

# A Wide Variety of Enclosures and Base


#### Frames For Total Customization


The physical design of the NCU and NEU was given as much careful thought as the rest of the Metasys system. NCUs and NEUs are configured from a family of electronic, electric, and pneumatic modules that fasten into a base frame. Each module has a magnesium and structural plastic case that protects internal electronics from electrostatic discharge during handling, or from airborne contaminants while in use. The metal case mates to a metal ground plate in the base frame, forming a continuous electromagnetic shield for all the electronics. Since each module already contains the shield it needs to perform reliably, adding future modules builds a faraday "box" on the fly, without the cost or planning necessary with traditional cabinets. It's this built-in protection that lets the NCU and NEU operate reliably, even in harsh, electrically noisy environments.

Three base frame sizes accommodate various numbers of modules and point I/O. For retrofit applications, you can mount the base frame and modules into an existing cabinet.

But for new construction, house the base frames in an attractive, thermally efficient Metasys enclosure-its transparent door allows keyed access to all operator override controls. And if you want, use a larger enclosure to house additional devices, such as application specific controllers, pneumatic cumulators, regulating valves, etc.

Subpanels, with standoffs, accommodate this mix and matched gear, and bring meters and gauges close to the transparent door for easy viewing. Use standard panels or design your own. Our Panel Unit in Poteau will even assemble and wire a custom configuration for you.





View of 2-Slot Base Frame Configuration, Inside the Enclosure

Figure 3: Enclosure With Customized and Base Frame Configurations

# Designed for Economical Installation

#### and Service

Installation accounts for 75% of the total cost of building controls. Instead of continuing the pattern of systems that individually wire diverse components, the Metasys family of modular components just plug into a standard chassis. These modules already contain the necessary relays, signal conditioners, overrides, and transducers that, individually, are expensive to wire together. By building in auxiliary functions, packaging them into modules, and joining them with plug-in connections, the Metasys base frame and modules can be installed or serviced without a single nut or screw. Changes? Simply plug in additions and replacements.

Installing an NCU or NEU is simple. First, mount an enclosure to claim wall space and land conduits for line-voltage wiring. After cables, wires, and pneumatic tubing are pulled, mount the base frame. The molded design of the base frame eliminates on-site labor by its snap-fit assembly and on-board gear; plus, its rigidity and light weight allow hanging of a complete system by one person, instead of the usual two.

Make all terminations into the NCU's fast-clamping screw terminators. Next, plug in the various modules housing the electronics, power supplies, control relays, transducers, etc. The staging of this modular installation facilitates the timely flow of material to construction projects, provides logical and obvious division of labor for the electrical and mechanical trades, and keeps the electronics off the construction site where they could get damaged or lost.

Once the panel is up and running, maintenance costs are also reduced. The enclosure's resistance to corrosion, and the material's consistent texture and color, eliminates plating and painting. Surface scratches will not mar the cover, and there is no opportunity for rust to develop.

You'll require less service because the integrated assembly builds-in reliability at the factory, instead of wiring it together in the field. And if you do need service, the modular format individually isolates and protects the components: severe misapplication interrupts service only at the easily-replaceable, low-cost module.

# Modules—The Foundation of the NCU/NEU

There are five basic types of modules that mount inside an NCU (four inside the NEU):

- Network Control Module (Only in NCU)
- Digital Control Module
- Point Multiplex Modules
- **Function Modules**
- **Power Supplies**

The following pages detail the purpose and features of each module type. Together, inside an NCU or NEU, they provide outstanding control performance and reliability in a modular design that's easy to install and service. They combine a library of proven, powerful software features with user-programmed flexibility, making the NCU and NEU cost-effective for a wide variety of custom control applications.




Figure 4: Modules of the Network Control Unit

#### Network Control Module

The Network Control Module (NCM) is the main processor in the NCU. Fully user-programmable, it is responsible for supervisory control activities for the points and control loops connected to the NCU and all NEUs and application specific controllers with which it communicates on its local buses.

You choose your NCM's configuration, whether as a standalone controller, a node on the N1 LAN working in concert with other NCMs, or as a connectivity path (bringing other systems under Metasys control or interfacing Metasys to a host system). The battery-backed memory of the NCM stores application programs, user data bases, and point histories. Every NCM includes the software features described in this section to coordinate system-wide efficiency, keeping you informed and in control while ensuring occupant safety and comfort.

#### Scheduling

Scheduling provides a long-term, system-wide means for issuing commands to points (e.g., on/off, or setpoint adjustment). Establish control on a time-of-day, day-of-week, or calendar basis. Virtually any number of commands may be scheduled per point.

Two types of weekly schedules can be defined: regular and alternate. These options give you the ability to create different on/off times for summer and winter. The NCM can automatically switch back and forth between these schedules based on either a date or an event, such as the outside temperature fluctuating around a limit. Holiday schedules can also be programmed to override the normal day-of-week programs. Up to 30 holidays, each lasting from 1 to 31 days, can be programmed up to a year in advance.

An Exception Program may also be scheduled up to a year in advance. This program overrides an individual point's weekly program on only the date for which it is scheduled. This allows those occasional changes to your normal building routines to be easily entered in advance, without the need to place your entire facility on holiday schedule.

#### Trending

Trending monitors changes in a point's value over time as a means to collect data when the system is operating properly, and to help diagnose problems in your facility.

Two different programs perform trending functions in the NCM. The first, Point History, keeps a running trend of every analog input point for the past 24 hours (one sample every 30 minutes), and a record of the last 10 changes for every binary input and all output points. For long term storage, point histories may optionally be uploaded from the NCM to an Operator Workstation. These histories are automatically available-should a building operator receive a note that an occupant's office was too hot, the operator can compare normal building operation data with the current information to diagnose problems in the facility. With this data automatically retained by the NCM, the operator can quickly resolve the problem and keep it from occurring again.

A second feature, User Trend, allows the building operator to create custom history files for selected points. For example, you may choose to trend various critical data values on a 1-minute basis and save all readings at the NCM for a week. Any number of points may be assigned to User Trend. As NCM memory becomes full, you can choose to automatically upload the oldest trends to any Operator Workstation.

#### Totalization

Capabilities of the NCM include Run Time Totalization, which keeps track of total operation hours for fans, pumps, and other equipment monitored or controlled with a binary point. Analog Totalization and Pulse Totalization monitor the consumption of chilled water, steam, gas, electricity, or other variables measured by either analog or pulse input sensors. Event Totalization counts how many times something has occurred, such as a compressor cycling on and off.

The NCM maintains totalized values on an hourly, daily, weekly, or monthly basis. For longer term storage, these totals may be automatically uploaded to an Operator Workstation at the end of each totalization period. Of course, you can assign limits to any totalized value, generating an alarm or maintenance message when the limit is exceeded.

The number of points added to the Totalization feature is limited only by available NCM memory.




Figure 5: Network Control Module

#### Demand Limiting

Demand Limiting monitors your building's electrical meters and predicts what the electrical demand will be. Should the prediction exceed a target value, the feature temporarily turns off nonessential equipment. The Load Rolling feature cycles equipment on and off to reduce electrical power consumption. Both features are coordinated such that the equipment being turned on and off is evenly distributed throughout the building, avoiding "roller coaster" effects that occur when many loads cycle at the same time. In addition, space temperatures and other comfort indicators are constantly monitored to avoid turning off equipment that might result in occupant discomfort.

Each NCU can monitor up to four independent electric meters for demand control. However, the loads to be shed when needed can be located at any NCU on the network. Using Dynamic Data Access, all NCUs in your facility work together to coordinate energy control strategies.

#### Control Processes

User-written control processes allow programming of additional application features into the NCM. With the powerful Graphic Programming Language, even a non-programmer can write specialized programs for optimal start time control, night setback, outside air economizer programs, chiller plant optimization, and more. Enter these energy-saving programs from an Operator Workstation, then load them into the NCM over the N1 LAN, or through the direct RS-232 connection.

#### Password Protection

The NCM provides Password Protection. Each operator is assigned an eight character password ID. The ID is programmed to indicate which level of command authority will be granted, and which groups of points the operator has access to. The NCM maintains five levels of command authority and 16 user-defined point groups, such as HVAC, electrical, medical gas, and security. Up to 50 user passwords may be programmed. And once again, Dynamic Data Access coordinates between all NCUs and Operator Workstations such that the password information is consistent throughout the system. This means that each operator's password will work the same regardless of where the I/O device he is using is connected to the network.

### Digital Control Module

The Digital Control Module (DCM) connects points to the NCU/NEU, and performs direct digital control of valves, actuators, variable speed drives, etc. The DCM is actually a coprocessor for the NCM, executing Proportional-Integral-Derivative (PID) loop calculations. This frees the NCM to perform duties such as scheduling, interlocks, and operation sequence. Each DCM supports up to ten universal input and ten universal output points. These points can be inputs and outputs for the DCM's PID algorithm, or they can be used independently for supervisory monitoring or control by the NCM.

You configure the PID algorithm in software, determining it as a proportional only, proportional plus integral, or proportional plus integral plus derivative controller. Applications include cascade or master/submaster control.

Furthermore, the PID algorithm is continuously self-tuning: after an initial setup, it automatically adjusts to equipment changes and load changes over time, without the need for manual recalibration. The result is service-free control with superior comfort and energy efficiency.

The PID algorithm also provides for both "softstart" and "bumpless transfer" control. This means gradually bringing chillers and fan systems into proper operating conditions at equipment start-up or manual-to-automatic changeover—without erratic cycling that can cause comfort problems, energy waste, and mechanical wear.

Building operators can monitor the performance of the PID control by use of the DCM's PID Diagnostic Trend feature. This feature samples the PID inputs and outputs every second, and makes the information available at an Operator Workstation in a graphical format. Control problems can be quickly identified and corrected.




Figure 6: Digital Control Module

#### **Function Module**

Function modules connect the sensor input and control output points to the DCM.

A variety of input function modules exist to provide signal conditioning and protection for the electronics of the DCM. Each input function module can process one—or a combination—of these signal types:

- Pneumatic, including a wide range of differential pneumatic signals
- Binary, dry contact or 120 VDC/VAC
- Voltage, 0 10 VDC or 120 VDC/VAC
- Current, 4 20 mA
- RTD Elements, both 1000 and 100 ohms

A variety of output function modules convert the electronic signals of the DCM into signals directly capable of controlling motor starters, actuators, etc. The types of output control signals include:

- Pneumatic, 1 19 PSI
- Voltage, 0 10 VDC
- Current, 4 20 mA
- Electrically isolated, if a ground reference is in the controlled device
- Binary, for 2-wire, incremental devices
- Triac, to control 24 VAC for 3-wire incremental devices
- Solenoid, for 2-position or switching control of pneumatic circuits
- Relay, including electrically maintained, magnetically latched, or momentary

The output function modules have manual override controls to allow the building operator to directly control both binary and analog outputs. These manual overrides are constantly monitored by the DCM—use of one is immediately reported to the system operator. The reporting mechanism prevents temporary overrides from becoming permanent, which could compromise energy management plans.

If the output is part of a PI or PID control loop, switching the output into "Manual" also puts the control loop into a tracking mode. The DCM monitors the controlled variable so that it can gracefully bring the output back into control when it is eventually placed back into "Automatic" mode. This feature provides a bumpless transfer of control from manual to automatic modes.

Using function modules makes the DCM compatible with a large variety of sensor and control output types, both electric and pneumatic. In addition, the robust design of the DCM electronics virtually eliminates the need for shielded cable in all but very electrically noisy environments. This means retrofit applications are cost effective for NCUs and NEUs, since most of the building's existing sensors and actuators can be reused.




Figure 7: Function Modules Plug into an NCU or NEU

#### Point Multiplex Modules

The Point Multiplex Modules (XM) economically interface points used for monitoring or supervisory control applications. They are perfect for adding point capacity in applications where the power and sophistication of a DCM is unnecessary.

Unlike the DCM, which has universal inputs and outputs characterized by function modules, each XM has a fixed input/output point configuration. All line-voltage relays, manual override controls, and other signal conditioning circuitry are housed with the electronics inside the XM. A family of XMs is available, differing only in point I/O mix. The next two charts index the capabilities of each XM.




Figure 8: The XRE of the Point Multiplex Family

#### Chart 1: Input-Only Point Multiplex Module

-	Multiplex Binary (XBN)		
Method	32 inputs monitoring: - Dry contacts - AC - DC - Frequencies of 10 Hz or less		
Indicators	32 LEDs (software configured) Point status change reports to NCM		
Applications	Monitors the status of 2-position devices such as fans, pumps, or security panels. Voltage input from a starter or pilot device can also indicate that the equipment has changed state. In addition, the XBN can detect pulses from flow meters, electric utility meters, or other pulse output devices whose frequency is 10 Hz or less.		

Chart 2: Input/Output Point Multiplex Modules

	Multiplex Relay Electrically Maintained (XRE)	Multiplex Relay Latched (XRL)	Multiplex Relay Momentary (XRM)
Method	8 inputs: Same as XBN.: 8 outputs: Electrically maintained Form C relay outputs.	8 inputs: Same as XBN. 8 outputs: Latching Form C relay outputs.	8 inputs: Same as XBN. 8 outputs: Momentary relay outputs, each with a set of Form A and Form C contacts.
Control 2-wire control Type		2-wire control	3-wire momentary control
Power Failure	The starter circuits de-energize; upon power restoration, the equipment does not immediately restart and cause a surge in demand. The user instead restarts safely and orderly via software commands.	The relay stays in the last position commanded—much like a light switch—even after loss of power.	The starter circuits de-energize; upon power restoration, the equipment does not immediately restart and cause a surge in demand. The user instead restarts safely and orderly via software commands.
Applications  Large air handler fans, large pumps, and other 2-wire devices that require a controlled startup after AC power loss.		Exhaust fans, which require minimal power and would be time consuming to manually restart; enabling circuits, for equipment under separate panel control; or other 2-wire devices that restart immediately after power returns.	Motors, pumps, pulse-on / pulse-off lighting contactors, and other 3-wire devices that require a controlled startup after AC power loss.

### Power Supply

A power supply module (one for each electronic module) regulates and filters incoming line-voltage and protects against brownout. To reduce your spare parts inventory, the same model of power supply services all electronic modules.

The advantage of separate power supplies is that they simplify service—you can turn off the power for one module while leaving all other modules in the NCU or NEU fully operational. Multiple power supplies also increase your system's reliability by eliminating noise propagation between the electronic modules.

Since these modules supply power not only to the electronic module itself, but also to all sensors, transducers, and relays connected to that module, they eliminate the need and cost of additional external supplies for the instrumentation.

Finally, the power supply is equipped with the necessary logic to stage a startup: when power switches on, the power supply protects data integrity and eliminates cycling outputs or false alarm reports.




Figure 9: Power Supply Module

Notes:

# **Specifications**

Product	Network Control Unit, Network Expansion Unit			
rioddot	Metholic Child, Nothern Expansion Com			
Power Requirements	85 - 264 VAC at 50/60 Hz			
Ambient Operating	32° to 122°F (0° to 50°C)			
Conditions	10 to 90% RH			
Ambient Storage				
Conditions				
Dimensions (H x W x D)	10" x 28" Enclosure-With-Cover (EN-EWC100-0)			
	10 in x 28 in x 8.5 in (26 x 72 x 22 cm)			
	(Fits 1-Slot Base Frame)			
	16" x 38" Enclosure-With-Cover (EN-EWC200-0)			
	16 in x 38 in x 8.5 in (41 x 97 x 22 cm)			
	(Fits 1-Slot or 2-Slot Base Frame; auxiliary gear with both configurations)			
	26" x 48" Enclosure-With-Cover (EN-EWC500-0)			
	26 in x 46 in x 8.5 in (67 x 118 x 22 cm)			
	(Fits 1-Slot, pair of 1-Slots, 2-Slot, or 5-Slot Base Frame(s); auxiliary gear with all configurations)			
Processor	Network Control Module: 80386 @ 16 mHz (NCM200); 80186 @ 8mHz (NCM100 series)			
	Digital Control Module: 80188 @ 8 mHz			
	Point Multiplex Modules: 8051 @ 11 mHz			
Agency Compliance	FCC Part 15 Class A; UL 916: CSA C22.2 #205			
Agency Listings	UL Listed and CSA Certified			



Controls Group 507 E. Michigan Street P.O. Box 423 Milwaukee, WI 53201

**FAN 635** Metasys Network Sales Resource Manual Revision Date 0492 Printed in U.S.A. -METASYS-

Issue Date 0392

# Air Handling Unit Controller

The Metasys™ Air Handling Unit (AHU)
Controller is a complete digital control system for most common air handling configurations, including single zone, variable air volume, multizone, and dual duct. The AHU Controller is designed to reduce energy expenses while keeping occupant comfort its top priority, and meets both goals admirably.

The AHU Controller has both hardware and software flexibility to adapt to many control variations in both new construction and retrofit applications. It can communicate on the Metasys N2 Bus, seamlessly providing all point and control information to the rest of the network. In a smaller facility, the AHU Controller is the perfect standalone controller. In either case, the AHU Controller, like the rest of Metasys, is simple to operate—and simply outstanding at providing efficient control and management of your facility's mechanical systems.




Figure 1: Air Handling Unit Controller

Features and Benefits				
۵	Standalone Control of Each Air Handling Unit	System reliability		
	Network Communications Over N2 Bus	Facility-wide control efficiencies and cost effective sensor sharing		
	Fully Integrated Modular Packaging	Purchase only needed parts		
	Complete Line of Compatible Sensors, Actuators, and Accessories	Total system solution		
	Interfaces to Both Pneumatic and Electric Actuators	Low cost installation for both new construction and retrofit applications		


# Modular Hardware Packaging


The AHU100 has a family of compatible components that make it ideal for field installation. The basic controller itself has three parts. The Base Module mounts easily to any surface using either a DIN rail or direct mount. It provides screw terminations for system inputs and outputs. All electronics are on a separate circuit board that plugs into the base, which provides easy servicing and protection of the electronics during initial installation. A cover attaches to the Base Module, completing the enclosure.


Additional components can be added as required to complete the control system. A Transformer Kit mounts on the same DIN rail as the Base Module, providing 24 VAC power for the entire AHU100 system, plus a convenient connection point for conduit that might be used for the line voltage wiring or low voltage sensor cables.

A Line Voltage Relay Kit added to the DIN rail provides pilot duty switched outputs. Each Relay Module contains four SPDT relays, each of which can be controlled by any of the AHU Controller's binary output points. Each relay also includes a manual Hand-Off-Auto switch for local overrides. The HOA switches can be monitored by a binary input on the AHU Controller to annunciate to an operator whenever an output has been placed in the "hand" or "off" positions.

One or more Function Module Kits can also be attached to the DIN rail. Each houses from two to four function modules, which provide the AHU Controller with direct connection to pneumatic actuators, differential pressure inputs, and pneumatic transmitters.










Figure 2: Base Module, Transformer Kit, Line Voltage Kit, Function Module

# **Components**

Described below are the Controller Enclosure Kit, Controller Board, and a family of compatible devices. The system may be configured for any combination of electric or pneumatic requirements. A DIN rail provides the mounting foundation for the components (direct wallmounting is also an option). No separate cabinet is required to house the system; however, a cabinet is available when required.

### Controller Enclosure Kit (AS-AHU101-0)

The Controller Board plugs into this housing, and it is where all field and local terminations connect (shielded cables are not required). The enclosure also provides an optically isolated

power supply for the N2 Bus and a phone jack to connect a laptop PC to the Zone Bus. The enclosure is shipped separately from the Controller Board to accommodate easier roughin procedures.

Cable connections are available for the Power Supply/Transformer Module, Line Voltage Relay Kit, and OAP Function Modules.

### Controller Board (AS-AHU102-0)

The Controller Board plugs into the enclosure. The AHU102 is temperature rated for equipment room application. Both versions process 16 inputs and 16 outputs, directly wired, as shown in Table 1.

Table 1: Sensors and Actuators

Point Type	Quantity	Characteristics
Analog Inputs	8	Jumper selectable for the following types:
,		0 to 10 VDC from any type of transmitter, range adjustable (0 to 5 VDC, 1 to 2 VDC, etc.)
		4 to 20 mA from any type of transmitter, (range adjustable)
		IAP Function Module (0 to 25 psi)
		IDP Function module (0 to 10.0 in wg, 7 ranges)
		Resistance, (1000 ohms nominal) from nickel, 1000 ohm platinum sensors, or silicon temperature sensors
Binary Inputs	8	0 to 15 VDC, dry contact, TTL compatible
Binary Outputs 10		24 VAC Triacs @ 0.5 amps Optional Relay Kit (AS-RLY100-0) available for 240 VAC @ 5 amps.
Analog Outputs	6	0 to 20 mA to any type of receiver or to the OAP Function Module. Output zero and span are adjustable.
		0 to 10 VDC (using a 500 W resistor) to any type of actuator, range adjustable.
		Optional zone bus for up to six M100CGA-2 actuators, which duplicate the analog outputs.

When connected to a Metasys Network or Metasys Companion, the Controller Board communicates to the system via the N2 Bus. Whether in a network or standalone configuration, communications to the laptop PC and digital actuators are via the Zone Bus.

## Zone Terminal (AS-ZTU100-0)

The Zone Terminal (ZT) is a person/controller interface developed as an easy-to-use controller adjustment and indication device. The ZT is designed for the user who needs a straightforward method to monitor and adjust points in an HVAC zone. The ZT plugs directly into the AHU Controller, or it may be used at any remote Zone Bus location through a Function Module Kit or Relay Kit.

The ZT can also be permanently connected to an AHU Controller by mounting the unit on a nearby wall or directly into the tower. The dedicated ZT provides alarm indication and scheduling for the controller, thereby completing the standalone AHU Controller strategy.

### Function Module Kit (AS-FMK100-0)

The Function Module Kit provides the enclosure and termination board to connect up to four, single-slot Function Modules (FMs) to the AHU. The applicable modules (ordered separately) may be from any mix of IAP, IDP, or OAP FMs (see below). Tubing connections and field terminations are simple due to the tubing ranagement trough. Multiple kits may be used per controller, limited by the controller's input/output capacity.

The kit mounts either below the AHU enclosure or remotely; when mounted remotely, a phone jack on the kit extends the controller's Zone Bus to allow easy setup and troubleshooting by the laptop PC from the remote location.

IAP 101-0 Input Pressure to Electrical Analog

The IAP is for a pneumatic transmitter interface, converting input air pressure (0 to 25 psi) to an analog signal range (4 to 20 mA). It occupies one slot in the FMK100-0 Kit, and is identical and interchangeable with IAPs used for other Metasys devices.

The separately ordered Pneumatic Connector Module (FM-PCM101) provides rough-in port connections for the tubing, then plugs into the IAP at commissioning.

IDP Series Static or Velocity Pressure Transducer

Each IDP Function Module converts static or velocity pressure (range depends on the particular IDP type) to a 4 to 20 mA analog signal. It occupies one slot in the FMK100-0, and is identical and interchangeable with IDPs used for other Metasys devices.

The separately ordered Pneumatic Connector Module (FM-PCM101) provides rough-in port connections for the tubing, then plugs into the IDP at commissioning.

OAP103-0/102-0 Analog Electrical Output to Air Pressure

The OAP is a pneumatic transducer that accepts a 0 to 20 mA analog signal from the controller and provides a corresponding air pressure output (user set from a 0 psi base). It occupies two contiguous slots in the FMK100-0. Cable connections are provided using an optional cable kit (screw type terminal connections are used when the FMK100-0 is remotely mounted).

The OAP102-0 is an insert module, attaching to the OAP103, that supplies rough-in port connections for the OAP103 tubing. The OAP102 additionally provides a local Auto/Manual switch, which can be wired back to a binary input at the controller to inform the Metasys Network of the switch status. The OAP102-0 is ordered separately.

### Relay Module (AS-RLY100-0)

The Relay Module contains four SPDT, line voltage relays (Form C), a circuit board, override switches, and a metal enclosure. Conduit knock-outs are provided on the relay enclosure for both low and line voltages. A phone jack in the module provides communications to the laptop PC by extending the Zone Bus.

The replaceable relays are UL/CSA approved and have an output rating per relay of up to 250 VAC at 5 amps AC inductive. Each relay has an LED to indicate an energized state and a Hand-Off-Auto switch to provide local control. The Hand-Off modes can be wired back to a binary input at the controller to supply manual override status information to the Metasys Network.

<sup>4</sup> Application Specific Controllers—Air Handling Unit Controller Product Bulletin

When the Relay Module is installed next to the controller, cable kits are available to connect the controller's binary outputs to the Relay Board. When the module is remote from the controller, connections are made with discrete wiring, using screw terminals.

Multiple Relay Modules may be connected to a controller. In addition, jumper connections can operate multiple relays per controller binary output (e.g., 3PDT action).

### Power Supply/Transformer Module (AS-XFR100-0)

This module is a 120 VAC to 24 VAC step down transformer, rated at 100 VA. It is UL/CSA approved and supplies power for all modules connected to the controller system.

The module enclosure includes a convenience outlet for 120 VAC, multiple conduit knock-outs for low voltage wiring, and a separate line voltage compartment and conduit knock-out for line voltage wiring. Included is a 3-pin plug to connect 24 VAC to the controller termination board.

Note:

If M100CGA-2 electric actuators are added to the configuration, they require a separate power source. All other loads, including relays, are supplied by the XFR100 (up to 84 VA).

### **Utility Enclosure Kit (AS-ENC101-0)**

The Utility Enclosure Kit houses the Zone Terminal as part of a tower configuration or other miscellaneous devices when they are necessary. The kit uses the same enclosure as that for the Relay Module and Power Supply/Transformer Module.

# Convenient Configuration Setup

The AHU Controller does not need to be programmed in the traditional sense. Instead, the control algorithms and input/output point assignments are configured with the use of the HVAC PRO software tool. The HVAC PRO runs on a laptop computer plugged directly into the AHU Controller or into a jack at the connected room sensor. These jacks are connected back to the AHU Controller over a simple twisted pair cable called a Zone Bus. Programs loaded into the AHU Controller are saved in nonvolatile EPROM memory, so there is no need to reload software after a loss of power.

Programming an AHU Controller is a simple matter of responding to a series of "yes/no" and multiple choice questions, and specifying setpoints and other parameters. No previous software programming experience is required. The AHU Controller has a library of proven control sequences and proportional-integralderivative algorithms that are automatically configured into a total system sequence-ofoperation in response to your answers to the questions.

Once configured, the AHU Controller's operating parameters, such as setpoints, gains, alarm limits, and so forth, may be changed from any Metasys operator device.

### Standalone Configuration

The controller connects to function modules, relay kits, and the Zone Terminal using discrete wiring, whether those modules are mounted adjacently or remotely. The Zone Bus accommodates daisy chain, star, or combination configurations for M100CGA-2 or laptop PC connections.

Access to the standalone AHU system is through the laptop PC or Zone Terminal, which connects to a phone jack on the controller termination board. Phone jacks are also mounted on function module kits and relay kits, extending the Zone Bus when kit locations are remote.

Using the HVAC PRO software, an operator configures, commissions, and diagnoses the entire standalone system.

Figures 3 through 6 show the arrangement of different AHU installations: an all-electric installation, an all-pneumatic installation, a combination installation, and an installation using remote function modules and relays.






Figure 3: AHU Controller Electric Installation




Figure 4: AHU Controller Pneumatic Installation




Figure 5: AHU Controller Electric/Pneumatic Installation




Figure 6: AHU Controller Installation With Remote Function Modules and Remote Relays

## **Metasys Network Configuration**

As powerful as the AHU Controller is by itself, your facility will benefit even more when AHU Controllers are part of a larger Metasys network. Each AHU Controller can connect to the Metasys N2 Bus (Figure 7). Either a Network Control Unit or Companion System can be programmed to provide added energy management and supervisory control capabilities, including optimal start, demand limiting, load rolling, run time totalization, and more.

The Metasys Dynamic Data Access™ networking software, available from the Network

Control Unit, makes all information from each AHU Controller available throughout the facility, so that it is possible, for example, to reset chiller or boiler temperatures based on the load demands of the AHU Controllers. Locally, HVAC control for the AHU is still handled by the HVAC PRO software, which interfaces with Metasys.

The full functions of the Operator Workstation and Network Terminal apply to the AHU: displaying values, setting points, and changing parameters. An optional laptop PC is the local operator interface to the AHU.




Figure 7: AHU Controller in Metasys Network

## **Metasys Companion Configuration**

The Metasys Companion connects to the AHU Controller over an independent N2 Bus (Figure 8). User access is through the Companion,

which implements built-in energy management programs throughout the devices on the bus.




Figure 8: AHU Controller in Companion System

#### Sensors and Actuators to Complete the System

The AHU Controller is matched with a family of sensors, actuators, control valves, and dampers needed to complete the control of any air handler. Its sensor inputs can accept both economical passive temperature sensors as well as industry standard 4 to 20 mA or 0 to 10 VDC transmitters. Outputs are available to control both electric and pneumatic actuators, as well as motor starters and staged heating and cooling.

## Application Flexibility

The AHU Controller can be configured in software to control single and dual path air handlers using either mixed air or 100% outside air. In addition, points unused in the air handler control scheme can be used in independent control loops, or in supervisory monitoring and control applications by the Metasys Network.

Table 2: Applications and Options

Application Classifications	Software Options
Primary Equipment Types	Mixed air single path
	Mixed air dual path
	100% outside air single path
	100% outside air dual path
Primary Control Strategies	Room control
	Room control of cooling, room reset of heating
	Return/exhaust air control, constant discharge setpoint
	Room reset of discharge setpoint
	Return air reset of discharge setpoint
	Hot/cold deck reset from coldest/warmest zone
Economizer Strategies	Dry bulb
	Enthalpy comparison
	Outside air enthalpy
	Differential outside/return air temperature
	Binary input from external economizer
	Vent and purge operation
Minimum Outside Air Strategies	Single damper with minimum position
	Separate damper—2-position
	Separate damper—minimum air flow station
Air Quality	Minimum position or min. flow reset by CO2 sensor
Preheat Configuration	2-position
•	Face & bypass valve control
	Modulated single coil
	Staged electric heat
	Circulating pump on/off logic
	Preheat lockout logic
Continued on next page	

Application Classifications (cont.)	Software Options
Heating Configuration	2-position with face & bypass control
•	Modulated single coil
	Staged electric heat
	Modulated common heating/cooling coil
	Circulating pump on/off logic
	Heating lockout logic
Cooling Configuration	2-position with face & bypass control
	Modulated single coil
	Staged DX
	Modulated common heating/cooling coil
	Circulating pump on/off logic
	Cooling lockout logic
Dehumidification	High signal select with cooling command
	Addition of dehumidification and cooling commands
Humidification	Modulated steam valve
	Staged electric heaters
Fan Start/Stop	Supply fan only
1 an Old 13 p	Supply fan and return fan
Static Pressure Control	Single supply fan
	Two speed fan
Fan Volume Matching	Single supply and single return fan, differential CFM
Unused Input/Output Control Loops	Analog input to analog output
Cincol input out part out in a series	Analog input to binary output
	Binary input to analog output
	Binary input to binary output
Unoccupied Control	Setup and setback
	Night cycle
	Morning warmup and cooldown

## More Software Capabilities

You can assign high and low alarm limits to all analog inputs, which alerts the operator at the Metasys Operator Workstation or Companion terminal when a problem occurs, such as a temperature or static pressure exceeding a safe value.

The AHU Controller also maintains a software time-of-day clock and can store back-up on/off schedules. These schedules will keep your fan systems in the proper operating mode even if there is a communication failure with the Network Control Unit or Companion controller.

## Conclusion

As either a member of the fully integrated system or as a standalone controller, the AHU Controller represents the best way to fully optimize the operation of your air handlers. It

combines the best of ease of setup and operation, flexibility of application, and precise control for comfort and energy management.

## Specifications

AHU Controller (AS-AHU101-0 Enclosure/Terminator Kit; AS-AHU102-0, Controller Board)
24 VAC, 50/60 Hz at 100 VA (from XFR100-0 Module)
32° to 122°F (0° to 50°C)
10 to 90% RH
-40° to 158°F (-40° to 70°C)
10 to 90% RH
13.3 in. x 7.9 in. x 6.9 in. (33.8 cm x 20.0 cm x 17.4 cm)
4.13 lbs (1.87 kg)
FCC Part 15, Subpart J, Class A
UL916
CSA C22.2 -205
UL Listed and CSA Certified as part of the Metasys Network
(AS-ZTU100-0)
(AS-XFR100-0)
(AS-FMK100-0)
(AS-RLY100-0)
(AS-ENC100-0)

The performance specifications are nominal and conform to acceptable industry standards. For application at conditions beyond these specifications, consult the local Johnson Controls office. Johnson Controls, Inc. shall not be liable for damages resulting from misapplication or misuse of its products.

0392

## **Unitary Controller**

The Metasys™ Unitary (UNT) Controller is an electronic device for digital control of packaged air handling units, unit ventilators, fan coils, heat pumps, and other terminal units serving a single zone or room. It can also be configured as a generic input/output device for basic point monitoring applications when used within a Metasys Network.

You can easily configure point inputs and outputs and software features to control a wide variety of HVAC equipment applications. You may use the UNT as a standalone controller, or connected to the Metasys Network through a Network Control Module (NCM) or Companion.

When connected to the Metasys Network, the UNT provides all point and control information to the rest of the network. The devices communicate through an N2 Bus. For a smaller facility, the UNT Controller can function as a standalone controller. Figure 1 illustrates the UNT Controller.




Figure 1: Unitary Controller

	Features and Benefits			
۵	Standalone Control System reliability			
٥	Network Communications Over N2 Bus	Facility-wide control efficiencies and cost effective sensor sharing		
۵	Multiple Modes of Operation for Various Occupancy Conditions	Comfort with economy		
	Built-in Control Program Library	No programming		
	Multiple Packaging Options for Both Field and Factory Installations			
	Interfaces to Both Pneumatic and Electric Actuators	Low cost installation for both new construction and retrofit applications		

## Flexible Hardware Packaging

The Unitary Controller is available in different hardware sets to suit environmental and

application needs. Use Table 1 to select the type that best suits your needs.

**Table 1: Unitary Controller Types** 

Point Type	UNT100/101	UNT110/111	UNT120/121
Ambient	32°F to 140°F	32°F to 140°F.	-40°F to 140°F
Temperature Rating	(0°C to 60°C)	(0°C to 60°C)	(-40°C to 60°C)
Analog Inputs	6	6	6
	RTD temperature elements (1000 ohm nickel, platinum, or silicon)	RTD temperature elements (1000 ohm nickel, platinum, or silicon)	RTD temperature elements (1000 ohm nickel, platinum, or silicon)
	2K ohm setpoint potentiometers	2K ohm setpoint potentiometers	2K ohm setpoint potentiometers
	0 to 10 VDC transmitters	0 to 10 VDC transmitters	0 to 10 VDC transmitters
Binary Inputs	4	4	4
	(4) Dry contacts	(4) Dry contacts	(4) Dry contacts
	(1) Momentary push button from zone sensor for temporary occupancy mode	(1) Momentary push button from zone sensor for temporary occupancy mode	(1) Momentary push button from zone sensor for temporary occupancy mode
	BI4 may be used as an accumulator input for frequencies less than 100 Hz	BI4 may be used as an accumulator input for frequencies less than 2 Hz	BI4 may be used as an accumulator input for frequencies less than 2 Hz
Analog Outputs	0/2	0/2	0/2
	0 to 10 VDC @ 10 mA	0 to 10 VDC @ 10 mA	0 to 10 VDC @ 10 mA
Binary Outputs	8/6	8/6	8/6
	24 VAC Triacs	24 VAC Triacs	24 VAC Triacs
	@ ».5 amps	@ ».5 amps	@ *.5 amps
		Low or High side common selectable	Low or High side common selectable
N2 Bus	Not Isolated	Isolated	Isolated
Zone Bus	Spade connectors at controller	Spade connectors at controller	Spade connectors at controller
	8-pin phone jack on controller	8-pin phone jack on controller	8-pin phone jack on controller
	6-pin phone jack at zone sensor	6-pin phone jack at zone sensor	6-pin phone jack at zone sensor

#### **Controller Enclosure**

The controller mounts easily to any surface using either direct mount or a controller enclosure. The common packaging for the UNT100/101 and UNT110/111 is in the AS-ENC100-0, or in an enclosure provided by the contractor.

The UNT120/121 Controller must be installed in the BZ-1000-7 Enclosure unless it is mounted within the enclosed low voltage electrical compartment of the mechanical unit being controlled.

#### -asy Monitoring and Diagnostics With the Zone Terminal

The Zone Terminal AS-ZTU100-0 (ZT) is a person / controller interface developed as an easy-to-use controller adjustment and indication device. The ZT is designed for the user who needs a straightforward method to monitor and adjust points in an HVAC zone. The ZT plugs into the Zone Sensor to communicate with a UNT Controller when used as a commissioning tool. The ZT can also be permanently connected to provide alarm indication and scheduling for a Unitary Controller.

## Convenient Configuration Setup

The UNT Controller does not need to be programmed in the traditional sense. Instead, the control algorithms and input/output point assignments are configured with the use of the HVAC PRO software tool.

The HVAC PRO runs on a laptop computer plugged directly into the UNT Controller or into a jack at the room sensor. The jack is connected back to the UNT Controller over a simple twisted pair cable called a Zone Bus. Programs loaded into the UNT Controller are saved in nonvolatile E<sup>2</sup>PROM memory, so there is no need to reload software after a loss of power.

Programming a UNT Controller is a simple matter of responding to a series of "yes / no" and multiple choice questions, and specifying setpoints and other parameters. No previous software programming experience is required.

The UNT Controller has a library of proven control sequences and proportional-integral algorithms that are automatically configured into a total system sequence-of-operation in response to your answers to the questions. Once configured, the UNT Controller's operating parameters, such as setpoints, gains, alarm limits, and so forth, may be changed from any Metasys operator device.

#### Metasys Network Configuration

As powerful as the UNT Controller is by itself, your facility benefits even more when UNT Controllers are part of a larger Metasys Network. Each UNT Controller can connect to the Metasys N2 Bus (Figure 2). Either a Network Control Unit or Companion System can be programmed to provide added energy management and supervisory control capabilities, including optimal start, demand limiting, load rolling, run time totalization, and more.

The Metasys Dynamic Data Access™ networking software, available from the Network Control Unit, makes all information from each UNT Controller available throughout the facility, so that it is possible, for example, to reset chiller or boiler temperatures based on the load demands of the UNT Controllers. Dynamic Data Access also makes sensor values, operating status, and any other parameter in the UNT Controller available to operators anywhere in your facility.




Figure 2: UNT Controller in Metasys Network

## **Metasys Companion Configuration**

The Metasys Companion connects to the UNT Controller over an independent N2 Bus (Figure 3). User access is through the Companion,

which implements built-in energy management programs throughout the devices on the bus.




Figure 3: UNT Controller in Companion System

## Application Flexibility

The UNT Controller can be configured in software to control a wide variety of packaged equipment. In addition, points unused in the control scheme can be used in supervisory monitoring applications by the Metasys Network.

The UNT Controller offers a variety of zone sensor connection options that let you select the features you—and your occupants—need. The simplest and most economical option is a solid-state sensing element wired directly to the controller. When this option is chosen, all setpoint adjustments and programming changes are made using the Operator Workstation or Network Terminal on the Metasys Network, or from the Operator Terminal on a Companion system.

An option provides the occupants in the zone the ability to adjust the setpoint to their preference, within a restricted range established by you.

The user setpoint can be overridden by you at any time using the operator interface devices or application programs in the Network Control Unit. This allows maximum energy savings, while still allowing occupants some control over their environment.

A second option uses a temporary override switch within the zone sensor package to automatically change to occupied conditions. This can further increase energy savings in individual offices or conference rooms.

Other options provide control of room lighting, as well as temperature, turning lights on or off based on the occupancy sensor, or scheduled commands issued from the network. A "boost" mode switch allows an occupant to temporarily provide extra cooling or heating. This is useful for conference rooms experiencing large heat load fluctuations.

Table 2: Applications and Options

Application Classifications	Software Option	Software Options	
Primary Equipment Types	Unit vents	ASHRAE Cycle 1 ASHRAE Cycle 2 ASHRAE Cycle 3 ASHRAE Cycle W	
	Heat pumps	Water to Air Air to Air	
	Packaged roofton	ps	
	Fan coils		
Primary Control Strategies	Room/zone contr	rol	
Economizer Changeover Strategies	Dry bulb		
	Outside air enthalpy		
	Differential outside	de/return air temperature	
	Binary input from	external economizer	
	Supervisory netw	vork command	
Mixed Air Control Strategies	Proportional outp	out to OA/RA damper actuator	
	Binary output to	Binary output to economizer actuator	
Heating Configuration	Modulated single	Modulated single coil	
	Staged electric h	Staged electric heat (2-stage max.)	
	Modulated comm	non heating/cooling coil	
	Reversing valve	logic	

Application Classifications (Cont.)	Software Options	
Cooling Configuration	Modulated single coil	
	Staged DX (2-stage max)	
•	Modulated common heating/cooling coil	
	Reversing valve logic	
Fan Start/Stop	Continuous Operation	
· ·	Cycled with call for heating/cooling	
Lighting Control	On and off outputs to lighting relay in conjunction with Occ/Unocc mode.	
Unoccupied Control	Setup and setback	
•	Morning warmup and cooldown	

## More Software Capabilities

The UNT Controller has additional capabilities to help manage your facility. You can assign high and low alarm limits to all analog inputs, to alert an operator at the Metasys Operator Workstation or Companion terminal when a problem occurs, such as a zone or mixed air temperature exceeding comfort or safety values.

The UNT Controller also maintains a software time-of-day clock and can store backup on/off schedules. These schedules will keep your fan systems in the proper operating mode even if there is a communication failure with the Network Control Unit or Companion controller.

## Conclusion

As either a member of the fully integrated system, or as a standalone controller, the UNT Controller represents the best way to fully optimize the operation of your HVAC equipment. It combines the best of ease of setup and operation, flexibility of application, and precise control for comfort and energy management.

## Specifications

Product	AS-UNT100-0 / AS-UNT101-0 AS-UNT110-0 / AS-UNT111-0			
Ambient Operating	32° to 140°F (0° to 60°C)			
Conditions	10 to 90% RH			
Dimensions	6.5 in. x 6.4 in. x 2.0 in. (165 x 163 x 51 mm) without enclosure 6.8 in. x 7.3 in. x 4.7 in. (173 x 185 x 119 mm) with the AS-ENC100-0 Enclosure			
(H x W x D)				
Product	AS-UNT120-0 / AS-UNT	121-0		
Ambient Operating	-40° to 140°F (-40° to 60	)°C)		
Conditions	10 to 90% RH			
Dimensions	6.5 in. x 6.4 in. x 2.0 in.	(165 mm x 163 mm x 51 mm) without	enclosure	
(H x W x D)	10.2 in. x 9.8 in. x 3 in.	10.2 in. x 9.8 in. x 3 in. (259 mm x 248 mm x 76 mm) with the BZ-1000-7 Enclosure		
Ambient Storage	-40° to 158°F (-40° to 70	0°C)		
Conditions	10 to 90% RH	10 to 90% RH 24 VAC, 50/60 Hz		
Power Requirements	24 VAC, 50/60 Hz			
Shipping Weight	1.4 lbs (0.64 kg)			
Agency Compliance	CSA C22.2 No. 205	FCC Part 15, Subpart J, Class A	IEEE 446	
	IEEE 472	IEEE 518	IEEE 587 Category A	
	UL 916	NEMA ICS 2, Part 2-230	VDE 0871 Class B	
Agency Listings	UL Listed and CSA Certified as part of the Metasys Network			
Accessories				
(Order Separately)				
Zone Terminal	(AS-ZTU100-0)			
Enclosure Kit	(AS-ENC100-0) for UNT			
	(BZ-1000-7) for UNT12	0/121		

The performance specifications are nominal and conform to acceptable industry standards. For application at conditions beyond these specifications, consult the local Johnson Controls office. Johnson Controls, Inc. shall not be liable for damages resulting from misapplication or misuse of its products.



Controls Group 507 E. Michigan Street P.O. Box 423 Milwaukee, WI 53201 FAN 635 Metasys Network Sales Resource Manual Revision Date 0392 Printed in U.S.A.

0692

-METASYS-

Application Specific Controllers Product Bulletin Issue Date

## Variable Air Volume Controller

The Variable Air Volume (VAV) Controller is an electronic device for digital control of single duct, dual duct, fan powered, and supply/exhaust VAV box configurations. Along with the capability of standalone control of the VAV box, the controller can also integrate the control of the room or zone baseboard heat and lighting logic. You may use the VAV as a standalone controller, or connected to the Metasys™ Network through a Network Control Module (NCM) or Companion.

When connected to the Metasys Network, the VAV provides all point and control information to the rest of the network. The devices communicate through an N2 Bus. The VAV Controller can also function as a standalone controller. Figure 1 illustrates the VAV Controller.




Figure 1: Variable Air Volume Controller

Features and Benefits					
☐ Standalone control System reliability					
Network communications over N2 Bus	Facility-wide control efficiencies and cost effective sensor sharing				
Multiple modes of operation for various occupancy conditions	Comfort with economy				
☐ Built-in control program library No programming					
Multiple packaging options for both field and factory installations	Installation flexibility				

## Flexible Hardware Packaging

The Variable Air Volume Controller can be configured to match most applications found in todays fast evolving VAV marketplace. The VAV is available in two different models which vary only by their output point configuration,

allowing you to economically select a controller to match the VAV box application. In addition, cable kits are available to make connection between the controller and the damper actuator and velocity pressure transducer easy.

Table 1: Variable Air Volume Controller Types

POINT TYPE	VAV100	VAV101
Ambient Temperature Rating	32°F to 140°F	32°F to 140°F
	(0°C to 60°C)	(0°C to 60°C)
Analog Inputs	6	6
	RTD temperature elements (1000 ohm nickel, platinum, or silicon)	RTD temperature elements (1000 ohm nickel, platinum, or silicon)
	2 K ohm setpoint potentiometers	2 K ohm setpoint potentiometers
	0 to 10 VDC transmitters	0 to 10 VDC transmitters
Binary Inputs	4	4
	(4) Dry contacts	(4) Dry contacts
	(1) Momentary push button from zone sensor for temporary occupancy mode	(1) Momentary push button from zone sensor for temporary occupancy mode
Analog Outputs	0	2
		0 to 10 VDC @ 10 mA
Binary Outputs	8	6
	24 VAC Triacs	24 VAC Triacs
	@ *.5 amps	@ *.5 amps
Zone Bus	spade connectors at controller	spade connectors at controller
	8 pin phone jack on controller	8 pin phone jack on controller
	6 pin phone jack at zone sensor	6 pin phone jack at zone sensor

#### Controller Enclosure

The controller mounts easily to any surface using either direct mount or a controller enclosure. The common packaging for the VAV

Controller is in the AS-ENC100-0, or in an enclosure provided by the VAV box manufacturer.

## Easy Monitoring and Diagnostics with the Zone Terminal (AS-ZTU100-0)

The Zone Terminal (ZT) is a person/controller interface developed as an easy-to-use controller adjustment and indication device. The ZT is designed for the user who needs a straightforward method to monitor and adjust points in an HVAC zone. The ZT plugs into the TE-6410 Metastat™ to communicate with or perform balancing of a VAV box system.

## Convenient Configuration Setup

The VAV Controller doesn't need to be programmed in the traditional sense. Instead, the control algorithms and input/output point assignments are configured with the use of the HVAC PRO software tool.

The HVAC PRO runs on a laptop computer plugged directly into the VAV Controller or into a jack at the room sensor. The jack is connected back to the VAV Controller over a simple twisted pair cable called a Zone Bus. Programs loaded into the VAV Controller are saved in nonvolatile E<sup>2</sup>PROM memory, so there is no need to reload software after a loss of power.

A second option allows you to load the configuration from the laptop via the N2 Bus. This option speeds up the initial loading and commissioning process prior to performing the final balancing procedures.

Programming a VAV Controller is a simple matter of responding to a series of "yes-no" and multiple choice questions, and specifying setpoints and other parameters. No previous software programming experience is required.

The VAV Controller has a library of proven control sequences and proportional-integral algorithms that are automatically configured into a total system sequence-of-operation in response to your answers to the questions.

Once configured, the VAV Controller's operating parameters, such as setpoints, gains, alarm limits, and so forth, may be changed from any Metasys operator device.

#### Factory Mounting Relationships

The original equipment manufacturers set up the VAV control system for factory mounting. This benefits you by lowering the overall cost of the installation.

#### Metasys Network Configuration

As powerful as the VAV Controller is by itself, your facility will benefit even more when VAV Controllers are part of a larger Metasys Network. Each VAV Controller can connect to the Metasys N2 Bus (Figure 2). Either a Network Control Unit or Companion system can be programmed to provide added energy management and supervisory control capabilities, including optimal start, demand limiting, load rolling, run time totalization, and more.

The Metasys Dynamic Data Access™ networking software, available from the Network Control Unit, makes all information from each VAV Controller available throughout the facility, so that it is possible, for example, to reset chiller or boiler temperatures based on the load demands of the VAV Controllers. Dynamic Data Access also makes sensor values, operating status, and any other parameter in the VAV Controller available to operators anywhere in your facility.




Figure 2: VAV Controller in Metasys Network

## Metasys Companion Configuration

The Metasys Companion connects to the VAV Controller over an independent N2 Bus (Figure 3). User access is through the

Companion, which implements built-in energy management programs throughout the devices on the bus.




Figure 3: VAV Controller in Companion System

## Application Flexibility

The VAV Controller can be configured to match most applications found in today's rapidly evolving VAV marketplace. The VAV-10n series is packaged for factory mounting by original equipment manufacturers in their panels. The ENC100 enclosure is used when an enclosure is not provided by the original equipment manufacturer. In addition, points unused in the control scheme can be used in supervisory monitoring and control applications by the Metasys Network.

The VAV Controller offers a variety of zone sensor connection options that let you select the features you – and your occupants – need. The simplest and most economical option is a solid-state sensing element wired directly to the controller. When this option is chosen, all setpoint adjustments and programming changes are made using the Operator Workstation or Network Terminal on the Metasys Network, or from the Operator Terminal on a Companion system.

An option provides the occupants in the zone the ability to adjust the setpoint to their preference, within a restricted range established by you. The user setpoint can be overridden by you at any time using the operator interface devices or application programs in the Network Control Unit. This allows maximum energy savings while still allowing occupants some control over their environment.

A second option uses an occupancy sensor to automatically or manually setback or setup zone temperatures when no one is around. This can further increase energy savings in individual offices or conference rooms.

Other options provide for control of room lighting as well as temperature, turning lights on or off based on the occupancy sensor or scheduled commands issued from the network. A "Boost" mode switch allows an occupant to temporarily provide extra cooling or heating, which is useful for conference rooms that experience large heat load fluctuations.

Table 2: Applications and Options

Application Classifications	Software Options	
Primary Equipment Types	VAV Box Single Duct Dual Duct Fan Powered or Assisted Supply/Exhaust	
Primary Control Strategies	Pressure Dependent Pressure Independent Constant Volume Auto Zero of Flow Transducers	
Box Heat Configuration	Incremental Time Based Proportional (3 Stages Maximum)	
Baseboard Heat Configuration	Incremental Time Based Proportional (1 Stage)	
Cooling Configuration	Incremental Output to Damper Actuator	
Fan Configurations	Parallel, Temperature Setpoint Parallel, CFM Setpoint Series, On-Off Control Series, Proportional Control	
Lighting Control	On and off outputs to lighting relay in conjunction with Occ/Unocc mode	
Occupied Selections	Occupied/Unoccupied, Standby, Shutdown, Boost Control, Morning Warm-Up, and Cooldown	

## More Software Capabilities

The VAV Controller has additional capabilities to help manage your facility. For example, the velocity sensor input to a pressure independent system can be automatically calibrated to its zero flow point once per day to ensure the VAV Controller maintains accuracy at low flows. You can also set up this feature to be implemented on a time schedule through the N2 network so that a critically controlled zone's airflow is not interrupted during occupied conditions.

You can assign high and low alarm limits to all analog inputs to alert an operator at the Metasys Operator Workstation or Companion terminal when a problem occurs, such as a zone or mixed air temperature exceeding comfort or safety values.

The VAV Controller also maintains a software time-of-day clock and can store backup on/off schedules. These schedules will keep your local zones in the proper operating mode even if there is a communication failure with the Network Control Unit or Companion controller.

## ( conclusion

As either a member of the fully integrated system, or as a standalone controller, the VAV Controller represents the best way to optimize the operation of your HVAC equipment. The VAV Controller combines the best of ease-ofsetup and operation, flexibility of application, and precise control for comfort and energy management.


## Specifications

Product	AS-VAV100-0 / AS-V	/AV101-0		
Ambient Operating	32° to 140°F (0° to 60°C)			
Conditions	10 to 90% RH 6.5 in. x 6.4 in. x 2.0 in. (165 x 163 x 51 mm) without enclosure			
Dimensions				
(H x W x D)	6.8 in. x 7.3 in. x 4.7	6.8 in. x 7.3 in. x 4.7 in. (173 x 185 x 119 mm) with the AS-ENC100-0 enclosure		
Ambient Storage	-40° to 158°F (-40° to	-40° to 158°F (-40° to 70°C)		
Conditions	10 to 90% RH	10 to 90% RH		
Power Requirements	24 VAC, 50/60 Hz at 40 VA (per typical system) 1.4 lbs (0.64 kg)			
Shipping Weight				
Agency Compliance	CSA C22.2 No. 205	FCC Part 15, Subpart J, Class A	IEEE 446	
	IEEE 472	IEEE 518	IEEE 587 Category A	
	UL 916	NEMA ICS 2, Part 2-230	VDE 0871 Class B	
Agency Listings	UL Listed and CSA	Certified as part of the Metasys Netwo	rk	
Accessories				
(Order Separately)				
Zone Terminal	(AS-ZTU100-0)			
Enclosure Kit	(AS-ENC100-0)			
Zone Sensors	(TE-6410 Series)			
Damper Actuator/Velocity Sensor Package	(ATP-2040 Series)			
Controller/Velocity Sensor Package	(AS-VAVDPT Series)			

The performance specifications are nominal and conform to acceptable industry standards. For application at conditions beyond these specifications, consult the local Johnson Controls office. Johnson Controls, Inc. shall not be liable for damages resulting from misapplication or misuse of its products.



Controls Group 507 E. Michigan Street P.O. Box 423 Milwaukee, WI 53201 FAN 635 Metasys Network Sales Resource Manual Printed in U.S.A.



...Is In the Palm of Your Hand!

H-90

# Integrate Dissimil

## **UNITY from Electronic Systems USA**

The Multi-Vendor Leader

If you're locked into a single supplier for your facility's automation systems, or struggling with a variety of equipment that won't communicate, you are not alone!

If you're coping with restricted access to parts, information and support, or being totally eliminated from the competitive bid process, there is a solution!

If you're still waiting for an answer like BACnet, you don't have to wait any longer!

The Future of Building Automation—Today!

As the nation's leading multi-vendor supplier of products and services to the building automation industry, Electronic Systems USA will put you in complete control of your facility—with a revolutionary product called UNITY.

UNITY is a powerful CPU replacement designed to fully integrate your entire facility—HVAC, Fire/Life Safety, Security and more—into a single, PC based system. UNITY offers you the flexibility and ease of operation to maximize your resources in today's tough economy!

#### A New Kind of Freedom

TY is the only true multi-vendor platform available to Honeywell a. Johnson Controls system owners.

UNITY features an exclusive Open Communication Platform. Cumbersome programming languages are virtually eliminated, and major manufacturers' HVAC, Fire/Life Safety and Security equipment are seamlessly integrated into a single operating system.

UNITY also allows full integration of the latest advanced Direct Digital Control (DDC) and addressable fire alarm products.

Leading Edge Technology

UNITY features a Graphic User Interface for easy access and control with minimal computer experience. UNITY runs under IBM's OS/2 multi-tasking operating software, making it the only reliable alternative in mission-critical applications.

UNITY is UL Listed for fire and security applications and operates on standard, off-the-shelf PC equipment. UNITY supports Arcnet, Ethernet, Token Ring and other LAN configurations.


From the World's Tallest Office Building to Maximum Security Facilities

UNITY is currently operating in some of the most prestigious facilities in the United States and abroad, replacing front-end equipment in highly complex and sophisticated Honeywell and Johnson Controls automation systems.

**UNITY** is Total Facility Management

Through UNITY, you have the power to integrate dissimilar systems and choose the original equipment manufacturers that best meet your ity's needs. The technology is available today from Electronic

Systems USA!



# r Systems-and Restore Your Fre



## edom of Choice!



## The Logical Group Tree™

UNITY features another quantum leap in facility management technology —The Logical Group Tree™. Designed and developed exclusively by Electronic Systems USA, The Logical Group Tree™ maps all building control operations—in extraordinary detail. This unique approach provides a simple, logical way to organize, monitor and control your combined building management systems. By dividing your entire facility into functional groups in logical progression, you can operate at peak efficiency.


- 1. The Logical Group Tree™ is instantly accessed by a click of a mouse. A typical "tree" consists of buildings within a complex, floors within the buildings, and progresses to individual system components such as chillers, air handling units, security doors, fire devices, etc.
  - doors, fire devices, etc.

    2. Simply point to the building you wish to access, click on it, and a structural drawing automatically
  - 3. Your next click selects the desired floor plan. At any time, you can move directly to any of the tree's branches—or continue viewing the selected floor. UNITY allows both graphical penetration and random selection of graphics. This saves valuable time in emergency situations.
    - 4. Continued graphical penetration quickly selects the desired piece of equipment or field point, and live data is displayed.
    - 5. One final click of the mouse displays a sequence of operation in text form. Instant information is now available to you, as well as field technicians and building managers.


#### Custom Design and Engineering

Every UNITY system is designed to be site-specific. Upon completion of a detailed site inspection, a hand-picked team of applications engineers will customize every system to meet and exceed detailed 'ity requirements. Each UNITY system is engineered complete .... customized graphics and specialized applications. Electronic Systems USA is committed to complete customer satisfaction. We are a national company with national resources, a dedicated sales

staff, and a strong technical infrastructure to support our growing network of branches







#### Turn-Key Installation

Installing UNITY is a simple and smooth operation. All database conversion takes place prior to installation, keeping system downtime to an absolute minimum. Electronic Systems USA performs built-in system training

site to ensure complete operc comfort with every UNITY installed.



Electronic Systems USA also holds a national listing under the Burglary and Fire Alarm Service Certification Program. This authorizes us to perform inspections of existing systems and issue UL Certificates of Compliance for applicable NFPA 72 series standards.



#### Comprehensive Training

We have been supporting system owners with some of the finest training in the industry since 1979. Our qualified instructors offer a customized, "hands-on" approach to the programming and applications of every UNITY system. Instruction is available on-site, or at Electronic Systems **USA's Corporate Training Center** in Louisville, Kentucky.



## **Quality Parts**

**Electronic Systems USA** maintains an extensive inventory of the finest quality new and reconditioned parts to maintain your HVAC, Fire/Life Safety and Security sysns. Our extensive



entory offers you a valuable source for parts that may no longer be available from the original manufacturer. Our exclusive two-year warranty on all reconditioned parts proves that we stand behind what we sell! Call toll free 1-800-765-7773 for pricing and delivery.

## Superior Products Backed by a Proven Company

Our accomplishments in multivendor applications have placed UNITY in some of the most prestigious buildings in the world. We offer superior automation products that will help you maintain your building's systems today, and well



into the future. Every UNITY system installed receives specific off-site system diagnosis and software support from a veteran team of dedicated product support engineers.

## The Nation's Leader in Multi-Vendor **Systems Integration**

Put the nation's leading supplier of multi-vendor products and services to work for you. Electronic Systems USA—integrating dissimilar systems, and restoring your freedom of choice!

## **Sales Centers**



Atlanta 3835 Presidential Pkwy. Suite 108 Atlanta, GA 30340 (404) 455-6100



Detroit 39555 Orchard Hill Place Dr. Suite 145 Novi, MI 48375 (313) 348-9292



Chicago 4413 Roosevelt Rd. Suite 110B Hillside, IL 60162 (708) 449-3334



Los Angeles 5900 S. Eastern Ave. Suite 152 Commerce, CA 90040 (213) 726-9821



San Francisco 7011 Koll Center Pkwy. Suite 270 Pleasanton, CA 94566 (510) 426-6811



Boston One Cabot Place Stoughton, MA 02072 (617) 344-8997



New York/ **New Jersev** 51 Commerce St. Springfield, NJ 07081 (201) 379-4833



Baltimore/ **Washington DC** 2613 Cabover Dr. Suite 105 Hanover, MD 21076 (410) 553-0317



Louisville 9410 Bunsen Pkwv. Louisville, KY 40220 (502) 495-6700

## **Service Centers**

Cincinnati 4790 Red Bank Rd., Suite 221

Cincinnati, OH 45227

(513) 271-2533

Charlotte 3553 N. Sharon Amity, Suite 201 Charlotte, NC 28205

(704) 531-8780

Cleveland 333 Babbitt Rd., Suite 303

Euclid, OH 44123

(216) 289-6358

St. Louis

2539 Williams Creek Rd. High Ridge, MO 63049 (314) 677-5435

Pittsburgh P.O. Box 711 Imperial, PA 15126 (412) 456-7447

**Dallas** 

P.O. Box 1636 Coppell, TX 75019 (214) 393-3473



Electronic Systems USA, Inc.

9410 Bunsen Parkway, Louisville, KY 40220

(800) 765-7773 • (502) 495-6700

FAX: (502) 495-2546



stems USA Corporate Headquarters, Louisville, KY

ogy, Trane and IBM OS/2 are registered trademarks or ms USA products and services are not sponsored or


Honeywell, Johnson Controls, Control Systems Internation service marks of companies other than Electronic Systems JISA approved by those companies, and Electronic Systems JISA

Literature Type	Product Brief
Literature Number	LIT-PB-001
Date	January 1992
Supersedes	New

- Integrates field equipment from a variety of manufacturers.
- Utilizes IBM's latest OS/2 Multi-Tasking operating system.
- Totally graphic based operator interface requires no computer experience.
- Energy Management, Fire/Life Safety and Security integrated into one manageable system.
- MEA, CSFM and UL listed 864/1076 UOJZ for fire and security applications.
- Expandable with the latest Direct Digital Control (DDC), Intelligent Access Control and Analog Fire systems.
- Exclusively features the "Logical Group Tree," a technological breakthrough developed by Electronic Systems USA.
- Operates on standard off-the-shelf PC hardware and software.



#### UNITY, The Multi-Vendor Platform



California State Fire Marshall Listed New York City MEA Listed

## **UNITY, The True Multi-Vendor Solution**

## Another First From Electronic Systems USA

UNITY is the latest in a family of PC based automation front-ends from the recognized leader in Multi-Vendor solutions. UNITY is the only Multi-Vendor software based system that can successfully integrate Fire/Life Safety, Security and Energy Management applications. UNITY is UL Listed under category 864/1076, along with MEA and CSFM for Fire/Life Safety, Security and Energy Management.

## **Bringing Leading Edge Technology To Your Facility**

While the automation industry awaits a solution from BACNET to solve their multi-vendor dilemma, UNITY is already installed and operational in some of the most prestigious buildings in the United States and abroad.

UNITY combines a powerful 80386 or 80486 based personal computer with IBM's advanced Operating System/2 (OS/2) multi-tasking system. The combination offers you the most powerful and flexible front-end replacement available today.

#### What Does Multi-Vendor Mean To You?

UNITY's Multi-Vendor capabilities mean freedom. Freedom to break away from the sole-source lock-in associated with many manufacturer's field equipment. Multi-Vendor also means power. By integrating several manufacturers' systems for Direct Digital Control, Intelligent Access Control and Addressable Fire applications into one system, UNITY puts the power of choice back in your hands.

## A Proven System Backed By A Proven Company

UNITY proudly boasts a growing list of satisfied users. Selected by many outstanding Fortune 100 corporations, UNITY is operational in some of the most prestigious buildings around the world. The list includes the world's tallest office building, world headquarters of America's largest telecommunications corporation, as well as the tallest multiple-building hotel/office complex in the United States.

UNITY is currently controlling a wide variety of facilities including government buildings, hospitals, universities, commercial buildings and nuclear power plants. Electronic Systems USA has proven its expertise in system upgrades and Multi-Vendor solutions by installing its systems in hundreds of buildings throughout the world.

# Electronic Systems USA, Inc. — The Recognized Leader in Third Party Building Automation Maintenance, Products and Support


Call Today for Your FREE 8-Page Color Brochure 1-800-765-7773

.ms USA, Inc. Electronic Systems USA

# Electronic Systems USA Leads the Multi-Vendor Charge!

Electronic Systems USA, the nation's leading supplier of multi-vendor products and services in the building automation

industry, specializes in integrating the latest technology with your existing system, thus protecting your original investment.



#### Automation Upgrade Services.

Electronic Systems USA can integrate major manufacturers' HVAC, Fire/Life Safety and Security systems into a single PC-based front end. Plus integrate the latest in advanced Direct Digital Control (DDC), distributed card access and addressable fire alarm products. This leading edge technology is only available through a revolutionary product called UNITY. A PCbased front end replacement, UNITY features a Graphic User Interface, eliminating cumbersome programming languages. UNITY is UL listed for fire and security applications and runs under IBM's OS/2 multi-tasking operating system, supporting Arcnet, Ethernet, Token Ring and other LAN configurations, as well as DOS and Windows applications.

#### **Customized Maintenance Services.**

Through the exclusive Premier-Flex program, system owners can tailor a service agreement to meet the specific needs of their facility. Preventive maintenance, 24-hour, 7-day emergency response, and hardware and software system support services are available. Electronic Systems USA holds a national listing with Underwriters Laboratories, Inc., and can issue UL Certificates of Compliance for NFPA 72 series standards.

#### Component and Repair Services.

Electronic Systems USA maintains a large inventory of new and reconditioned parts for major manufacturers' automation systems. And a state-of-the-art circuit board repair lab with full diagnostic testing equipment. All repaired parts are backed by an exclusive 2-year warranty—twice the standard industry warranty.

#### Comprehensive Training.

Electronic Systems USA has been supporting system owners with the finest third party training in the industry since 1979. Qualified instructors offer a customized, "hands-on" approach to maintenance and programming courses. Instruction is available on-site, or at the Corporate Training Center in Louisville, Kentucky.

Find out how you can protect your original investment! Call Electronic Systems USA today at (800) 765-7773.



## Electronic Systems USA, Inc.

The Multi-Vendor Leader

## **Profile**


McDonnell Douglas Aerospace Center

## McDonnell Douglas Aerospace Exceeds Energy Savings Projections by 81%

McDonnell Douglas Aerospace, headquartered in Huntington Beach, California, is a three and a half million square foot, multibuilding facility housing its Space and Defense Systems business unit. The nation's leading defense contractor relies on the proven qualities of excellence, innovation and experience as they continue to meet the challenges of the 21st century, bridging the gap between concept and hardware to establish the world's future in space.

As the entire country felt the pinch of a declining economy in 1991 and 1992, McDonnell Douglas Aerospace began looking for ways to reduce spending. The facility's HVAC systems came under immediate scrutiny.

The facility's main complex houses 60 air handling units that were operating 24 hours per day. The main complex was originally controlled by a Honeywell Delta 1000 system. In a separate 8-story office building, two stand-alone Honeywell Excel DDC (direct digital control) panels and a hand-



held display device were used for monitoring and calculating the building's field data.

The configuration of equipment at McDonnell Douglas presented specific problems. The McDonnell Douglas staff struggled with the system's difficult programming language (CIL), and spent thousands of dollars trying to keep system calculations accurate and equipment operational. They had an annual maintenance contract with Honeywell, but it did not cover the cost of emergency service or spare parts for the entire system.

The facility began its mission to bring energy spending under control by researching available solutions for modernizing the McDonnell Douglas Aerospace automation systems. Ultimately, Electronic Systems USA, Inc., and their front-end replacement product, UNITY, was selected to accomplish the modernization. UNITY provided McDonnell Douglas with the optimum solution by upgrading the current system without replacing the field equipment, such as data gathering panels, wiring, sensors, etc. UNITY also provided a multivendor, PC based platform for controlling the facility.

Financing for the project was secured by presenting some impressive figures to demonstrate a three month return on investment:

- With the UNITY system, Honeywell's maintenance agreement could be reduced to \$25,000 per year.
- Labor and overtime could be reduced substantially.
- McDonnell Douglas Aerospace could realize \$129,000 per year in energy savings.
- A \$20,000 rebate could be realized through the Utility Rebate Program of Southern California Edison.

UNITY was installed to replace the Delta 1000 front-end, and the Excel panels in the 8-story building were replaced with new Direct Digital Control panels and tied into the UNITY system. System operators were then able to program their own energy management strategies, such as an Optimum Start/Stop program to maximize usage of the 60 air handling units during peak hours. Integrating the field points from the 8-story building into the central system also simplified control and monitoring strategies.

One year after the UNITY system was installed, the engineering staff proudly reported that McDonnell Douglas Aerospace had exceeded its original energy savings projections:

- As a result of UNITY's ease of programming and operation, the Honeywell maintenance agreement of \$38,000 per year was totally eliminated.
- Labor and overtime expenditures were reduced by \$135,000 per year.
- The energy savings realized were over \$233,000 per year, netting a rebate of greater than \$31,000 from Southern California Edison.

Retrofit of the McDonnell Douglas Aerospace facility with UNITY from Electronic Systems USA, along with meticulous planning and implementation netted the following:

- · A 60-day payback
- 81% greater energy savings than originally projected
- A utility rebate that exceeded projections by 59%

The retrofit at McDonnell Douglas Aerospace was not only completed on budget, it also realized outstanding labor savings and generated tremendous energy savings.



McDonnell Douglas
exceeded their original
savings projection by 81%
within one year of the
UNITY installation



UNITY has the ability to integrate not only dissimilar systems (Delta 1000 and Excel), but also different manufacturers' equipment (Honeywell, Johnson Controls, Landis & Gyr Powers, Control Systems International, Edwards Systems Technology, Trane, etc.) into a PC based operating system. This presents a major advantage in freeing a facility from obligation to the original equipment manufacturer for upgrades, parts and service, and also opens up opportunity for competitive bids on future expansions. UNITY features a Graphic User Interface, which allows easy access and control with minimal computer experience. The system eliminates CIL programming and replaces it with English language for energy management programming to implement strategies. UNITY operates on standard offthe-shelf PC equipment, which provides many avenues for product support.




## Electronic Systems USA, Inc.

The Multi-Vendor Leader

## **Profile**

Renaissance Center, Detroit

## UNITY Gives Renaissance Center Freedom of Choice



Through the vision of Henry Ford II, Renaissance Center is a six tower complex centered around the tallest hotel in North America, a 73-story Westin Hotel. Renaissance Center incorporates more than five and a half million square feet of commercial and hotel space. The complex requires one of the largest commercial central cooling plants in the world, with over 14,000 tons of cooling capacity.

Operating a facility of this magnitude posed serious problems as the installed systems began to age. The original building automation system installed at Renaissance Center was a combination of Honeywell Delta 2000, Delta 1000 and Excel DDC equipment. The 8,000 field points comprising Renaissance Center utilized the most complex combination of Honeywell control interpreter language (CIL) programming ever installed to control HVAC applications. Extreme difficulty in working with the CIL programming software prohibited integrating new energy management strategies required to operate efficiently. The highly customized system required Renaissance Center to rely solely on Honeywell for system expansions, eliminating a competitive bid situation.

Faced with outdated technology, and virtually no software documentation to support the highly customized system, Renaissance Center, along with the outside accounting and finance firm, Coopers and Lybrand, conducted an expansive study to upgrade the building's automation systems with state-of-the-art technology.

After a 2-year evaluation, Electronic Systems USA was selected for the upgrade, on the basis of their outstanding reputation as a multi-vendor systems integrator. Renaissance Center selected Electronic Systems USA and their powerful, PC based front-end replacement, UNITY, for their ability to offer proven, cost effective solutions.

The initial project involved integrating the existing Honeywell equipment (Delta 2000, Delta 1000 and Excel) into a single operating system. Electronic Systems USA successfully accomplished the task by replacing the old generation front-end with a UNITY system capable of full protocol communication to the field. This type of architecture allowed the field equipment to remain in place and communicate to the new front-end. Careful planning and execution of the installation resulted in minimal downtime for Renaissance Center.

The second stage of the project involved a retrofit of the Renaissance Center chiller plant. The chiller plant presented an interesting challenge, since virtually all controls were operated manually from the original installation. Electronic Systems USA engineers worked extensively with Renaissance Center personnel to achieve their goals of state-of-the-art equipment, smooth installation and budget adherence.

The chiller plant was retrofitted with automated controls and tied into the UNITY system.

The project was bolstered by a utility rebate from Detroit Edison, based on a 2-year payback.

While numerous DDC vendors offered equipment which would meet the general applications required of the 14,000 ton chiller plant, the combination of Control Systems International (CSI) equipment and the UNITY front-end proved superior. The configuration enabled Electronic Systems USA and Renaissance Center staff to initiate advanced control strategies that will have long-term benefits for the facility.

One such strategy is aimed at reducing kilowatt usage in order to avoid demand charges from Detroit Edison, the local utility. By designating on/off points within the CSI subsystem for demand control, UNITY is able to monitor the point data, analyze it, and initiate demand strategies to perform opposing tasks, such as shutting off unnecessary air handler units.

The UNITY system has also enabled the engineering staff at Renaissance Center to implement control strategies that monitor solar load and initiate an optimization schedule for pump sequencing that resets the differential pressure to control the flow of chilled water throughout the facility. The chiller plant has nine pumps that control the flow of chilled water throughout the facility. This strategy results in an automatic pump selection based on averaged run time rather than a set sequence. The result is reduced maintenance costs and extended life of the equipment.

UNITY now provides seamless integration of the existing Honeywell equipment into a multi-vendor platform, operating on standard off-the-shelf hardware. The new front-end is easily maintained, eliminates proprietary control languages, and simplifies programming new energy management strategies.

The UNITY system also enabled Renaissance Center to integrate and expand with advanced Direct Digital Control technology without relying on the original HVAC equipment manufacturer.

Electronic Systems USA was able to provide long-term solutions for Renaissance Center. The facility operates more efficiently, and remains independent of equipment manufacturers for product support. UNITY's architecture gives Renaissance Center the benefit of opening their facility to competitive bid on future expansions. And they are free to maximize operations through the implementation of energy management strategies.

UNITY truly gives Renaissance Center freedom of choice!

Renaissance Center houses one of the largest central cooling plants in the world, and represents one of the most complex system retrofits ever undertaken.



#### FEDERAL AVIATION ADMINISTRATION

ESUSA was selected through the bid process to upgrade 26 Air Route Traffic Control Centers (ARTCC) across the United States. The FAA wanted a computer-based frontend system that could monitor and control critical mechanical and environmental subsystems within the air traffic radar centers. ESUSA's first generation Honeywell CPU replacement, the Building Control Console, was chosen.

Each ARTCC is between 80,000 and 100,000 square feet and uses approximately 20 Delta 2500 Data Gathering Panels (DGPs). While the Delta 2500 could perform duty cycling and limited optimum start/stop, there was no way for the user to expand control strategies or add new algorithms for additional control points without sending data back to the factory. In addition, parts were very difficult to obtain.

While the BCC is not Direct Digital Control (DDC), it does allow on-site programming, as well as expanded control options such as load shedding, temperature-compensated duty cycling, more sophisticated chiller and boiler optimization, and lighting control. The BCC also came with color graphics, multi-tasking software and trending report capabilities.

Because the project was a federal government installation, the vendor was selected on the basis of low bid. Other bidders were Honeywell, which offered its Excel Plus system at \$1.8 million, and Optimum Controls Corp., Reading Valley, PA, which bid its Optimum 9000 system at \$1.9 million. ESUSA's winning bid was \$1.2 million.

ESUSA is currently integrating CSI DDC to the BCC in many of these sites. The southwest region has standardized with the CSI System 7000 for its DDC needs.

Contact: Sid Wibbels Louisville

## PROPERTY MANAGEMENT REFERENCES (Partial list)

John Buck Company	Sears Tower	Chicago
LaSalle Property Management	O'Hare Plaza	Chicago
Cushman & Wakefield	One Rotary Center	Chicago
Premisys R.E. Management	Citicorp Plaza	Los Angeles
LaSalle Property Management	Fox Plaza	Los Angeles
MS Management Services	Security Pacific	Los Angeles
CB Commercial	12100 Wilshire Blvd.	Los Angeles
Charles Dunn Company	University Towers	Los Angeles
Premisys R.E. Management	Gateway Center	Newark, NJ
LaSalle Property Management	NationsBank Plaza	Charlotte
Galbreath Company	Mobil Oil Building	Dallas
Brookfield Development	World Trade Center	Denver

# APPENDIX I SCOPE OF WORK

GENERAL SCOPE OF WORK

FOR A

FOR ENERGY MANAGEMENT STUDY
FORT BELVOIR. VA

Performed as part of the ENERGY ENGINEERING ANALYSIS PROGRAM (EEAP)

# SCOPE OF WORK FOR A LIMITED ENERGY STUDY

#### TABLE OF CONTENTS

- 1. BRIEF DESCRIPTION OF WORK
- 2. GENERAL
- 3. PROJECT MANAGEMENT
- 4. SERVICES AND MATERIALS
- 5. PROJECT DOCUMENTATION
  - 5.1 ECIP Projects
  - 5.2 Non-ECIP Projects
  - 5.3 Nonfeasible ECOs
- 6. DETAILED SCOPE OF WORK
- 7. WORK TO BE ACCOMPLISHED
  - 7.1 Review Previous Studies
  - 7.2 Perform a Limited Site Survey
  - 7.3 Reevaluate Selected Projects
  - 7.4 Lvaluate Selected ECOs
  - 7.5 Combine ECOs into Recommended Projects
  - 7.6 Submittals, Presentations and Reviews

#### ANNEXES

- A DETAILED SCOPE OF WORK
- B EXECUTIVE SUMMARY GUIDELINE
- C REQUIRED DD FORM 1391 DATA

# 1. BRIEF DESCRIPTION OF WORK: The Architect-Engineer (AE) shall:

Engineering Analy-Review the previously come specific building, OMIT .. opportunity (ECO) covered by this sis Program (EEAP) system, or ene

- 1.2 Perform a limited site survey of specific buildings or study. areas to collect all data required to evaluate the specific ECOs
- included in this study. r ECO from the previous 2.3 Reevaluate the special study to determination and technical applicability.
- 1.4 Evaluate specific ECOs to determine their energy savings potential and economic feasibility.
- 1.5 Provide project documentation for recommended ECOs as detailed herein.
- 1.6 Prepare a comprehensive report to document all work performed, the results and all recommendations.
- 2.1 This study is limited to the evaluation of the specific GENERAL 2. buildings, systems, or ECOs listed in Annex A, DETAILED SCOPE OF
- 2.2 The information and analysis outlined herein are consid-WORK. ered to be minimum requirements for adequate performance of this
- methods of energy conservation
  shall be considered, including servation opportunity consider

  considered in Annex A, all energy conservation opportunity consider

  e reasonable and practical evements of operational methods over an energy conservation opportunity consider

  considered in Annex A, all energy conservation opportunity cons chis report. Any energy conservation opporinfeasible shall also be documented in the retunity consider port with reasons for elimination.
  - applicable to each OMIT use of all energy sources
  - 2.5 The "Energy Conservation Investment Program (ECIP) Guidance", described in letter from CEHSC-FU, dated 4 Nov 1992 and the latest revision from CEHSC-FU establishes criteria for ECIP projects and shall be used for performing the economic analyses of all ECOs and projects. The program, Life Cycle Cost In Design (LCCID), has been developed for performing life cycle cost calculations in accordance with ECIP guidelines and is referenced in the ECIP Guidance. If any program other than LCCID is proposed for life cycle cost analysis, it must use the mode 丁-3

of calculation specified in the ECIP Guidance. The output must be in the format of the ECIP LCCA summary sheet, and it must be submitted for approval to the Contracting Officer.

- Computer modeling will be used to determine the energy savings of ECOs which would replace or significantly change an existing heating, ventilating, and air-conditioning (HVAC) system. The rquirement to use computer modeling applies only to heated and air-conditioned or air-conditioned-only buildings which exceed 8,000 square feet or heated-only buildings in excess of 20,000 square feet. Modeling will be done using a professionally recognized and proven computer program or programs that integrate architectural features with air-conditioning, heating, lighting and other energy-producing or consuming systems. These programs will be capable of simulating the features, systems, and thermal loads of the building under study. The program will use established weather data files and may perform calculations on a true hour-by-hour basis or may condense the weather files and the number of calculations into several "typical" days per month. The Detailed Scope of Work, Annex A, will list programs that are acceptable to the Contracting Officer. If the AE desires to use a different program, it must be submitted for approval with a sample run, an explanation of all input and output data, and a summary of program methodology and energy evaluation capabilities.
- 2.7 Energy conservation opportunities determined to be technically and economically feasible shall be developed into projects acceptable to installation personnel. This will involve combining similar ECOs into larger packages which will qualify for ECIP, funding, and determining in coordination with installation personnel the appropriate packaging and implementation approach for all feasible ECOs.
  - 2.7.1 Projects which qualify for ECIP funding shall be identified, separately listed, and prioritized by the Savings to Investment Ratio (SIR).
  - 2.7.2 All feasible non-ECIP projects shall be ranked in order of highest to lowest SIR.
  - 2.7.3 At some installations Energy Conservation and Management (ECAM) funding will be used instead of ECIP funding. criteria for each program is the same. The Director of Engineering and Housing will indicate which program is used at this instal-This Scope of Work mentions only ECIP, however, ECAM is lation. also meant.

## PROJECT MANAGEMENT

Project Managers. The AE shall designate a project manager to serve as a point of contact and liaison for work required under this contract. Upon award of this contract, the individual shall be immediately designated in writing. The AE's designated project manager shall be approved by the Contracting Officer prior This designated individual shall be to commencement of work.

responsible for coordination of work required under this contract. The Contracting Officer will designate a project manager to serve as the Government's point of contact and liaison for all work required under this contract. This individual will be the Government's representative.

- Installation Assistance. The Commanding Officer or authoresentative at the installation will designate an individual sist the AE in obtaining rized representative at the installation will designate an individual to assist the AE in obtaining information and establishing contacts necessary to accomplish the work required under this contract. This individual will be the installation representative.
- Public Disclosures. The AE shall make no public announcements or disclosures relative to information contained or developed in this contract, except as authorized by the Contracting
- 3.4 Meetings. Meetings will be scheduled whenever requested officer. by the AE or the Contracting Officer for the resolution of questions or problems encountered in the performance of the work. AE's project manager and the Government's representative shall be required to attend and participate in all meetings pertinent to the work required under this contract as directed by the Contracting Officer. These meetings, if necessary, are in addition to the presentation and review conferences.
  - Site Visits, Inspections, and Investigations. shall visit and inspect/investigate the site of the project as necessary and required during the preparation and accomplishment of the work.

- 3.6.1 The AE shall provide a record of all significant confer-3.6 Records ences, meetings, discussions, verbal directions, telephone conversations, etc., with Government representative(s) relative to this contract in which the AE and/or designated representative(s) thereof participated. These records shall be dated and shall identify the contract number, and modification number if applicable, participating personnel, subject discussed and conclusions reached. AE shall forward to the Contracting Officer within ten calendar days, a reproducible copy of the records.
  - 3.6.2 The AE shall provide a record of requests for and/or receipt of Government-furnished material, data, documents, information, etc., which if not furnished in a timely manner, would significantly impair the normal progression of the work under this The records shall be dated and shall identify the con-The AE shall tract number and modification number, if applicable. forward to the Contracting Officer within ten calendar days, a reproducible copy of the record of request or receipt of material.
    - The AE and the Government's representative shall conduct entry and exit interviews with the Director of Engineering and Housing before starting work at the installation

and after completion of the field work. The Government's representative shall schedule the interviews at least one week in advance.

- 3.7.1 Entry. The entry interview shall describe the intended procedures for the survey and shall be conducted prior to commencing work at the facility. As a minimum, the interview shall cover the following points:
  - a. Schedules.
  - b. Names of energy analysts who will be conducting the site survey.
  - c. Proposed working hours.
  - d. Support requirements from the Director of Engineering and Housing.
- 3.7.2 Exit. The exit interview shall briefly describe the items surveyed and probable areas of energy conservation. The interview shall also solicit input and advice from the Director of Engineering and Housing.
- 4. <u>SERVICES AND MATERIALS</u>. All services, materials (except those specifically enumerated to be furnished by the Government), plant, labor, supervision and travel necessary to perform the work and render the data required under this contract are included in the lump sum price of the contract.
- 5. PROJECT DOCUMENTATION. All energy conservation opportunities which the AE has considered shall be included in one of the following categories and presented in the report as such:
- 5.1 ECIP Projects. To qualify as an ECIP project, an ECO, or several ECOs which have been combined, must have a construction cost estimate greater than \$300,000, a Savings to Investment Ratio greater than one and a simple payback period of less than ten years. For ECAM projects, the \$300,000 limitation may not apply; in such cases, the AE shall check with the installation for guidance. The overall project and each discrete part of the project shall have an SIR greater than one. All projects meeting the above criteria shall be arranged as specified in paragraph 2.7.1 and shall be provided with programming documentation. Programming documentation shall consist of a DD Form 1391, life cycle cost analysis (LCCA) summary sheet(s) (with necessary backup data to verify the numbers presented), and a Project Development Brochure (PDB). A life cycle cost analysis summary sheet shall be developed for each ECO and for the overall project when more than one ECO are combined. The energy savings for projects consisting of multiple ECOs must take into account the synergistic effects of the individual ECOs. [For projects and ECOs reevaluated from previous studies, the backup data shall consist of copies of the original calculations and analysis, with new pages revising the original calculations and analysis. In addition, the backup data shall include as much of the following as is available: the increment

of work under which the project or ECO was developed in the previous study, title(s) of the project(s), the energy to cost (E/C) ratio, the benefit to cost (B/C) ratio, the current working estimate (CWE), and the payback period. The purpose of this information is to provide a means to prevent duplication of projects in any future reports.]

- 5.2 Non-ECIP Projects. Projects which do not meet ECIP criteria with regard to cost estimate or payback period, but which have an SIR greater than one shall be documented. Projects or ECOs in this category shall be arranged as specified in paragraph 2.7.2 and shall be provided with the following documentation: the life cycle cost analysis (LCCA) summary sheet completely filled out, a description of the work to be accomplished, backup data for the LCCA, ie, energy savings calculations and cost estimate(s), and the simple payback period. The energy savings for projects consisting of multiple ECOs must take into account the synergistic effects of the individual ECOs. In addition these projects shall have the necessary documentation prepared, as required by the Government's representative, for one of the following categories:
  - a. Quick Return on Investment Program (QRIP). This program is for projects which have a total cost greater than \$3,000 but less than \$100,000 and a simple payback period of two years or less.
  - b. Productivity Enhancing Capital Investment Program (PE-CIP). This program is for projects which have a total cost of greater than \$3,000 but lees than \$100,000 and a simple payback period of four years or less.
  - c. OSD Productivity Investment Funding (OSD PIF). This program is for projects which have a total cost of more than \$100,000 and a simple payback period of four years or less.

The above programs and the required documentation forms are all described in detail in AR 5-4, Change No. 1.

- d. Regular Military Construction Army (MCA) Program. This program is for projects which have a total cost greater than \$300,000 and a simple payback period of four to twenty-five years. Documentation shall consist of DD Form 1391 and a Project Development Brochure.
- e. Low Cost/No Cost Projects. These are projects which the Director of Engineering and Housing (DEH) can perform using his resources. Documentation shall be as required by the DEH.

  These projects shall be combined for Exp. Funding
- 5.3 Nonfeasible ECOs. All ECOs which the AE has considered but which are not feasible, shall be documented in the report with reasons and justifications showing why they were rejected.
- 6. <u>DETAILED SCOPE OF WORK</u>. The Detailed Scope of Work is contained in Annex A.

## 7. WORK TO BE ACCOMPLISHED.

- which applies to the specific acquaint the AE with the work that has been perform MIT asly. Much of the information the AE may need to devel. Os in this study may be contained in the previous study.
- 7.2 <u>Perform a Limited Site Survey</u>. The AE shall obtain all necessary data to evaluate the ECOs or projects by conducting a site survey. However, the AE is encouraged to use any data that may have been documented in a previous study. The AE shall document his site survey on forms developed for the survey, or standard forms, and submit these completed forms as part of the report. All test and/or measurement equipment shall be properly calibrated prior to its use.
- 7.3 Reevaluate Selected Projects. The AE shall reevaluate the projects and ECOs listed in Annex A. - ese are projects and but that have not been ECOs that the previous study has ider' Implished. If the project accomplished or only parts have + chere are no changes to the project may be accept struction cost es of shall be updated based on the rent data available. or ECO is acceptable as is, +' With the above information the project shall rent data availa then be analyzed wased on current ECIP criteria. If the project or ECO is basically acceptable but some of the buildings in the original project have been deleted or new buildings can be added, the necessary changes shall be made to the energy savings, the energy costs and construction costs shall be updated, and the revised project or ECO shall then be analyzed using current ECIP guidance. If the original project or ECO has had numerous changes made to it so that all of the numbers are suspected of being inaccurate, but the project or ECO is still considered feasible, the AE shall develop the project from the beginning and analyze it with the current ECIP quidance. These projects shall be separately listed in the report.
- 1.4 Evaluate Selected ECOs. The AE shall analyze the ECOs listed in Annex A. These ECOs shall be analyzed in detail to determine their feasibility. Savings to Investment Ratios (SIRs) shall be determined using current ECIP guidance. The AE shall provide all data and calculations needed to support the recommended ECO. All assumptions and engineering equations shall be clearly stated. Calculations shall be prepared showing how all numbers in the ECO were figured. Calculations shall be an orderly step-by-step progression from the first assumption to the final number. Descriptions of the products, manufacturers catalog cuts, pertinent drawings and sketches shall also be included. A life cycle cost analysis summary sheet shall be prepared for each ECO and included as part of the supporting data.

- 7.5 Combine ECOs Into Recommended Projects. During the Interim Review Conference, as outlined in paragraph [7.6.1], the AE will be advised of the DEH's preferred packaging of recommended ECOs into projects for implementation. Some projects may be a combination of several ECOs, and others may contain only one. These projects will be evaluated and arranged as outlined in paragraphs 5.1, 5.2, and 5.3. Energy savings calculations shall take into account the synergistic effects of multiple ECOs within a project and the effects of one project upon another. The results of this effort will be reported in the Final Submittal per par [7.6.2].
- The work accom-Submittals, Presentations and Reviews. plished shall be fully documented by a comprehensive report. report shall have a table of contents and shall be indexed. and dividers shall clearly and distinctly divide sections, subsections, and appendices. All pages shall be numbered. Names of the persons primarily responsible for the project shall be included. The AE shall give a formal presentation of the interim submittal to installation, command, and other Government personnel. Slides or view graphs showing the results of the study to date shall be used during the presentation. During the presentation, the personnel in attendance shall be given ample opportunity to ask questions and discuss any changes deemed necessary to the study. A review conference will be conducted the same day, following the presentation. Each comment presented at the review conference will be discussed and resolved or action items assigned. It is anticipated that the presentation and review conference will require approximately one working day. The presentation and review conference will be at the installation on the date agreeable to the Director of Engineering and Housing, the AE and the Government's representative. The Contracting Officer may require a resubmittal of any document(s), if such document(s) are not approved because they are determined by the Contracting Officer to be inadequate for the intended purpose.
  - 7.6.1 Interim Submittal. An interim report shall be submitted for review after the field survey has been completed and an analysis has been performed on all of the ECOs. The report shall indicate the work which has been accomplished to date, illustrate the methods and justifications of the approaches taken and contain a plan of the work remaining to complete the study. Calculations a plan of the work remaining to complete the study. Calculations showing energy and dollar savings, SIR, and simple payback period of all the ECOs shall be included. The results of the ECO analyses shall be summarized by lists as follows:
  - a.All ECOs eliminated from consideration shall be grouped into one listing with reasons for their elimination as discussed in par 5.3.
  - b.All ECOs which were analysed shall be grouped into two listings, recommended and non-recommended, each arranged in order of descending SIR. These lists may be subdivided by building or area as appropriate for the study.

The AE shall submit the Scope of Work and any modifications to the Scope of Work as an appendix to the report. A narrative summary describing the work and results to date shall be a part of this submittal. At the Interim Submittal and Review Conference, the Government's and AE's representatives shall coordinate with the Director of Engineering and Housing to provide the AE with direction for packaging or combining ECOs for programming purposes and also indicate the fiscal year for which the programming or implementation documentation shall be prepared. The survey forms completed during this audit shall be submitted with this report. The survey forms only may be submitted in final form with this submittal. They should be clearly marked at the time of submission that they are to be retained. They shall be bound in a standard three-ring binder which will allow repeated disassembly and reassembly of the material contained within.

- 7.6.2 Final Submittal. The AE shall prepare and submit the final report when all sections of the report are 100% complete and all comments from the interim submittal have been resolved. AE shall submit the Scope of Work for the study and any modifications to the Scope of Work as an appendix to the submittal. report shall contain a narrative summary of conclusions and recommendations, together with all raw and supporting data, methods The report shall integrate all used, and sources of information. aspects of the study. The recommended projects, as determined in accordance with paragraph 5, shall be presented in order of priority by SIR. The lists of ECOs specified in paragraph [7.6.1] shall also be included for continuity. The final report and all appendices shall be bound in standard three-ring binders which will allow repeated disassembly and reassembly. The final report shall be arranged to include:
- a. An Executive Summary to give a brief overview of what was accomplished and the results of this study using graphs, tables and charts as much as possible (See Annex B for minimum requirements).
- b. The narrative report describing the problem to be studied, the approach to be used, and the results of this study.
- c. Documentation for the recommended projects (includes LCCA  $\mbox{\it Summary Sheets}$  ).
  - d. Appendices to include as a minimum: .
    - Energy cost development and backup data
    - 2) Detailed calculations
    - 3) Cost estimates
      - Computer printouts (where applicable)
      - 5) Scope of Work

#### APPENDIX A

# ENERGY MANAGEMENT SYSTEM (EMS) STUDY SCOPE OF WORK

- 1. <u>Purpose</u>. The Architect/Engineer (AE) shall analyze three types of energy management systems for five representative buildings in order to recommend a definitive strategy for the installation.
- 2. Buildings to be Evaluated. The study population consists of five buildings:
  - a. Building 3136 (14,110 SF)
  - b. Building 1425 (15,570 SF)
  - c. Building 200 (26,850 SF)
  - c. Building 219 (31,270 SF)
  - d. Building 247 (148,067 SF)
- 2. Energy Management System (EMS) Evaluation. The AE shall audit the existing FM switch EMS, studying the specifications and determining the remaining potential. Changes to the current strategy will be recommended if applicable. The AE shall research existing PowerLine Carrier (PLC) and Direct Digital Control (DDC) systems available on the market. Each type EMS must be compared to the others for the five representative buildings.
- 3. <u>Building Audits</u>. The AE shall audit the electrical and mechanical systems and the heat gain/loss characteristics for each building above. The audit shall include the information needed to evaluate each EMS. Evaluation shall be in terms of cost savings (including demand) and energy savings.
- 4. Energy Conservation Opportunities (ECOs). The AE shall determine the optimum type of EMS to install in the buildings listed above. Cost savings and energy savings shall be quantified for each building. The pros/cons of each system shall be qualified for each building.
- a. <u>FM Switch System</u>. The AE shall evaluate the cost/benefit of including additional buildings on the current system. The current strategy may be continued or may be modified if appropriate.

b. <u>Powerline Carrier System</u>. The AE shall evaluate the cost/benefit of installing a powerline carrier system as the EMS. The strategy will be recommended for each building.

\*.

- c. <u>Direct Digital Control (DDC) Energy Management System</u>. The AE shall evaluate the cost/benefit of installing a DDC system as the EMS. The strategy will be recommended for each building.
- 5. <u>ECO Analysis</u>. The ECOs listed above shall be analyzed against the existing conditions for each building. Each ECO shall be analyzed individually, per building listed in paragraph 2 above, for cost savings (including demand) and energy savings using ECIP criteria. The program simulation method used for the analyses shall be approved by the Installation.
- 6. Market Analysis. A market analysis shall be conducted to determine efficient and reliable products to successfully realize the potential of each ECO. At least one system shall be recommended for each ECO evaluated. Price information and specifications shall be provided. Generalities shall be unacceptable. The factors leading to each selection shall be documented.
- 7. Extrapolated Results. The conclusions and recommendations of this study will be extrapolated by the Government over the installation building population. The AE shall provide and explain the parameters under which such a projection will have validity. An overall EMS strategy shall be recommended.
- 8. <u>Submittals</u>. The work accomplished shall be fully documented in a comprehensive report. The report shall have a table of contents and have appendices. All pages shall be numbered, including the appendices. The AE shall provide calculations needed to support all data presented. The calculations shall be an orderly step-by-step progression from the first assumption to the final number, showing how all numbers in the analysis were developed.

All assumptions shall be clearly stated. Descriptions of the products, catalog cuts, pertinent drawings, and sketches shall also be included. Each submittal shall consist of five (5) copies, four bound and one (1) in a three ring binder.

a. <u>Interim Submittal</u>. The interim report shall present the work that has been accomplished to date, illustrate the methods and justifications of the approaches taken, and contain a plan for completing the remaining work.

- b. <u>Prefinal Submittal</u>. The prefinal report shall be a comprehensive document detailing the analyses performed under this contract and the logical conclusions.
- c. <u>Final Submittal</u>. Any revisions or corrections resulting from comments made during the review of the prefinal report or during the presentation and review conference shall be incorporated into the final report. Pen and ink changes or errata sheets will not be acceptable. The program simulation shall be submitted as a part of the final submittal on either 3.5 or 5.25 inch disk(s).
- d. <u>Comments</u>. Government comments to all submittals, except the final submittal, will be delivered to the AE in written form. The Government will require two weeks to review each submittal. Meetings will be scheduled as necessary to discuss those comments that the AE does not concur with or does not understand.
- 9. <u>Interviews</u>. The AE shall conduct entry and exit interviews with representatives from the Directorate of Engineering and Housing before starting work at the installation and after completion of the prefinal submittal. The interviews shall be scheduled at least one week in advance.
- a. <u>Entry</u>. The entry interview shall thoroughly brief and describe procedures for the study and shall be conducted prior to commencing work on the study.
- b. <u>Exit</u>. The exit interview shall summarize the work performed and present the conclusions and recommendations.
- 10. <u>Services and Materials</u>. All services, materials, labor, and travel necessary to perform the work and render the data required under this contract are included in the lump sum of the contract.

## 11. <u>Deliverables</u>.

- a. <u>Interim Submittal</u>. 90 calendar days from date of receipt by the AE firm of the delivery order.
- b. <u>Prefinal Submittal</u>. 45 calendar days from date of receipt by the AE firm of review comments on interim submittal.
- c. <u>Final Submittal</u>. 14 calendar days from receipt by the AE firm of review comments on the prefinal submittal.
- d. Government Review Time. Government review and comments on the interim submittal will normally take one to two weeks.

to the computer modeling requirements of paragraph 2.6, then the computer modeling requirements of paragraph 2.6, then the computer modeling requirements of paragraph 2.6, then the computer modeling requirements of paragraph 2.6, then the computer work acceptable to the office doing the traducinal review should be listed in the detailed scope of work. Some acceptable simulation programs follow:

- a. Building Loads and System Thermodynamics (BLAST) \*
- b. DOE 2.1B \*
- c. Carrier E20 or Hourly Analysis Program (HAP) \*\*
- d. Trane Air-Conditioning Economics (TRACE) \*\*
- titled Life Cycle Costing in Design (LCCID) is available from the BLAST Support Office in Urbana, Illinois for a nominal fee. This computer program can be used for performing the economic calculations for ECIP and non-ECIP ECOs. The AE is encouraged to obtain and use this computer program. The BLAST Support Office can be contacted at 144 Mechanical Engineering Building, 1206 West Green Street, Urbana, Illinois 61801. The telephone number is (217) 333-3977 or (800) 842-5278."

# 13. Government Firmished Information:

ETLs 1110-3-254, Use of Electric Power for Comfort Space Heating (if applicable), and 1110-3-282, Energy Conservation

\* (2) Architectural and Engineering Instructions.

(3) Energy Conservation Investment Program (ECIP) Guidance, dated 4 Nov 1992 and the latest revision with current energy prices and discount factors for life cycle cost analysis.

(点) TM 5-785, Engineering Weather Data, TM 5-800-2, General Criteria Preparation of Cost Estimates.

(5) AR 5-4, Change No. 1, Department of the Army Productivity Improvement Program.

AR 415-15, 1 Jan84, Military Construction, Army (MCA)

Program Development

X(9) The latest MCP Index.

14. Facility Assistance Representative

Mr Mike Strimbough Emergy Coordinatod 703 806-4007

#### ANNEX B

### EXECUTIVE SUMMARY GUIDELINE

- 1. Introduction.
- Building Data (types, number of similar buildings, sizes, etc.)
- 3. Present Energy Consumption of Buildings or Systems Studied.
  - o Total Annual Energy Used.
  - o Source Energy Consumption.

Electricity - KWH, Dollars, BTU
Fuel Oil - GALS, Dollars, BTU
Natural Gas - THERMS, Dollars, BTU
Propane - GALS, Dollars, BTU
ther - QTY, Dollars, BTU

- 4. Reevaluated Projects Results.
- 5. Energy Conservation Analysis.
  - o ECOs Investigated.
  - o ECOs Recommended.
  - o ECOs Rejected. (Provide economics or reasons)
  - o ECIP Projects Developed. (Provide list) \*
  - o Non-ECIP Projects Developed. (Provide list) \*
  - o Operational or Policy Change Recommendations.
- \* Include the following data from the life cycle cost analysis summary sheet: the cost (construction plus SIOH), the annual energy savings (type and amount), the annual dollar savings, the SIR, the simple payback period and the analysis date.
- Energy and Cost Savings.
  - o Total Potential Energy and Cost Savings.
  - o Percentage of Energy Conserved.
  - o Energy Use and Cost Before and After the Energy Conservation Opportunities are Implemented.

#### ANNEX C

### REQUIRED DD FORM 1391 DATA

To facilitate ECIP project approval, the following supplemental data shall be provided:

- a. In title block clearly identify projects as "ECIP."
- b. Complete description of each item of work to be accomplished including quantity, square footage, etc.
- c. A comprehensive list of buildings, zones, or areas including building numbers, square foot floor area, designated temporary or permanent, and usage (administration, patient treatment, etc.).
- d. List references, and assumptions, and provide calculations to support dollar and energy savings, and indicate any added costs.
- (1) If a specific building, zone, or area is used for ; sample calculations, identify building, zone or area, category, prientation, square footage, floor area, window and wall area for each exposure.
  - (2) Identify weather data source.
- (3) Identify infiltration assumptions before and after improvements.
- (4) Include source of expertise and demonstrate savings claimed. Identify any special or critical environmental conditions such as pressure relationships, exhaust or outside air quantities, temperatures, humidity, etc.
- e. Claims for boiler efficiency improvements must identify data to support present properly adjusted boiler operation and future expected efficiency. If full replacement of boilers is indicated, explain rejection of alternatives such as replace burners, nonfunctioning controls, etc. Assessment of the complete existing installation is required to make accurate determinations of required retrofit actions.
- f. Lighting retrofit projects must identify number and type of fixtures, and wattage of each fixture being deleted and installed. New lighting shall be only of the level to meet current criteria. Lamp changes in existing fixtures is not considered an ECIP type project.

- g. An ECIP life cycle cost analysis summary sheet as shown in the ECIP Guidance shall be provided for the complete project and for each discrete part included in the project. The SIR is applicable to all segments of the project. Supporting documentation consisting of basic engineering and economic calculations showing how savings were determined shall be included.
  - h. The DD Form 1391 face sheet shall include, for the complete project, the annual dollar and MBTU savings, SIR, simple amortization period and a statement attesting that all buildings and retrofit actions will be in active use throughout the amortization period.
  - i. The calendar year in which the cost was calculated shall be clearly shown on the DD Form 1391.
  - j. For each temporary building included in a project, separate documentation is required showing (1) a minimum 10-year continuing need, based on the installation's annual real property utilization survey, for active building retention after retrofit, (2) the specific retrofit action applicable and (3) an economic analysis supporting the specific retrofit.
  - k. Nonappropriated funded facilities will not be included in an ECIP project without an accompanying statement certifying that utility costs are not reimbursable.
  - 1. Any requirements required by ECIP guidance dated 4 Nov 1992 and any revisions thereto. Note that unescalated costs/savings are to be used in the economic analyses.
  - m. The five digit category number for all ECIP projects except for Family Housing is 80000. The category code number for Family Housing projects is 71100.

# APPENDIX J MEETING MINUTES

## Einhorn Yaffee Prescott



ARCHITECTURE & ENGINEERING, P.C.

## **Minutes of Meeting**

Directorate of Public Works
Environmental and Natural Resources Division
9430 Jackson Loop
Ft. Belvoir, VA 22060-5130
ATTN: Mike Stumbaugh
Contract No. DACA31-92-D-0061

Delivery Order 0004

Project Name:
Ft. Belvoir Energy

Management Study

Project Number:
60692.00

Date of Meeting:
10/14/93

Time of Meeting:

1:30 p.m.
Location of Meeting:
Ft. Belvoir Bldg, 1442

Meeting Number:

Purpose of Meeting:

To establish complete product scope and define expectations of all parties involved.

Attendees:

Representing:

Mike Stumbaugh Kevin Eskandary Steve Maskell Julius Stone Frank Ebbert David Smith

Ft. Belvoir
Einhorn Yaffee Prescott
Einhorn Yaffee Prescott
Einhorn Yaffee Prescott
Einhorn Yaffee Prescott

Einhorn Yaffee Prescott

The following constitutes my understanding of the items discussed and the decisions reached. If there are any additions or corrections, please contact the undersigned:

cc: Attendees
Jim Hawk, CENAB

igned:

Date: 10 15 93

Project: Ft. Belvoir EMS Study Date: 10/14/93 Page 2 of 4

Subject	Decision/Action Summary	
Existing FM Switch EMS	Mr. Stumbaugh stated that the existing FM switch EMS could be evaluated by visiting Building 191, where it is currently installed and talking with the operating personnel at that building. Mr. Stumbaugh will provide contact name and number and arrange a meeting between the operating personnel and an EYP representative.	
Type of Heating Fuel	Mr. Stumbaugh indicated that the base currently uses fuel oil for most of its heating needs but an up grade to gas was underway. He also indicated that for purposes of this study the heating costs are to be calculated using gas as the fuel. Mr. Stumbaugh will provide to EYP the gas rates which will be applied to this study.	
Use of Fiber Optics	Mr. Stumbaugh indicated that the existing fiber optics network which is currently in operation at Ft. Belvoir is to be used for all interbuilding EMS data transmission where possible. He will provide to EYP a contact name and phone number for Harris Corporation which maintains the fiber optic network.	
Scope of EMS Study	Mr. Eskandary stated that energy savings could possibly be realized by including building and site lighting in the EMS scope and asked if this should be addressed in the study. Mr. Stumbaugh stated that the primary area to be investigated was the heating, ventilating, and air conditioning (HVAC) systems and that site lighting is currently controlled by photo-cell controls and was to remain as such. It was agreed that any potential savings regarding EMS control of lighting would be discussed within the text of the report but would not be included in the economic analysis of the systems.	
	Mr. Smith asked if the auditorium (building 219A) adjacent to building 219 was to be included in the scope of this study. Mr. Stumbaugh indicated that building 219A was to be included.	
	Mr. Eskandary inquired as to the extent of control diagrams expected to be included in the report. Mr. Stumbaugh stated that the report should include schematic diagrams showing the general scheme of the system being proposed for each building.	
Computer Modeling	Mr. Smith proposed two possible programs to be used in model the building energy consumption. These programs are <u>Carrier E20-II</u> and <u>ASEAM 3.0</u> . Mr. Stumbaugh stated that he was	

Project: Ft. Belyoir EMS Study Date: 10/14/93


Page 3 of 4

Subject	Decision/Action Summary
	familiar with both programs and that either was acceptable to him for use in this study. Mr. Smith indicated that he would notify Mr. Stumbaugh in the near future as to which program would be used.
Schedule	The schedule for the project was discussed and Mr. Stumbaugh indicated that the schedule was to be as outlined in the original scope of work with the starting date being October 14, 1993.
Site Surveys	Mr. Stumbaugh indicated that access would be available without clearance to all buildings except building 3136 which is a secure area and would require prior clearance. Mr. Stumbaugh is to arrange for acquisition of necessary clearance for building 3136.
	Mr. Stumbaugh is to provide to EYP a list of contact names and phone numbers of personnel in each building. These persons are to be interviewed by EYP to determine the current operating hours and procedures for each building.
Electric Rates	Mr. Stumbaugh indicated that the electric service was provided to the base by Virginia Power in the form of a large primary service and was billed as such. He is to provide to EYP the electric billing information for the past year for the purposes of establishing current rate structures.
Power Line Carrier Systems	There was a general discussion concerning Power Line Carrier (PLC) systems and the applicability to this study. Mr. Smith indicated that he has contacted several vendors and was in the process of gathering information about PLC systems available today. Mr. Stumbaugh stated that building 1442 had an operating PLC system and that he would provide EYP with information about that system.
Miscellaneous	Mr. Smith requested a copy of the latest Energy Conservation Investment Program (ECIP) guidelines. Mr. Stumbaugh said he would provide this document to EYP.
	Mr. Smith asked if there was a particular report format that was preferred and Mr. Stumbaugh indicated that he would provide a copy of a previous study to EYP for reference purposes.

Project: Ft. Belvoir EMS Study Date: 10/14/93

Subject	Decision/Action Summary
	Mr. Stumbaugh indicated that building 219 was about to undergo a major renovation which was to include an EMS. He said he would provide to EYP information on this project and the EMS which was to be installed.
	-

## Einhorn Yaffee Prescott



**ARCHITECTURE &** ENGINEERING, P.C.

# **Minutes of Meeting**

To:

Directorate of Public Works Environmental and Natural Resources Division 9430 Jackson Loop Ft. Belvoir, VA 22060-5130 ATTN: Mike Stumbaugh Contract No. DACA31-92-D-0061

Delivery Order 0004

Ft. Belvoir Energy Management Study Project Number: 60692.00 Date of Meeting: 12/6/93 Time of Meeting: 9:00 a.m. Location of Meeting: Ft. Belvoir Bldg. 1442 Meeting Number:

Project Name:

Purpose of Meeting:

To review report format and confirm correct approach to study.

Attendees:

Representing:

Mike Stumbaugh David Smith

Ft. Belvoir Einhorn Yaffee Prescott

The following constitutes my understanding of the items discussed and the decisions reached. If there are any additions or corrections, please contact the undersigned:

Attendees

J. Hawk, CENAB

K. Eskandary, EYP

J. Stone, EYP

Project: Ft. Belvoir EMS Study

Date: 12/6/93

Page 2 of 3

Subject	Decision/Action Summary	
Review of proposed report outline:	- Mike Stumbaugh commented that the executive summary should include a one page description of recommended projects with all applicable pay-back and return-on-investment figures. This summary should be in tabular form if possible.	
	- David Smith stated that EYP would develop a format for such a table and include that format in the interim submittal.	
	- Mr. Stumbaugh expressed his desire to have the executive summary be as short and concise as possible and that the bulk of the technical information be included in the evaluation section of the report.	
Discussion of control system options:	- Mr. Smith explained that there are two basic types of Powerline Carrier Control systems available. One system has two-way communication capabilities and can perform many of the comfort control and energy management functions of a Direct Digital Control System while the other features one-way communication and operates primarily by turning equipment on and off using a series of relays.	
	- It was agreed that because of the simplicity and greater availability of suppliers and technical support, only the one-way system would be considered as part of this study.	
Discussion of EMS systems evaluation matrix:	- Mike Stumbaugh requested that reliability and maintainability be added to the evaluation criteria as well as compatibility with existing mechanical equipment.	
	- It was agreed that cost should be added to the evaluation criteria and that the matrix may be best used to evaluate the three EMS options in general and not in their application to each building. Mr. Smith is to further develop the matrix and decide upon the application.	
	- Preliminary schematic diagrams were reviewed and Mike Stumbaugh indicated that the format was acceptable. David Smith commented that these schematics would be refined and revised to accommodate the results of the economic analysis and recommendations from the control vendors.	

Project Ft. Belvoir EMS Study

Date: 12/6/93

Page 3 of 3

Minutes of Meeting	Project Name: Ft. Belvoir Energy
	Management Study Project Number: 60692.00
то: Mr. Jim Hawk	Date of Meeting: 3/24/94
CENAP AE Acquisition Branch 10 S. Howard Street	Time of Meeting: 10:00 a.m.
Baltimore, MD 21201 COE Project No. DACA31-92-D-0061 Delivery Order No. 0004	Location of Meeting: Ft. Belvoir Bldg. 1442 Meeting Number: 3
Purpose of Meeting:	
To review comments on interim submittal	-
Attendees:	Representing:
Jim Hawk	COE
Mike Stumbaugh	DPW - Fort Belvoir Einhorn Yaffee Prescott
Kevin Eskandary David Smith	Einhorn Yaffee Prescott
Julius Stone	Einhorn Yaffee Prescott
The following constitutes my understanding of the items disc corrections, please contact the undersigned:	cussed and the decisions reached. If there are any additions or
cc: Attendees	
	Signed:

Project: Ft. Belvoir EMS Study Date: 3/24/94 Page 3 of 6/

in the Victoria

Subject	Decision/Action Summary	
Review of COE Comments	EYP Response: Mechanical	
	1. Approval by other divisions of the Corp of Engineers (COE) is not within the scope of the contract for this study. This approval will be the responsibility of Fort Belvoir (the Post).	
	2. The decision to use DDC controls in any of the buildings in this study and the acquisition of any required waiver will be the responsibility of the Post personnel, not the authors of this report. The report will address only the cost/benefit analysis for the various type of EMS.	
	EYP Response: Electrical	
	1. The program was inadvertently referred to as Version 3.0. The program used was actually Version 3.02.	
	2. EYP will use data that was shown on the original contract drawings for each building. Where data is not available EYP will estimate the outside air quantities based on known conditions.	
	3. Mike Stumbaugh indicated that actual change over dates vary from year to year. It was decided that April 15 and September 15 would be used for the purposes of this study.	
	4. The ECIP Guidelines recommend a ten (10) year Economic Analysis Life for EMS or HVAC Control projects. If any other criteria are to be followed COE must advise.	
	5. The BLCC life cycle cost analysis program uses data from the NISTIR 85-3273 as required by the ECIP guidelines.  Also see the enclosed letter explaining the BLCC program.	
	6. The 3.1% discount factor is the FEMP discount rate for 1994 listed in the "Energy Prices and Discount Factors for Life-Cycle Cost Analysis 1994" as compiled by the	

Project Ft. Belvoir EMS Study

Date: 12/6/93

Page 4 of 6

Subject	Decision/Action Summary
	National Institute of Standards and Technology for the United States Department of Energy. This same standard recommends that a 4.0% discount factor be used for study periods of up to 10 years. The ECIP guidelines utilize a discount rate of 4.0% to establish the energy price escalation factors. The COE must advise EYP as to the actual discount rate which is to be applied to this study. Please note that the life cycle cost analysis software packages allow the user to input any discount factor.
	7. EYP will comply. The COE will provide a copy of this standard to EYP.
	8. As stated in the report this system is best utilized for residential and small commercial systems as it is currently being applied, and does not have application for the buildings in this study. EYP will expand on the narrative that describes the abilities and limitations of this system.
	9. COE will clarify this comment. To what guide specification does it refer.
	10. The input data will be reviewed to confirm validity. If any errors are found they will be corrected, otherwise the data will be utilized. COE will advise as to the range that would normally be expected.
	11. The manufacturers of the DDC systems have indicated that fiber optics can be utilized as a communications path for the control systems. COE will advise if there is additional guidance referred to in this comment.
	12. This study will recommend a type of EMS to be installed in each building, it will not specify each individual control point; therefore, whether the existing boiler remains or is replaced will have little effect on the outcome of this recommendation.

Project: Ft. Belvoir EMS Study

Date: 12/6/93

Page 5 of 6

Subject		Decision/Action Summary
	13.	These chillers use R-22. This will be stated in the Prefinal submittal of the report.
	14.	This statement is true; however, this study will recommend a type of EMS to be installed in each building, it will not specify each individual control point; therefore, whether the existing chiller remains or is replaced will have little effect on the outcome of this recommendation.
	15.	This chiller uses R-22. This will be stated in the Pre-final submission of the report.
	16.	This chiller uses R-22. This will be stated in the Pre-final submission of the report.
	17.	Where available, lighting wattage values were taken from the original construction drawings and verified in the field. Also please note that building 200 is a recreation building with special areas which contain considerable amounts of incandescent lighting. The input data will be verified and corrected if found to be in error.
	18.	The 25 sq ft per person is for an assembly area and will be verified prior to the Pre-final submission of the report.
	19.	EYP will establish an estimated infiltration rate based on building conditions and utilize this rate consistently for the baseline conditions as well as all ECO alternatives.
	20.	ECIP Summary sheets will be included in the Pre-final submission of the report.
	21.	See the enclosed letter explaining the BLCC program.
	22.	All input information for the energy modeling was included in Appendix C of the report. If further information is need please specify.
	23.	See the enclosed letter explaining the BLCC program.

Project: Ft. Belvoir EMS Study Date: 12/6/93

Page 6 of 6

Subject		Decision/Action Summary	
	24.	See the attached letter explaining the BLCC program. COE is to provide a copy of TM 5-802-1.	
Review of the Post's			
Comments:	EYP	Response	
	1.	All spelling errors will be corrected prior to the Pre-final submittal.	
	2.	EYP will explain in more detail the capabilities and limitations of the existing FM Switch system in the Pre-Final submittal.	
	3.	Schematic diagrams and drawings are being formulated and will be included in the Pre-Final submittal.	
	4.	The advantages and disadvantages of each type of EMS will be described in more detail in the Pre-Final submittal.	
	5.	The purpose of the study will be more clearly stated in the Pre-Final submittal. The Executive Summary will also include a recommended strategy for applying EMS to each of the sample buildings.	
	6.	A matrix is being developed to evaluate the relative merits of all three system types. This matrix will be completed and included in the Pre-Final submittal.	
	7.	A simple electric rate of \$0.0616/Kwh will be used for all energy cost calculations as determined by the Installation Utility Chief.	
	8.	EYP will use data that was shown on the original contract drawings for each building. Where such data is not available EYP will estimate the outside air quantities based on known conditions.	
	9.	Proposed systems have not yet been finalized and will be described in more detail in the Pre-Final submittal.	

Project: Ft. Belvoir EMS Study

Date: 12/6/93

Page 7 of 6

Subject	Decision/Action Summary
	10. All conclusions will be supported by cost/benefit data in the Pre-Final submittal.
	11. The cost of the equipment necessary to connect the building EMS to the post fiber optic system as well as the cost of the central terminal and related software outweigh the benefit if only a small number of buildings are connected to the system. A more descriptive narrative with actual cost data will be included in the Pre-Final submittal.
	12. The general Ft. Belvoir data, as provided by Mike Stumbaugh will be included in the Pre-Final submittal.
	13. All energy savings data is generated by a computer program which is based on equipment input information and does not reflect items such as demand savings and system maintenance costs. EYP will investigate modifying the program input data to more closely simulate the differences in energy costs between the PLC and DDC systems.
	14. EYP will describe the limitations of the computer simulation program and how the program was used to model the energy usage for the baseline conditions as well as all ECO alternatives.
	15. The Pre-final report will include a section which describes what factors will most likely effect the energy usage in a given building and how this affects the savings potential of an EMS.
Re-Submittal	The Interim Report will be revised and re-submitted, for record purposes, within four weeks after EYP receives all information which is to be provided by COE and Ft. Belvoir.
	The Pre-final Report will be submitted for review within 45 days after EYP receives all information which is to be provided by COE and Ft. Belvoir.

	Project Name: Ft. Belvoir EMS Study
Minutes of Meeting	To Deliver Divide Study
<b>3</b>	
	Project Number:
	60692.00  Date of Meeting:
To:	11/22/94
Mr. James Hawk	Time of Meeting:
CENAB AE Acquisition Branch	10:30 a.m.
10 S. Howard Street	Location of Meeting:
Baltimore, MD 21201	Et Balvoir Building 1442
COE Project No. DACA31-92-D-006	Meeting Number:
Delivery Order No. 0004	4
Purpose of Meeting:	
, urpose of Meeting.	
To review comments on Pre Final sub	omittal.
Attendees:	Representing:
, mondoo.	
Jim Hawk	COE
Mike Stumbaugh	DPW - Fort Belvoir
David Smith	Einhorn Yaffee Prescott
Julius Stone	Einhorn Yaffee Prescott
The following constitutes my understanding of the item	s discussed and the decisions reached. If there are any additions o
The following constitutes my understanding of the item corrections, please contact the undersigned:	is discussed and the decisions reached. If there are any additions o
corrections, please contact the undersigned:	s discussed and the decisions reached. If there are any additions o
The following constitutes my understanding of the item corrections, please contact the undersigned:  cc: Attendees	s discussed and the decisions reached. If there are any additions o
corrections, please contact the undersigned:	is discussed and the decisions reached. If there are any additions o
corrections, please contact the undersigned:	is discussed and the decisions reached. If there are any additions o
corrections, please contact the undersigned:	is discussed and the decisions reached. If there are any additions o
corrections, please contact the undersigned:	is discussed and the decisions reached. If there are any additions o
corrections, please contact the undersigned:	is discussed and the decisions reached. If there are any additions o

Project: Ft. Belvoir EMS Study Date: 11/22/94 Page 2 of 5

Subject	Decision/Action Summary
Review of Comments	Agreed Upon Course of Action:
	Purnell's Comments:
	1. EYP will provide tabs and dividers and add page numbers to the appendices.
	2. A typographical error was found in this calculation and the will be corrected in the revised submission.
	3. The Washington, DC weather data was compared to the actual Ft. Belvoir data and it was determined that the average difference in the mean monthly temperature was less than one degree fahrenheit. It was agreed that the Washington DC data was valid and would be accepted by the COE and Ft. Belvoir.
	Stumbaugh's Comments:
	1. EYP will include page number references in the Table of Contents.
	2. EYP will replace the Installation Mission with a statement provided by Mike Stumbaugh and will change the term 'base' to 'installation' throughout the revised report.
	3. All references to FM Switch (FMS) will be changed to FM Relay (FMR) throughout the revised report. The demand savings will be estimated using a calculation which is based on the demand savings strategy described in Section 2 of the report.
	4. EYP will describe in the revised report, the probable reasons that building 3136 did not qualify for ECIP funding while building 1425 did and they are of similar construction and system type.
	5. EYP will develop further criteria for applying the results of this study to other buildings on the installation. This criteria will be explained in the Executive Summary of the revised report using tables or charts wherever possible.

Project: Ft. Belvoir EMS Study Date: 11/22/94 Page 3 of 5

Subject	Decision/Action Summary
	6. EYP will revise the term 'control information' in the second paragraph in Methodology to read 'type and condition of existing control systems'. The Washington DC weather data will be utilized and is acceptable to COE and Ft. Belvoir.
	7. EYP will describe in the Methodology section of the revised report the relative values of the features listed in the EMS Evaluation Matrix.
	8. The label AHU-1 refers to a type of unit. The drawings will remain as originally submitted.
	Hawk's Comments:
	1. The reference to the incorrect format refers mainly to the Executive Summary of the report. More specific statements are made in comment 2.
	2. The format of the executive summary as follows.
	a: Table 1 will be modified to exclude the ECIP compliance column and include a column for Total KBTU savings.  This table will also serve as the list of ECOs considered.
	b: EYP will include specific recommendations concerning the future of the existing FMR system.
	e: EYP will create a table comparing the energy savings, economic and operational merits of all three systems for each building. Following this table will be specific recommendations for each building based on the content of the table.
	f: EYP will include specific recommendations concerning the future of the existing FMR system.
	g: Becuase the main purpose of this report is to establish criteria for installation wide implementation of EMS

Project: Ft. Belvoir EMS Study Date: 11/22/94 Page 4 of 5

Subject	Decision/Action Summary
	each ECO will be treated as an individual project. Table 1 will serve as the summary of the ECO packaging.  h: None of the ECOs evaluated will qualify for ECIP funding because the cost estimates are less than \$300,000. Mike Stumbaugh indicated that other funding programs would be used. Based on this information EYP will include Life Cycle Cost Analysis Summary sheets for each recommended ECO. These summary sheets will serve as the appropriate programming documentation.  i: EYP will include Life Cycle Cost Analysis Summary Sheets for each recommended ECOs.
Electric Rate	j: EYP will develop further criteria for applying the results of this study to other buildings on the installation.  The Ft. Belvoir Utility Chief has established an equivalent electric rate of \$0.0616 /kw hr. This rate includes all demand and administrative charges in addition to the electrical consumption charges. It was previously agreed that this value would be used in all energy calculations. Subsequent to the submission of the Pre Final report it was determined that demand savings calculations could be included in the study in addition to energy consumption estimates. It was agreed that the equivalent rate was no longer valid because it includes the demand costs which were also being estimated in the demand savings calculations. Based on this information it was decided that the actual billing rate of \$0.01968/kw hr would be used for estimating electrical consumption costs.
Resubmission	EYP will resubmit the Pre Final report on January 18, 1995. EYP will deliver one copy of the report to each of the following agencies:  1. Mr. James Hawk CENAB, AE Acquisition Branch City Crescent Building 10 S. Howard Street Baltimore, Maryland 21201

Project: Ft. Belvoir EMS Study Date: 11/22/94 Page 5 of 5

Subject	Decision/Action Summary
	2. USA Garrison - Ft. Belvoir Attention Mike Stumbaugh 9430 Jackson Loop, Suite 107 Ft. Belvoir, Virginia 22060
	3. U.S. Army Corps of Engineers Mobile, Alabama (Mr. Hawk is to provide the complete address for this agency)
	All copies of the report will be in three-ring binders.
	Mr. James Hawk will process payment of an EYP invoice for 65% of the total contract amount for work completed to date.
Doviment	
Payment	



#### DEPARTMENT OF THE ARMY BALTIMORE DISTRICT, U.S. ARMY CORPS OF ENGINEERS P.O. BOX 1715

BALTIMORE, MD 21203-1715

REPLY TO ATTENTION OF

December 29, 1994

Engineering Division

Mr. David Smith
Project Manager
Einhorn, Yaffee Prescott
1000 Potomac Street, N.W.
Washington, DC 20007-3238

Dear Mr. Smith:

Reference is made to the minutes of the Prefinal Review Meeting held at Fort Belvoir, Virginia, December 6, 1994, for the Fort Belvoir Family Housing Insulation (encl 1), and EMS Study (encl 2), Contract DACA31-92D-0061, submitted to Mr. James Hawk for review.

The minutes submitted on December 5, 1994 have been reviewed and are accepted. If you have any questions, please contact Mr. James Hawk at 410-962-6704.

Sincerely,

Encls

Stanléy N. Block, P.E. Chief, Military Branch

## Project Name: Ft. Belvoir EMS Study **Minutes of Meeting** Project Number: 60692.00 Date of Meeting: To: 6-1-95 Mr. James Hawk Time0of Meeting: CENAB AE Acquisition Branch 10:30 a.m. 10 S. Howard Street Location of Meeting: Baltimore, MD 21201 Ft. Belvoir Building 1442 COE Project No. DACA31-92-D-0061 Meeting Number: Delivery Order No. 0004 5 Purpose of Meeting: To review comments on revised Pre-Final submission. Representing: Attendees: **COE** - Baltimore District Jim Hawk DPW - Ft. Belvoir Wayne Stone DPW - Ft. Belvoir John Strang **David Smith** Einhorn Yaffee Prescott Einhorn Yaffee Prescott Julius Stone The following constitutes my understanding of the items discussed and the decisions reached. If there are any additions or corrections, please contact the undersigned: Attendees Tony Battaglia, COE - Mobile District

Project: Ft. Belvoir EMS Study Date: 6-1-95 Page 2 of 9

Subject	Decision/Action Summary
	The following are our responses to the Prefinal review comments for this project:
Comments From Stumbaugh Comment No.1:	1. A "Purpose" section should precede the Executive Summary. The purpose section found on Page II-1 would be appropriate. 2. There appears to be seven mission elements. 3. The third paragraph should be removed. 4. Throughout the text, "Installation" should be capitalized when referring to Fort Belvoir. 5. Executive Order 12902. 6. FY should be placed in front of 1985 and 2005.
EYP Response:	The Purpose section from Page II-1 will be copied and inserted into the Introduction section of the Executive Summary. The third paragraph of the Executive Summary will be removed. The term "Installation" will be capitalized throughout the report. The Executive Order will be referred to as Executive Order 12902. FY will be placed in front of 1985 and 2005.
Comment No. 2: \square	The * appears unnecessary. If Building 1425 is to come under true DDC, then the vendor will still have to replace almost all of the existing components, with the exception of the wiring. There will still be a significant cost for the central building controller and associated compatible components. A DDC for 1425 may not be as expensive as starting from scratch, but it would still be a real cost and a valid project to connect 1425 to the central system.
EYP Response:	The * is necessary because the savings and payback estimates are based on a baseline condition with no time of day scheduling control. Building 1425 is currently equipped with a control system capable of time of day scheduling.
Comment No. 3:	In some cases, real energy savings could be achieved with FMR. The AC for a small building with a significant unoccupied period could simply be turned off at night in the summer and shoulder months. The problem generally is lack of feedback. Full pump-down would have to be incorporated in the FMR to safeguard the system.
	·

Project: Ft. Belvoir EMS Study Date: 6-1-95 Page 3 of 9

Subject	Decision/Action Summary
Gubject	Devision Politically
EYP Response:	Buildings with extended unoccupied periods could be effectively controlled using the FMS. This is only recommended for buildings with a set schedule or where operating personnel can be notified in advance of changes in the occupancy schedule. This information will be included in the Executive Summary.
Comment No. 4:	1. There should be an FY in front of 1985 and 2000. 2. The following sentence should be changed: "For this reason the control system reliability will be significantly increased for two reasons."
EYP Response:	FY will be added in front of 1985 and 2000. "for two reasons" will be changed to "in two ways."
Comment No.5:	1. Building 3136 analysis: do you have the costs associated with fixing the system and installing a DDC at the same time? Would this project meet ECIP criteria? 2. Under ECIP projects developed, present simple payback and installed cost along with SIR. 3. The last sentence on the page should start with "Another" instead of "Other".
EYP Response:	The economic analysis of repair/replacement of the existing HVAC system is beyond the Scope of Work for this project. The sentence will be changed to begin with "another" in lieu of "other".
Comment No. 6:	Remember to capitalize "Installation" throughout the document.
EYP Response:	"Installation" will be capitalized throughout the report.
Comment No. 7:	1. Arrowheads should be placed on all the path lines. 2. Ensure that all the interrogatives end in question marks. 3. Is there any way to work in building size and/or consumption as an initial criteria on this flowchart (e.g., Is the building > 10,000 sf and have an annual heating consumption > 1,000 gallons?)
EYP Response:	Arrowheads will be added and, all interrogatives will be changed to end in a question mark. No relationship between building size or consumption and payback could be found in the extrapolation of data from this study.

Project: Ft. Belvoir EMS Study Date: 6-1-95 Page 4 of 9

Subject	Decision/Action Summary
Juajube	
Comment No. 8:	<ol> <li>Simple payback should be recorded to one decimal place. 2.     "Total Energy Savings KBTU" should be "Total Annual Energy Savings KBTU".</li> </ol>
EYP Response:	Simple payback will be recorded to one decimal place. The "Total Energy Savings KBTU" column head will be changed to read "Total Annual Energy Savings".
Comment No. 9:	1. Check (BOD Oct 1994) - What does BOD stand for? 2. Check the 2.I. line and ensure that the MBTU/Yr. Savings is totaled. 3. check these items for each ECIP form.
EYP Response:	BOD is a typographical error. The line should read October 1994. The line 2.I. will be checked for all ECIP sheets and changes will be made where necessary.
Comments From Battaglia/Woodruff:	
Comment No. 1: \((General)\)	When tables are referenced in the text of the study the location of the table should be given. An example of this is on Page 1-6 of the Executive Summary in the last paragraph.
EYP Response:	All references to tables will be changed to include the page number of the table referenced.
Comment No. 2: (General)	The study contains numerous instances where words have been deleted or added to the text. Some examples of this are: Page 1-5, Paragraph 4, line three, the word "in" should be inserted between the words actuators and each. On Page 1-7 in the last line of the first complete paragraph, the work "must" has been added.
EYP Response:	The report will be reviewed for words deleted or added to the text and corrections will be made where necessary.
Comment No. 3: $$ (Ex. Sum. P. I-6)	The text of the first complete paragraph of this page describes what would be a good FEMP project.

Project: Ft. Belvoir EMS Study Date: 6-1-95 Page 5 of 9

	Design (Action (Action )
Subject	Decision/Action Summary
EYP Response:	This may indeed qualify for FEMP funding; however economic analysis of this type of mechanical upgrade and/or replacement is beyond the scope of this study.
Comment No.4: (Ex. Sum. P. I-9)	The first sentence on this page presents an impossibility. If the systems do not have a payback they cannot be recommended.
EYP Response:	A stated goal of this project was to recommend control strategies to be applied to the entire installation. For this reason, conclusions where derived using subjective as well as objective economic analysis. While it is true that the recommended system does not provide a payback for this building, it does add significantly to the energy and total economic savings installation-wide. The FMR system will be described as the best economic alternative.
Comment No. 5: (Ex. Sum. P. I-18)	Under investment cost 5.5% should be shown for SIOH and 6% should be used for the design cost. This applies to the other economic calculations as well.
EYP Response:	Design costs and SIOH will be added as instructed.
Comment No. 6: (Ex. Sum. P. I-18)	The ECIP Guidance requires a discount rate of 3.1% for the demand savings discount factor.
EYP Response:	As stated in a previous review comment response, the FEMP or ECIP discounted factor is listed as 3.1% in the "Energy Prices and Discount Factors for Life-Cycle Cost Analysis 1994" as compiled by the National Institute of Standards and Technology for the United States Department of Energy. This same standard recommends that a 4.0% discount factor be used for study periods up to 10 years. The ECIP Guidelines utilize a discount factor of 4.0% to establish the energy price escalation factors. The COE must advise EYP as to the actual discount rate which is to be applied to this study.
Comment No. 7: ./ (General)	LCCA summary sheets should be provided for each alternative evaluated.

Project: Ft. Belvoir EMS Study Date: 6-1-95 Page 6 of 9

Decision/Action Community
Decision/Action Summary
Section 7.6.2 of the Scope of Work for this project requires that LCCA Summary Sheets be provided for all recommended projects. The LCCA output sheets are provided for all investigated ECOS in Section III of the report.
In regard to the Energy Management System Evaluation Matrix, there should be some backup calculations to support the assigned values, or this approach should be abandoned in favor of one that evaluates each of the application programs for each of the building investigated.
The assigned values for this matrix are explained in Section II of the report. It is meant to compare in a relative analysis, the different capabilities of the system being studied.
The matrix was developed in conjunction with Ft. Belvoir personnel and was modified over the course of this study to satisfy their requirement to quantify some of the subjective advantages of these three very different systems. The matrix is only one of the tools used to evaluate the systems.
The figure referenced in the second paragraph should be 2.2 not 2.1. Figure 2.2 on the following page is not dark enough.
The reference to Figure 2.1 on Page II-5 will be changed to Figure 2.2. Figure 2.2 will be darkened so that it is readable.
The whole description of Direct Digital Control EMS systems is superficial. TM5-815-2 requirements should be discussed.
The Scope of Work Appendix A, Section B requires a description of products and systems. Section II.C provides a description of the systems studied, in order to give the reader a simplified understanding of the functions and capabilities of each system. The DDC system description provides the reader with an overview of the systems available in the marketplace today.
Are the values at the bottom of this page measured or nameplate values?

Project: Ft. Belvoir EMS Study Date: 6-1-95 Page 7 of 9

Subject	Decision/Action Summary
EYP Response:	The values used in all demand savings calculations are nameplate data collected and shown on the equipment data sheet. All ampere ratings are full load values.
Comment No. 12: \(\square\) (Vol. 1, P. III-2)	The Power Factor used in this calculation looks low. Is there some backup data to show where it came from?
EYP Response:	The power factor value utilized in the demand savings calculations was an assumption based on a comparison of catalog data for similar model air cooled packaged chillers. Catalog data will be included in the Appendix along with calculation.
Comment No. 13: (Vol. 1, P. III-4)	The list on this page lists the points but not the applications. The applications should be listed and must agree with the HAP in Appendix C.
EYP Response:	The application of the controllers in the proposed system is described in the text preceding the point lists. This application data and the points list match the system modeled in the HAP which is described in Appendix C. This point will be explained in the methodology section of the report.
Comment No. 14: \(\sqrt{Vol. 1, P. III-9}\)	The Discount rate should be 3.1% not 4.0%.
EYP Response:	See Comment 6 response.
Comment No. 15: \(\sqrt{Vol. 1, P. III-9}\)	Demand is being treated as an energy expenditure which would use one type of PW discount factor. However demand should be treated as an annually recurring non-energy savings, which uses a different type of PW discount factor.
EYP Response:	"Building Life Cycle Cost" BLCC 4.0 from NIST was used for all LCCA calculations. The demand costs were entered in the appropriate field and the program automatically applies the correct discount rate for each type of expense. See Appendix E for program inputs. The Life Cycle Cost Analysis Summary Sheets in Section I for the recommended projects use the discount rates specified in the ECIP criteria.

Project: Ft. Belvoir EMS Study Date: 6-1-95 Page 8 of 9

Subject	Decision/Action Summary
Comment No. 16: (Vol. 1, P. III-24)	What appears to be missing is the calculations that show how the values shown in this table were obtained. We know that the Carrier HAP Program was used to do the calculations about how did the input for this case vary from that of the base case in order to account for all of the applications? This comment is applicable to all of the ECO Building Simulation Results.
EYP Response:	The Input Data for the Carrier E20-II Program is shown in Appendix C and reflects the applications of the different systems described for each in Section II for each analysis.
Comment No. 17: √ (Vol. 1, P. III-24)	The top paragraph on this page tries to justify DDC even though DDC has no SIR
EYP Response:	Refer to Comment 4 response.
Comment No. 18: (Vol. 1, P. C-4)	The lighting operating schedule does not look realistic. There realistically would not be 100% lighting for 12 hours on Saturday and 10 hours on Sunday.
EYP Response:	Building 200 is a recreation facility, the hours for the lighting and people occupancy reflect the posted hours of operation for this facility.
Comment No. 19 \( (Vol. 1, P. C-40)	Why are you allowing cooling and heating overlap? Is this the reason for higher annual cooling loads shown on Page D-5?
EYP Response:	This building utilizes a four pipe system which will allow for simultaneous operation of the heating and cooling systems. The input is correct for the PLC and DDC models. It is incorrect however for the base building model. The base building model will be corrected and the calculations will be performed again.
Comment No. 20: (Vol. 1, P. C-52)	Is the heating and cooling overlap shown in this schedule the reason for the annual cooling coil load on Page D-7 being greater than for the base case shown on Page D-3?
EYP Response:	See Comment 19 response.

Project: Ft. Belvoir EMS Study Date: 6-1-95 Page 9 of 9

Subject	Decision/Action Summary
Comment No. 21: (Vol. 1, P. C-80)	Explain why part-load efficiency is the same as full load capacity.
EYP Response:	The burner on this boiler has a single fixed firing rate. For this reason the part load efficiency "equals" the full load efficiency. The inputs for the other ECOs will be checked and corrected as necessary to reflect this condition.
Comment No. 22: (Vol. 1, P. C-82)	The part-load performance data in this table looks more realistic than that shown for the base case. What effect would PLC have on the boiler efficiency at part load.
EYP Response:	See Comment 21 response.
Comment No. 23: (Vol. 1, P. G-7)	Why are there two Honeywell price quotes for Building 200?
EYP Response:	The third price quote is actually from Andover; this typographical error will be corrected. It will have no effect on the results of the study.
Acceptance of Submission:	Mr. Hawk stated that the Pre-Final Submission was accepted as noted.
Payment:	Mr. Smith is to submit an invoice for 90% and Mr. Hawk will process this invoice for payment.
Final Submission:	COE is to provide information concerning discount factors and all revisions will be made as described above. Wayne Stone and John Strang from Ft. Belvoir are to provide copies of the programming documentation necessary for funding. After receipt of this information, EYP will complete the Final Submission and submit it to COE.
•	N:\60692.00\MINUTES\95-5-F16.WPD
<b>\</b>	

# APPENDIX K MISCELLANEOUS CALCULATIONS

Einhorn Yaffee	
Prescott  ARCHITECTURE & ENGINEERING, PC.	U

PROJECT NATE TO BELLIDER LMS CON	Access = 2 3/2 22
Calculated by	Date8/16/95
Checked by	Date
Scale	Sheet No of

SAMPLE CALCULATION TO ESTABLISH APPROXIMATE FOWER LACTOR FOR NIR COOLED RECHADORING CHATER.

CATALOG THATA FOR SIMILAR CHILLER INDICATES THE FOLLOWING

- FULL LOAD AMFACITY TOR 40 TON CHILLER (PAGE K-2)

4 COMPRESSORS @ 172 AMP EACH = 68,8 + 4 FANS @ 1,8 AMP EACH = 7.2 76 AMPS FLA = 76 AMPS @ 460 V 30

- KW INPOT @ FULL COAD & 95°F ENTERING AIR (PAGE K-3)

KW = 39.6

FENER FACTOR = (V)(A)(J3) FOR THREE PHASE POWER

(@ FUL LOAD)

- 39,600 W

(460)(76)(J3)

PF = 0.65

THIS POWER FACTOR VALUE IS USED FOR ALL DEMAND LAVINGS CATCULATIONS THROUGHOUT THE KEPORT.



## **Electrical Data**

### 10-60 Tons

10



Table 31-1 — Electrical Data

			Un	it Wiring					Motor Da	ta			
	Model	Nameplate	Voltage		Max Fuse	Rec. Dual		Compressor	(Ea)		Fans (Ea)		Contro
Tons	Number	Voltage	Range	MCA	Size	Element	Qty	RLA	LRA	Qty	KW	FLA	KW
	CGA120B1	208-230/60/1	187-254	71.0	90		2	28.9	150	1	.95	6	_
	CGA120B3	208-230/60/3	187-254	48.3	60		2	18.8	118	1	.95	6	_
10	CGA120B4	460/60/3	414-506	25.2	35		2	10.0	71	1	.95	2.7	
	CGA120BW	575/60/3	518-632	17.3	20		2	6.8	43	1	.95	2.0	_
	CGA180B3	208-230/60/3	187-254	72.6	90		2	29.5	179	2	1.03	3.1	
15	CGA180B4	460/60/3	414-506	33.6	40		2	13.5	90	2	1.03	1.6	
	CGA180BW	575/60/3	518-632	26.7	35		2	10.8	72	2	1.03	1.2	_
		200-230/60/3	180-220	97	125	110	2	39.4	247	2	0.9	4.1	0.2
20	CGAD-C20	200-230/60/3	208-254	97	125	110	2	39.4	247	2	0.9	4.1	0.2
20	CGAD-C20	460/60/3	416-508	43	60	50	2	17.2	95	2	0.9	1.8	0.2
		575/60/3	520-635	33	45	40	2	13.2	76	2	0.9	1.4	0.2
		200-230/60/3	180-220	122	175	150	2	39.4,56.0	247,376	3	0.9	4.1	0.2
25	CGAD-C25	200-230/60/3	208-254	122	175	150	2	39.4,56.0	247,376	3	0.9	4.1	0.2
25	CGAD-C25	460/60/3	416-508	52	70	60	2	17.2,23.5	95,142	3	0.9	1.8	0.2
		575/60/3	520-635	41	50	45	2	13.2,18.7	76,114	3	0.9	1.4	0.2
-		200-230/60/3	180-220	139	175	175	2	56.0	376	3	0.9	4.1	0.2
30	CGAD-C30	200-230/60/3	208-254	139	175	175	2	56.0	376	3	0.9	4.1	0.2
30	CGAD-CSU	460/60/3	416-508	59	80	70	2	23.5	142	3	0.9	1.8	0.2
		575/60/3	520-635	47	60	60	2	18.7	114	3	0.9	1.4	0.2
		200-230/60/3	180-220	184	200	200	4	39.4	247	4	0.9	4.1	0.3
40	CGAD-C40	200-230/60/3	208-254	184	200	200	4	39.4	247	4	0.9	4.1	0.3
40	COAD-C40	460/60/3	416-508	81.	90	90	4	17.2	95	4	0.9	1.8	0.3
		575/60/3	520-635	62	70	70	4	13.2	76	4	0.9	1.4	0.3
		200-230/60/3	180-220	230	250	250	4	39.4,56.0	247,376	6	0.9	4.1	0.3
50	CGAD-C50	200-230/60/3	208-254	230	250	250	4	39.4,56.0	247,376	6	0.9	4.1	0.3
50	CGAD-C50	460/60/3	416-508	99	110	110	4	17.2,23.5	95,142	6	0.9	1.8	0.3
		575/60/3	520-635	77	90	90	4	13.2,18.7	76,114	6	0.9	1.4	0.3
		200-230/60/3	180-220	263	300	300	4	56.0	376	6	0.9	4.1	0.3
60	CGAD-C60	200-230/60/3	208-254	263	300	300	4	56.0	376	6	0.9	4.1	0.3
00	CGMD-C00	460/60/3	416-508	111	125	125	4	23.5	142	6	0.9	1.8	0.3
		575/60/3	520-635	88	100	100	4	18.7	114	6	0.9	1.4	0.3

- Notes:

  1. MCA: Minimum Circuit Ampacity is 125 percent of the largest compressor RLA plus 100 percent of the other compressor(s) RLA plus the sum of the condenser fan FLA per NEC 440-33.

  2. Maximum Fuse Size: 225 percent of the largest compressor RLA plus 100 percent of the other compressor(s) RLA plus the sum of the condenser fan FLA per NEC 440-22.

  3. Recommended Dual Element Fuse Size: 150 percent of the largest compressor RLA plus 100 percent of the other compressor(s) RLA plus the sum of the condenser fan FLA.

  4. RLA: Rated in accordance with UL standard 465.

- Control kw includes operational controls only. Does not include evaporator heat tape.
   All units are across the line starting. Compressors will never start simultaneously.
- An utilis are access the interesting. Confriessors will have a start simulation execution.
   S. One 115/60/1, 15 amp. jobsite provided power connection is required to operate both the unit controls and evaporator heat tape. If the optional control power transformer is ordered, one jobsite supplied 115/60/1, 15 amp. power connection is required for the evaporator heat tape. All CGA 120 and 180 units have 24-volt control power transformer provided as standard.
   All 200/230 volt units are factory set for 200 volt usage. For 230 volt usage, wiring leads on the unit transformers must be changed at the jobsite. All CGA 120 and 180 units are factory
- set for 230-volt usage, wiring leads on unit transformers must be changed at the job site.



## **Performance Data**

## 10-80 Tons **Part Load**

Table 29-1 — Part Load Data, ARI Points (10-80 Tons)

			Entering Condenser Air Temperature (Degrees F)								
Tons	Model Number	•	95 100% Load	87 80% Load	85 75% Load	79 60% Load	75 50% Load	71 40% Load	67 30% Load	65 25% Load	
10	CGA 120	EER Capacity (Tons) KW Input	9.5 8.8 10.1				11.6 4.8 4.0	_	_	_	
15	CGA 180	EER Capacity (Tons) KW Input	9.6 14.4 17.0	<u>-</u>			11.1 7.6 7.1			=	
20	CGAD-C20	EER Capacity (Tons) KW Input	9.7 18.0 20.0		=	=	13.9 10.8 7.1	- -	=		
25	CGAD-C25	EER Capacity (Tons) KW Input	9.3 22.4 25.8	<u>-</u>	_ _ _	12.5 15.3 11.6	<u>-</u>	13.7 11.2 6.7	=		
30	CGAD-C30	EER Capacity (Tons) KW Input	9.7 27.1 30.4		- -	<del>-</del>	14.0 16.0 10.6	<del>-</del> -		=	
40	CGAD-C40	EER Capacity (Tons) KW Input	9.7 35.2 39.6		11.2 28.1 25.4		14.1 21.4 14.0			15.0 10.9 6.4	
80	CGAD-C50	EER Capacity (Tons) KW Input	9.3 44.4 51.6	10.8 37.8 35.4		12.6 30.6 23.2		<del>-</del> -	14.0 15.7 10.2		
60	CGAD-C60	EER Capacity (Tons) KW Input	9.5 52.7 60.8		11.1 41.8 39.0	<u> </u>	14.1 31.9 21.2	=		15.2 16.3 9.6	
70	CGAC-C70	EER Capacity (Tons) KW Input	9.9 62.5 70.0	. <u>-</u>	10.5 50.8 52.6	_ _ _	11.8 34.3 31.8		=	13.4 21.6 16.4	
80	CGAC-C80	EER Capacity (Tons) KW Input	9.7 73.9 83.4	_	10.6 62.0 61.6	<u>-</u>	12.1 40.7 36.2	<u> </u>		13.3 25.1 18.3	

#### Notes:

Notes:

1. Table 29-1 data is rated in accordance with ARI Standard 590-81, Section 7.3.

— 44 F leaving chilled water temperature.

— (55 F + 0.4 F x % Load) = entering ambient temperature.

— Constant evaporator waterflow as determined at full load operation at 95 F ambient and 10 F evaporator temperature drop.

— % Load by compressor displacement as defined by ARI Standard 590-81.

2. Kw input is for compressors only.

3. EER = Energy Efficiency Ratio, (Btu/watt-hour). Power inputs include compressors, condenser fans and control power.

Einhorn Yaffee	
Prescott	
ARCHITECTURE & ENGINEERING, PC	

Project Name ET EE 12 K EM = 1	Project No 60692.00
Calculated by	Date 8/16/95
Checked by	
Scale	Sheet No of

TOTA ENEXGY CARCULATIONS B!	1	ENERGY.	7	TYPE
-----------------------------	---	---------	---	------

BIDG 200 - BASE & FMR (FROM PAGE D. 2)

ELECTRIC - HUAC 291599 KWh

14580 (5% SEE PAGE II-2) 306179 KWh

ELECTRIC - NON-HVAC 421743 KWh
1727922 KWh

NATURAL GAS 28480 Thorm + 1424 (5%- SEE PAGE II-2)

[29904 Therm]

BLDG 200 - PLC (FROM PAGE D.4)

ELECTRIC PURC 233536 KWh 1/677 (5% SEE PAGE II-2)

245213

421743 KWh

NATURAL GAS 21115

21115 Therm + 1056 (5%- SEE PAGE II-2)

22171 Therm

(FROM PAGE D-6)

206634 KWh

421743 KWB

BLD6 200 - DDC

ELECTRIC- HYAC

ELECTRIC - NON-HVAC

[628377 KI

NATURAL GAS 18411 Therm

Einhorn	
_Yaffee	
Prescott	
ARCHITECTURE & ENGINEERING PC	

Project Name FT BELVOIR EMS STUDY	
Calculated by DUS	Date 8/16/95
Checked by	Date
Scale	Sneet No of

# TOTAL ENERGY CALCULATIONS BY ENERGY TYPE

BLDG 219 BASE & FMR

(FROM PAGE D-9)

ELECTRIC - HVAC

388008 kWh

19400 (5% SEE PAGE I.2) 407408 KWh

ELECTRIC - NON HVAC

496200 KWh 903608 KWhI

NATURAL GAS

23850 Therm + 1193 (5% SLE PAGE 11-2)

BUG 219 FIC

(FROM PAGE D-11)

ELECTRIC - HVAC

190811 KWh. <u>9541 (5%</u> SEE PAGE II.2) 200351 KWh

ELECTRIC - NON HVAC

496200 KWh

696551 KWh

NATURAL GAS

15490 Therm 775 (5% SEE PAGE II - 2) 16265 Therm

BLOG 219 DDC

(FROM PAGE D-13)

ELECTRIC - HVAC ELECTRIC - NON HYAC

181447 KWh 496200 KWh 677647 KWh

NATURAL GAS

15490 Therm

Einhorn	
Yaffee Prescott	
ARCHITECTURE & ENGINEERING PC	V

Project Name FT BELVOR EMS STORT  Calculated byPLS	63672.00
Calculated by	Date 8/16/95
Checked by	Date
Scale	Sheet No of

# TOTAL ENERGY CALCULATIONS BY ENERGY TYPE

BLDG 247 BASE & FMR

(FROM PAGE D-16)

ELECTRIC - HVAC

592897 KWh 29645 (5% SEE [RGIII] 622542 KWh

ELECTRIC - NON HYAC

1422880 Kwh 12045422 Kwh 1

NATURAL GAS

38/63 Therm
1908 6% SEE PROE #-2)
[4007] Therm]

BLDG 247 PLC

(FROM PAGE D-18)

ELECTRIC - MYAC

406978 KWh <u>20349</u> (5 % SEE FAGE II-2) 427327 KWh

ELECTRIC - NON HVAC

1422880 KWh 11850207 KWh 1

NATURAL GAS

27010 Therm 1351 (5% SEE PAGE I.2) 28361 Therm

BLDG 247 DDC

(FROM PAGE D-20)

ELECTRIC HUAC ELECTRIC NON HUAC 404356 kWh 1422880 kWh 1827236 KWh

NATURAL GAS

27079 Therm



Project Name FT BELLIDE EMS STE	1- 100 to 60692.00
Calculated by DLS	Date 8/16/95
Checked by	Date
Scale	Sheet No of

# TOTAL ENERGY CANCULATIONS BY ENERGY TYPE

BLDG 1425 BASE & FMR

(FROM PAGE D-23)

ELECTRIC - HVAC

72273 KWh 3614 (5% SEE PAGE II-2) 75887 KWh

ELECTRIC - NON HVAC

189882 KWh 265769 KWh

DISTRICT STEAM

242,000 /b 12,100 (5% SEE PACE #1.2) 254,100 16

BLD6 1425 PKC

(FROM PAGE D-25)

ELECTRIC - HVAC

56679 KWh

2834 (5% 500 FACE II-2) 59513 Kluh

ELECTRIC - NON HVAC

189882 KWh 249395 KWh

DISTRICT STEAM

70000 16 3500 (5% SEE PAGE II-2) 73500 lb

BLDG 1425 DDC

CFROM PAGE D-27)

ELECTRIC - HVAC ELECTRIC NON HVAC

56679 KWh 189882 KWh 246561 KWh

DISTRICT STEAM

70000 lb

Einhorn Yaffee Prescott	
ARCHITECTURE & ENGINEERING PC	

Project Name ET BELVOIR EMS Study  Calculated by DLS	H= -000 60692.00
Calculated by	Date 8/16/95
Checked by	Sate
Scale	Sheet No of

Toras	FAITPG4	CALCULATIONS	134	FNITUGY	TYPE
101110	DIVERDI	Chicocarino	15/	CITCACI	, ,, ,

BLDG 3136 BASE & FMR

ELECTRIC- HVAC\_

ELECTRIC - NO HVAC

DISTRICT STEAM

BLD6 3136 PLC

ELECTRIC - HVAC

ELECTRIC - NON-HVAC

DISTRICT STEAM

BLDG 3136 DDC

ELECTRIC - HVAC ELECTRIC - NON HVAC

DISTRICT STEAM

(FROM PAGE D-30)

82975 KWh 4149 (5% SEE PAGE IT-2) 87124 KWh 256487 KWh 346101 KWh

413.000 16 20650 (5%, SEE PAGE II-2) 433650 16

(FROM PAGE D-32)

75724 KWh 3786 (5% SEE PACE II-2) 79510 KWh 256487 KWh 335997 KWh

228,000 /b 11400 (5% SEE PAGE II-2) 239,400 16

(FROM PAGE D-34)

75724 KWh 256487 KWh 332211 KWh

228,000 lb

Einhorn Yaffee	
Prescott	
ARCHITECTURE & ENGINEERING, PC	

Project Name H BELVOIR EMS STUDY	
Calculated by	Date8/17/95
Checked by	Date
Scale	Sheet No of

# CARCULATIONS FOR TOTAL ANNUAL ENERGY CONSUMPTION TABLE 4 SECTIONS

# BLOG ZOO BASE & FMR

ELECTRIC (FROM PAGE K-4) NATURAL GAS (FROM PAGE K-4)

727,922 kWh x 3.413 kBTU/kWh = 2484398 KBTU 29,904 Therm x 100 KBW/Therm = 2990400 KBTS

# BLPG 200 PLC

NATURAL GAS (FROM PAGE K-4)

ELECTRIC (FROM PAGE K-4) Idologido KWA x 3.413 KBTU/KWA = 2276355 KBTU
NATURAL GAS (FROM PAGE K-4) 22,171 Therm X 100 KBTU/Therm = 2217100 KBTU

4493455 KBTU

## BLOG ZOO DDC

ELECTRIC (FROM PAGE K-4) 628,377 kwh x 3.43 kBTO/kwh = 2144651 kBTU
NATURAL GAS (FROM PAGE K-4) 18,411 Therm x 100 kBTO/kwh = 1841100 kBTO 3985751 KBTO

# BLOG 219 BASE & FIAR

ELECTRIC (FROM PAGE K.5) 903,608 kwh x 3,415 kBTV/KWh = 3083,111 KBTV NATURAL GAS (FROM PAGE K-5) 25,043 KWh X 100 KBTO/Them = 2504,300 KBTU 5,587,411 KBTU

## BLDG 219 PLC

ELECTRIC (FROM PAGE K-5) NATURAL GAS (FROM PAGE K-5)

696,551 KWA X 3.413 KBTW/KWA = 2377,329 KBTO 16,265 Therm X 100 KBTU/Therm= 1,626,500 KBTU

4,003,829 KBTU)

## BLDG 219 DDC

ELECTRIC (FROM PAGE K-5) NATURAL GAS (FROM PAGE K-5)

677,647 Kuth x 3.413 KBTU/KWh 15,490 Therm x 100 kBTU/merm 1,549,000 kBTU

2312809 KBTU 861809 KBU

Einhorn Yaffee Prescott	
ARCHITECTURE & ENGINEERING PC	

Project Name FT BELVOIR ENS STUDY	80,000 60692,00
Calculated by	Date8/17/95
Checked by	Date
Scale	Sheet Noof

# CALCULATIONS FOR TOTAL ANNUAR ENERGY CONSUMPTION (TABLE 4 SECTION I)

## BLDG 247 BASE & FMR

ELECTRIC (FROM PAGE K-6) NATURAL GAS (FROM PAGE K-6)

20 45,422 KWh x 3,413 KBTU/KWh = 6981025 KBA 40,071 Thermx 100 KBTV/Therm = 4007100 KBTV

## BLDG 247 PLC

NATURAL GAS (FROM PAGE KG)

ELECTRIC (FROM PAGE K-G) 1,850,207 KWh X 3,413 KBTU/KWh = 6,314,757 KBTU 28,361 Tham x 100 KBTU/Therm = 2836,100 KBTU 9,159857 KBW

## PLDG 247 DDC

ELECTRIC (FROM PAGE K-6) NATURAL GAS (FROM PAGE KG)

1827,236 kWh × 3.413 kBTU/KWh = 6,236,357 kBTU
27,079 Therm × 100 kBTU/Therm = 2,707,900 kBTU 8,944,257 KBTU

BLDG 1425 BASE & FMR

ELECTRIC (FROM PAGE K-7) 265,769 KWh x 3.413 KBW/KWH = 907,070 KBTU DISTRICT STEAM (FROM PAGE K-7) 254, 100 16 x 1,340 KBTU/16 = 340,494 KBTU 1,247564 KBTU

BLDG 1425 PLC

ELECTRIC (FROM PAGE K-7) 249,395 KWh × 3413 KBTU/KWh - B51,105 KBTU
DISTRICT STEAM (FROM PAGE K-7) 73,500 /b × 1,340 KBTU/18 = 98,440 KBTU 949675 KBW

BLDG 1425 DDC 246561 KWh X 3.413 KBW/KWh = 841513 KBTU ELECTRIC (FROM PAGE K-7) 93800 KBW 70,000 16 x 1.340 KBTV/16 DISTRICT STEAM (FROM PAGE K-7) 935.313 KBTU